

BERGER EXCAVATING CONTRACTORS, INC.

EXCAVATING · GRADING · TRUCKING · SEWER AND WATER

Mr. Mike Grinnell
Lake County Public Works

October 25, 2017

Reference: Rt. 45 10" HDPE WM replacement

The following is our proposal for the above referenced project.

Watermain Installation

2 EA-10x10 Pressure Connection w/ VV- assumed 6.5' to bottom of pipe
370' of 10" DR 11 HDPE water main by HDD method- including pressure test and chlorination
MJ adaptors, DIP C153 Bends & PVC Water main to make connection to Pressure connection
Capping of existing 10" pipe with MJ Cap 5' from PC
125' Silt Fence

Lump Sum Price of: \$ 129,000.00

Exclusions:

Trench Backfill
Concrete Collars or Anchors
Disposal of existing pipe- assumed smashed and left in hole
Landscape or pavement Restoration
Traffic Control
Dirt Haul off
Performance Bond
Highway permit bonds or fees
Pressure connection deeper than above listed depths will require extra payment
Construction Entrance or Haul roads

STANDARD EXCLUSIONS:

Street sweeping for other trades, removal and replacement of unsuitable below subgrade, excessive pumping, handling of hazardous materials, demolition, removal of spoil from other trades, surveying, **soil testing**, Concrete or Asphalt Testing, permits, bonds, haul roads, snow removal, Erosion Control Inspections, Temp seeding or stabilization. Absolutely no backcharges will be accepted without notification and approval by Berger within 3 days of work.

If you have any questions, please feel free to contact me at 847-526-5457.

Respectfully,



Kyle Berger

1205 GARLAND ROAD · WAUCONDA, IL 60084

PHONE: 847-526-5457 · FAX: 847-526-4204