

## Summary of Bids Received

**Project:** Lewis Avenue - Kenosha Road Resurfacing  
**Section:** 11-00999-17-RS  
**Description:** Hot-Mix Asphalt Resurfacing  
**CPMS Pin:** B-00897  
**Let Date:** 3/20/2012

Bidder	Address	City, State, Zip	Bond	Bid Price	% Over/Under Eng. Estimate	\$ Over/Under Eng. Estimate
Peter Baker & Son Company	1349 Rockland Road	Lake Bluff, IL 60044	Bid Bond	\$3,165,980.56	-11.69%	-\$419,261.89
Curran Contracting Company	286 Memorial Court	Crystal Lake, IL 60014	Bid Bond	\$3,396,541.66	-5.26%	-\$188,700.79
Payne & Dolan, Inc.	28327 W. Route 173	Antioch, IL 60002	Bid Bond	\$3,996,923.03	11.48%	\$411,680.58
Engineer's Estimate				\$3,585,242.45		

Design	_____	IDOT(2)	_____	Contract Bidder	_____	MGB then Plan Rack	_____
Finance	_____	Bid Tab File	_____	Resident Eng.	_____	Administrative Assistant	_____
Construction	_____	Project File	_____	Request By Mail	_____	Mgr Capital Programming	_____

### Return Bid Tabulation

**Project:** Lewis Avenue - Kenosha Road Resurfacing  
**Section:** 11-00999-17-RS  
**Description:** Hot-Mix Asphalt Resurfacing  
**CPMS Pin:** B-00897  
**Let Date:** 3/20/2012

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Curran Contracting Company		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
1	20101700	SUPPLEMENTAL WATERING	20.0	UNITS	\$50.00	\$1,000.00	\$1.00	\$20.00	\$1.00	\$20.00	\$1.00	\$20.00
2	20200100	EARTH EXCAVATION	149.0	CU YD	\$50.00	\$7,450.00	\$35.00	\$5,215.00	\$46.85	\$6,980.65	\$55.75	\$8,306.75
3	20200600	EXCAVATING AND GRADING EXISTING SHOULDER	263.0	UNIT	\$45.00	\$11,835.00	\$155.30	\$40,843.90	\$422.00	\$110,986.00	\$195.00	\$51,285.00
4	35100100	AGGREGATE BASE COURSE, TYPE A	52.0	TON	\$30.00	\$1,560.00	\$55.00	\$2,860.00	\$59.15	\$3,075.80	\$35.00	\$1,820.00
5	35100500	AGGREGATE BASE COURSE, TYPE A 6"	7,109.0	SQ YD	\$10.00	\$71,090.00	\$5.00	\$35,545.00	\$5.10	\$36,255.90	\$3.00	\$21,327.00
6	35100700	AGGREGATE BASE COURSE, TYPE A 8"	1,183.0	SQ YD	\$12.00	\$14,196.00	\$6.00	\$7,098.00	\$7.00	\$8,281.00	\$5.00	\$5,915.00
7	40600100	BITUMINOUS MATERIALS (PRIME COAT)	42,940.0	GAL	\$1.00	\$42,940.00	\$0.01	\$429.40	\$0.01	\$429.40	\$0.01	\$429.40
8	40600300	AGGREGATE (PRIME COAT)	752.0	TON	\$1.00	\$752.00	\$1.00	\$752.00	\$1.00	\$752.00	\$1.00	\$752.00
9	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	15.0	TON	\$450.00	\$6,750.00	\$472.85	\$7,092.75	\$336.10	\$5,041.50	\$450.00	\$6,750.00
10	40600635	LEVELING BINDER (MACHINE METHOD), N70	1,486.0	TON	\$62.50	\$92,875.00	\$65.00	\$96,590.00	\$71.50	\$106,249.00	\$67.30	\$100,007.80
11	40600990	TEMPORARY RAMP	1,929.0	SQ YD	\$25.00	\$48,225.00	\$12.05	\$23,244.45	\$10.90	\$21,026.10	\$8.00	\$15,432.00
12	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	17,004.0	TON	\$55.00	\$935,220.00	\$55.00	\$935,220.00	\$65.50	\$1,113,762.00	\$54.55	\$927,568.20
13	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	11,102.0	TON	\$62.50	\$693,875.00	\$79.35	\$880,943.70	\$76.50	\$849,303.00	\$70.15	\$778,805.30
14	42001300	PROTECTIVE COAT	1,610.0	SQ YD	\$2.00	\$3,220.00	\$1.50	\$2,415.00	\$1.50	\$2,415.00	\$1.00	\$1,610.00
15	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	1,844.0	SQ FT	\$6.00	\$11,064.00	\$5.25	\$9,681.00	\$5.25	\$9,681.00	\$4.35	\$8,021.40
16	42400800	DETECTABLE WARNINGS	194.0	SQ FT	\$30.00	\$5,820.00	\$21.00	\$4,074.00	\$21.00	\$4,074.00	\$25.00	\$4,850.00
17	44000157	HOT-MIX ASPHALT SURFACE REMOVAL 2"	14,527.0	SQ YD	\$4.00	\$58,108.00	\$2.10	\$30,506.70	\$2.00	\$29,054.00	\$2.40	\$34,864.80
18	44000164	HOT-MIX ASPHALT SURFACE REMOVAL 3 3/4"	97,450.0	SQ YD	\$4.00	\$389,800.00	\$2.70	\$263,115.00	\$2.55	\$248,497.50	\$2.45	\$238,752.50
19	44000200	DRIVEWAY PAVEMENT REMOVAL	8,292.0	SQ YD	\$7.00	\$58,044.00	\$4.00	\$33,168.00	\$4.40	\$36,484.80	\$4.00	\$33,168.00

### Return Bid Tabulation

**Project:** Lewis Avenue - Kenosha Road Resurfacing  
**Section:** 11-00999-17-RS  
**Description:** Hot-Mix Asphalt Resurfacing  
**CPMS Pin:** B-00897  
**Let Date:** 3/20/2012

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Curran Contracting Company		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
20	44000500	COMBINATION CURB AND GUTTER REMOVAL	1,800.0	FOOT	\$6.00	\$10,800.00	\$8.90	\$16,020.00	\$8.90	\$16,020.00	\$3.50	\$6,300.00
21	44000600	SIDEWALK REMOVAL	493.0	SQ FT	\$4.00	\$1,972.00	\$1.60	\$788.80	\$1.60	\$788.80	\$2.00	\$986.00
22	44201785	CLASS D PATCHES, TYPE I, 12 INCH	587.0	SQ YD	\$40.00	\$23,480.00	\$35.00	\$20,545.00	\$62.50	\$36,687.50	\$30.00	\$17,610.00
23	44201789	CLASS D PATCHES, TYPE II, 12 INCH	881.0	SQ YD	\$40.00	\$35,240.00	\$35.00	\$30,835.00	\$53.75	\$47,353.75	\$30.00	\$26,430.00
24	44201794	CLASS D PATCHES, TYPE III, 12 INCH	2,642.0	SQ YD	\$40.00	\$105,680.00	\$35.00	\$92,470.00	\$51.35	\$135,666.70	\$30.00	\$79,260.00
25	44201796	CLASS D PATCHES, TYPE IV, 12 INCH	1,761.0	SQ YD	\$40.00	\$70,440.00	\$35.00	\$61,635.00	\$46.65	\$82,150.65	\$30.00	\$52,830.00
26	44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	12,076.0	SQ YD	\$1.50	\$18,114.00	\$1.40	\$16,906.40	\$1.39	\$16,785.64	\$1.53	\$18,476.28
27	48100100	AGGREGATE SHOULDERS, TYPE A	4,517.0	TON	\$25.00	\$112,925.00	\$15.00	\$67,755.00	\$18.80	\$84,919.60	\$21.00	\$94,857.00
28	50105220	PIPE CULVERT REMOVAL	52.0	FOOT	\$10.00	\$520.00	\$85.00	\$4,420.00	\$85.00	\$4,420.00	\$20.00	\$1,040.00
29	56109210	WATER VALVES TO BE ADJUSTED	6.0	EACH	\$500.00	\$3,000.00	\$354.00	\$2,124.00	\$354.00	\$2,124.00	\$355.00	\$2,130.00
30	60260100	INLETS TO BE ADJUSTED	22.0	EACH	\$500.00	\$11,000.00	\$404.00	\$8,888.00	\$404.00	\$8,888.00	\$404.00	\$8,888.00
31	60603900	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12 (ABUTTING EXISTING PAVEMENT)	400.0	FOOT	\$30.00	\$12,000.00	\$21.00	\$8,400.00	\$21.00	\$8,400.00	\$21.00	\$8,400.00
32	60605100	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	1,400.0	FOOT	\$30.00	\$42,000.00	\$27.80	\$38,920.00	\$27.80	\$38,920.00	\$22.50	\$31,500.00
33	67100100	MOBILIZATION	1.0	L SUM	\$76,300.00	\$76,300.00	\$235,000.00	\$235,000.00	\$500,000.00	\$500,000.00	\$189,132.00	\$189,132.00
34	70300100	SHORT TERM PAVEMENT MARKING	127,871.0	FOOT	\$0.10	\$12,787.10	\$0.01	\$1,278.71	\$0.28	\$35,803.88	\$0.01	\$1,278.71
35	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	1,322.0	SQ FT	\$0.10	\$132.20	\$0.01	\$13.22	\$1.00	\$1,322.00	\$0.01	\$13.22
36	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	57,250.0	FOOT	\$0.10	\$5,725.00	\$0.01	\$572.50	\$0.20	\$11,450.00	\$0.01	\$572.50
37	70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	49,738.0	FOOT	\$0.10	\$4,973.80	\$0.01	\$497.38	\$0.22	\$10,942.36	\$0.01	\$497.38
38	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	5,667.0	FOOT	\$0.10	\$566.70	\$0.01	\$56.67	\$0.24	\$1,360.08	\$0.01	\$56.67

### Return Bid Tabulation

**Project:** Lewis Avenue - Kenosha Road Resurfacing  
**Section:** 11-00999-17-RS  
**Description:** Hot-Mix Asphalt Resurfacing  
**CPMS Pin:** B-00897  
**Let Date:** 3/20/2012

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Curran Contracting Company		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
39	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	4,991.0	FOOT	\$0.50	\$2,495.50	\$0.01	\$49.91	\$0.60	\$2,994.60	\$0.01	\$49.91
40	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	602.0	FOOT	\$1.00	\$602.00	\$0.01	\$6.02	\$1.00	\$602.00	\$0.01	\$6.02
41	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	21,312.0	FOOT	\$0.50	\$10,656.00	\$1.00	\$21,312.00	\$0.60	\$12,787.20	\$0.01	\$213.12
42	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	1,202.0	SQ FT	\$5.00	\$6,010.00	\$4.00	\$4,808.00	\$4.00	\$4,808.00	\$3.50	\$4,207.00
43	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	52,046.0	FOOT	\$0.60	\$31,227.60	\$0.50	\$26,023.00	\$0.52	\$27,063.92	\$0.50	\$26,023.00
44	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	45,216.0	FOOT	\$0.75	\$33,912.00	\$0.65	\$29,390.40	\$0.55	\$24,868.80	\$0.55	\$24,868.80
45	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	5,099.0	FOOT	\$1.00	\$5,099.00	\$0.75	\$3,824.25	\$1.00	\$5,099.00	\$0.70	\$3,569.30
46	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	4,537.0	FOOT	\$2.00	\$9,074.00	\$1.60	\$7,259.20	\$2.00	\$9,074.00	\$1.40	\$6,351.80
47	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	547.0	FOOT	\$4.00	\$2,188.00	\$3.75	\$2,051.25	\$4.00	\$2,188.00	\$4.00	\$2,188.00
48	78001110	PAINT PAVEMENT MARKING - LINE 4"	18,082.0	FOOT	\$0.50	\$9,041.00	\$0.20	\$3,616.40	\$0.30	\$5,424.60	\$0.05	\$904.10
49	78001120	PAINT PAVEMENT MARKING - LINE 5"	39,088.0	FOOT	\$0.60	\$23,452.80	\$0.20	\$7,817.60	\$0.35	\$13,680.80	\$0.05	\$1,954.40
50	78100100	RAISED REFLECTIVE PAVEMENT MARKER	363.0	EACH	\$30.00	\$10,890.00	\$21.00	\$7,623.00	\$32.00	\$11,616.00	\$23.00	\$8,349.00
51	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	363.0	EACH	\$8.00	\$2,904.00	\$4.00	\$1,452.00	\$8.70	\$3,158.10	\$5.00	\$1,815.00
52	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	15.0	FOOT	\$20.00	\$300.00	\$20.20	\$303.00	\$35.00	\$525.00	\$20.20	\$303.00
53	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL	1.0	EACH	\$1,000.00	\$1,000.00	\$1,520.00	\$1,520.00	\$2,500.00	\$2,500.00	\$1,520.00	\$1,520.00
54	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	381.0	FOOT	\$1.00	\$381.00	\$1.10	\$419.10	\$3.00	\$1,143.00	\$1.10	\$419.10

### Return Bid Tabulation

**Project:** Lewis Avenue - Kenosha Road Resurfacing  
**Section:** 11-00999-17-RS  
**Description:** Hot-Mix Asphalt Resurfacing  
**CPMS Pin:** B-00897  
**Let Date:** 3/20/2012

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Curran Contracting Company		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
55	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	367.0	FOOT	\$1.25	\$458.75	\$1.30	\$477.10	\$3.00	\$1,101.00	\$1.30	\$477.10
56	87500600	TRAFFIC SIGNAL POST, 10 FT.	1.0	EACH	\$1,500.00	\$1,500.00	\$739.00	\$739.00	\$1,400.00	\$1,400.00	\$739.00	\$739.00
57	87800100	CONCRETE FOUNDATION, TYPE A	4.0	FOOT	\$200.00	\$800.00	\$247.50	\$990.00	\$200.00	\$800.00	\$247.50	\$990.00
58	87900200	DRILL EXISTING HANDHOLE	1.0	EACH	\$250.00	\$250.00	\$228.00	\$228.00	\$145.00	\$145.00	\$228.00	\$228.00
59	88030110	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	4.0	EACH	\$1,000.00	\$4,000.00	\$871.00	\$3,484.00	\$1,200.00	\$4,800.00	\$871.00	\$3,484.00
60	88600600	DETECTOR LOOP REPLACEMENT	2,371.0	FOOT	\$15.00	\$35,565.00	\$15.40	\$36,513.40	\$13.00	\$30,823.00	\$15.40	\$36,513.40
61	88800100	PEDESTRIAN PUSH-BUTTON	4.0	EACH	\$300.00	\$1,200.00	\$348.00	\$1,392.00	\$220.00	\$880.00	\$348.00	\$1,392.00
62	89502210	MODIFY EXISTING CONTROLLER CABINET	1.0	EACH	\$350.00	\$350.00	\$2,485.00	\$2,485.00	\$2,300.00	\$2,300.00	\$2,485.00	\$2,485.00
63	89502380	REMOVE EXISTING HANDHOLE	4.0	EACH	\$1,400.00	\$5,600.00	\$380.00	\$1,520.00	\$1,100.00	\$4,400.00	\$380.00	\$1,520.00
64	LC400100	BUTT JOINT FOR ENTRANCE RESURFACING	4,802.0	FOOT	\$8.00	\$38,416.00	\$9.20	\$44,178.40	\$0.60	\$2,881.20	\$4.00	\$19,208.00
65	LC600200	INSTALL SURVEY MONUMENTS	18.0	EACH	\$800.00	\$14,400.00	\$504.25	\$9,076.50	\$243.00	\$4,374.00	\$375.00	\$6,750.00
66	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	5,423.0	SQ YD	\$10.00	\$54,230.00	\$2.85	\$15,455.55	\$4.40	\$23,861.20	\$8.20	\$44,468.60
67	X6026800	INLETS TO BE RECONSTRUCTED (SPECIAL)	70.0	EACH	\$500.00	\$35,000.00	\$500.00	\$35,000.00	\$1,005.00	\$70,350.00	\$1,005.00	\$70,350.00
68	X6030205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	21.0	EACH	\$800.00	\$16,800.00	\$650.00	\$13,650.00	\$765.00	\$16,065.00	\$765.00	\$16,065.00
69	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	5.0	CAL MO	\$2,000.00	\$10,000.00	\$1,000.00	\$5,000.00	\$1,500.00	\$7,500.00	\$1,500.00	\$7,500.00
70	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	1.0	L SUM	\$133,600.00	\$133,600.00	\$75,000.00	\$75,000.00	\$20,000.00	\$20,000.00	\$39,888.00	\$39,888.00
71	XX006343	SEEDING (COMPLETE)	6,916.0	SQ YD	\$10.00	\$69,160.00	\$5.50	\$38,038.00	\$5.50	\$38,038.00	\$5.50	\$38,038.00
72	XX206400	MAILBOX POST	66.0	EACH	\$200.00	\$13,200.00	\$150.00	\$9,900.00	\$50.00	\$3,300.00	\$200.00	\$13,200.00
<b>Bid Total</b>						<b>\$3,585,242.45</b>		<b>\$3,396,541.66</b>		<b>\$3,996,923.03</b>		<b>\$3,165,980.56</b>

### Return Bid Details

**Project:** Lewis Avenue - Kenosha Road Resurfacing  
**Section:** 11-00999-17-RS  
**Description:** Hot-Mix Asphalt Resurfacing  
**CPMS Pin:** B-00897  
**Let Date:** 3/20/2012

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extn. Price			
1	20101700	SUPPLEMENTAL WATERING	20.0	UNITS	\$50.00	\$1,000.00	\$1.00	\$1.00	\$1.00
2	20200100	EARTH EXCAVATION	149.0	CU YD	\$50.00	\$7,450.00	\$35.00	\$55.75	\$45.87
3	20200600	EXCAVATING AND GRADING EXISTING SHOULDER	263.0	UNIT	\$45.00	\$11,835.00	\$155.30	\$422.00	\$257.43
4	35100100	AGGREGATE BASE COURSE, TYPE A	52.0	TON	\$30.00	\$1,560.00	\$35.00	\$59.15	\$49.72
5	35100500	AGGREGATE BASE COURSE, TYPE A 6"	7,109.0	SQ YD	\$10.00	\$71,090.00	\$3.00	\$5.10	\$4.37
6	35100700	AGGREGATE BASE COURSE, TYPE A 8"	1,183.0	SQ YD	\$12.00	\$14,196.00	\$5.00	\$7.00	\$6.00
7	40600100	BITUMINOUS MATERIALS (PRIME COAT)	42,940.0	GAL	\$1.00	\$42,940.00	\$0.01	\$0.01	\$0.01
8	40600300	AGGREGATE (PRIME COAT)	752.0	TON	\$1.00	\$752.00	\$1.00	\$1.00	\$1.00
9	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	15.0	TON	\$450.00	\$6,750.00	\$336.10	\$472.85	\$419.65
10	40600635	LEVELING BINDER (MACHINE METHOD), N70	1,486.0	TON	\$62.50	\$92,875.00	\$65.00	\$71.50	\$67.93
11	40600990	TEMPORARY RAMP	1,929.0	SQ YD	\$25.00	\$48,225.00	\$8.00	\$12.05	\$10.32
12	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	17,004.0	TON	\$55.00	\$935,220.00	\$54.55	\$65.50	\$58.35
13	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	11,102.0	TON	\$62.50	\$693,875.00	\$70.15	\$79.35	\$75.33
14	42001300	PROTECTIVE COAT	1,610.0	SQ YD	\$2.00	\$3,220.00	\$1.00	\$1.50	\$1.33
15	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	1,844.0	SQ FT	\$6.00	\$11,064.00	\$4.35	\$5.25	\$4.95
16	42400800	DETECTABLE WARNINGS	194.0	SQ FT	\$30.00	\$5,820.00	\$21.00	\$25.00	\$22.33
17	44000157	HOT-MIX ASPHALT SURFACE REMOVAL 2"	14,527.0	SQ YD	\$4.00	\$58,108.00	\$2.00	\$2.40	\$2.17

### Return Bid Details

**Project:** Lewis Avenue - Kenosha Road Resurfacing  
**Section:** 11-00999-17-RS  
**Description:** Hot-Mix Asphalt Resurfacing  
**CPMS Pin:** B-00897  
**Let Date:** 3/20/2012

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
18	44000164	HOT-MIX ASPHALT SURFACE REMOVAL 3 3/4"	97,450.0	SQ YD	\$4.00	\$389,800.00	\$2.45	\$2.70	\$2.57
19	44000200	DRIVEWAY PAVEMENT REMOVAL	8,292.0	SQ YD	\$7.00	\$58,044.00	\$4.00	\$4.40	\$4.13
20	44000500	COMBINATION CURB AND GUTTER REMOVAL	1,800.0	FOOT	\$6.00	\$10,800.00	\$3.50	\$8.90	\$7.10
21	44000600	SIDEWALK REMOVAL	493.0	SQ FT	\$4.00	\$1,972.00	\$1.60	\$2.00	\$1.73
22	44201785	CLASS D PATCHES, TYPE I, 12 INCH	587.0	SQ YD	\$40.00	\$23,480.00	\$30.00	\$62.50	\$42.50
23	44201789	CLASS D PATCHES, TYPE II, 12 INCH	881.0	SQ YD	\$40.00	\$35,240.00	\$30.00	\$53.75	\$39.58
24	44201794	CLASS D PATCHES, TYPE III, 12 INCH	2,642.0	SQ YD	\$40.00	\$105,680.00	\$30.00	\$51.35	\$38.78
25	44201796	CLASS D PATCHES, TYPE IV, 12 INCH	1,761.0	SQ YD	\$40.00	\$70,440.00	\$30.00	\$46.65	\$37.22
26	44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	12,076.0	SQ YD	\$1.50	\$18,114.00	\$1.39	\$1.53	\$1.44
27	48100100	AGGREGATE SHOULDERS, TYPE A	4,517.0	TON	\$25.00	\$112,925.00	\$15.00	\$21.00	\$18.27
28	50105220	PIPE CULVERT REMOVAL	52.0	FOOT	\$10.00	\$520.00	\$20.00	\$85.00	\$63.33
29	56109210	WATER VALVES TO BE ADJUSTED	6.0	EACH	\$500.00	\$3,000.00	\$354.00	\$355.00	\$354.33
30	60260100	INLETS TO BE ADJUSTED	22.0	EACH	\$500.00	\$11,000.00	\$404.00	\$404.00	\$404.00
31	60603900	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12 (ABUTTING EXISTING PAVEMENT)	400.0	FOOT	\$30.00	\$12,000.00	\$21.00	\$21.00	\$21.00
32	60605100	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	1,400.0	FOOT	\$30.00	\$42,000.00	\$22.50	\$27.80	\$26.03
33	67100100	MOBILIZATION	1.0	L SUM	\$76,300.00	\$76,300.00	\$189,132.00	\$500,000.00	\$308,044.00
34	70300100	SHORT TERM PAVEMENT MARKING	127,871.0	FOOT	\$0.10	\$12,787.10	\$0.01	\$0.28	\$0.10
35	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	1,322.0	SQ FT	\$0.10	\$132.20	\$0.01	\$1.00	\$0.34

### Return Bid Details

**Project:** Lewis Avenue - Kenosha Road Resurfacing  
**Section:** 11-00999-17-RS  
**Description:** Hot-Mix Asphalt Resurfacing  
**CPMS Pin:** B-00897  
**Let Date:** 3/20/2012

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
36	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	57,250.0	FOOT	\$0.10	\$5,725.00	\$0.01	\$0.20	\$0.07
37	70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	49,738.0	FOOT	\$0.10	\$4,973.80	\$0.01	\$0.22	\$0.08
38	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	5,667.0	FOOT	\$0.10	\$566.70	\$0.01	\$0.24	\$0.09
39	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	4,991.0	FOOT	\$0.50	\$2,495.50	\$0.01	\$0.60	\$0.21
40	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	602.0	FOOT	\$1.00	\$602.00	\$0.01	\$1.00	\$0.34
41	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	21,312.0	FOOT	\$0.50	\$10,656.00	\$0.01	\$1.00	\$0.54
42	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	1,202.0	SQ FT	\$5.00	\$6,010.00	\$3.50	\$4.00	\$3.83
43	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	52,046.0	FOOT	\$0.60	\$31,227.60	\$0.50	\$0.52	\$0.51
44	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	45,216.0	FOOT	\$0.75	\$33,912.00	\$0.55	\$0.65	\$0.58
45	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	5,099.0	FOOT	\$1.00	\$5,099.00	\$0.70	\$1.00	\$0.82
46	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	4,537.0	FOOT	\$2.00	\$9,074.00	\$1.40	\$2.00	\$1.67
47	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	547.0	FOOT	\$4.00	\$2,188.00	\$3.75	\$4.00	\$3.92
48	78001110	PAINT PAVEMENT MARKING - LINE 4"	18,082.0	FOOT	\$0.50	\$9,041.00	\$0.05	\$0.30	\$0.18
49	78001120	PAINT PAVEMENT MARKING - LINE 5"	39,088.0	FOOT	\$0.60	\$23,452.80	\$0.05	\$0.35	\$0.20



### Return Bid Details

**Project:** Lewis Avenue - Kenosha Road Resurfacing  
**Section:** 11-00999-17-RS  
**Description:** Hot-Mix Asphalt Resurfacing  
**CPMS Pin:** B-00897  
**Let Date:** 3/20/2012

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
50	78100100	RAISED REFLECTIVE PAVEMENT MARKER	363.0	EACH	\$30.00	\$10,890.00	\$21.00	\$32.00	\$25.33
51	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	363.0	EACH	\$8.00	\$2,904.00	\$4.00	\$8.70	\$5.90
52	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	15.0	FOOT	\$20.00	\$300.00	\$20.20	\$35.00	\$25.13
53	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL	1.0	EACH	\$1,000.00	\$1,000.00	\$1,520.00	\$2,500.00	\$1,846.67
54	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	381.0	FOOT	\$1.00	\$381.00	\$1.10	\$3.00	\$1.73
55	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	367.0	FOOT	\$1.25	\$458.75	\$1.30	\$3.00	\$1.87
56	87500600	TRAFFIC SIGNAL POST, 10 FT.	1.0	EACH	\$1,500.00	\$1,500.00	\$739.00	\$1,400.00	\$959.33
57	87800100	CONCRETE FOUNDATION, TYPE A	4.0	FOOT	\$200.00	\$800.00	\$200.00	\$247.50	\$231.67
58	87900200	DRILL EXISTING HANDHOLE	1.0	EACH	\$250.00	\$250.00	\$145.00	\$228.00	\$200.33
59	88030110	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	4.0	EACH	\$1,000.00	\$4,000.00	\$871.00	\$1,200.00	\$980.67
60	88600600	DETECTOR LOOP REPLACEMENT	2,371.0	FOOT	\$15.00	\$35,565.00	\$13.00	\$15.40	\$14.60
61	88800100	PEDESTRIAN PUSH-BUTTON	4.0	EACH	\$300.00	\$1,200.00	\$220.00	\$348.00	\$305.33
62	89502210	MODIFY EXISTING CONTROLLER CABINET	1.0	EACH	\$350.00	\$350.00	\$2,300.00	\$2,485.00	\$2,423.33
63	89502380	REMOVE EXISTING HANDHOLE	4.0	EACH	\$1,400.00	\$5,600.00	\$380.00	\$1,100.00	\$620.00
64	LC400100	BUTT JOINT FOR ENTRANCE RESURFACING	4,802.0	FOOT	\$8.00	\$38,416.00	\$0.60	\$9.20	\$4.60
65	LC600200	INSTALL SURVEY MONUMENTS	18.0	EACH	\$800.00	\$14,400.00	\$243.00	\$504.25	\$374.08

### Return Bid Details

**Project:** Lewis Avenue - Kenosha Road Resurfacing  
**Section:** 11-00999-17-RS  
**Description:** Hot-Mix Asphalt Resurfacing  
**CPMS Pin:** B-00897  
**Let Date:** 3/20/2012

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
66	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	5,423.0	SQ YD	\$10.00	\$54,230.00	\$2.85	\$8.20	\$5.15
67	X6026800	INLETS TO BE RECONSTRUCTED (SPECIAL)	70.0	EACH	\$500.00	\$35,000.00	\$500.00	\$1,005.00	\$836.67
68	X6030205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	21.0	EACH	\$800.00	\$16,800.00	\$650.00	\$765.00	\$726.67
69	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	5.0	CAL MO	\$2,000.00	\$10,000.00	\$1,000.00	\$1,500.00	\$1,333.33
70	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	1.0	L SUM	\$133,600.00	\$133,600.00	\$20,000.00	\$75,000.00	\$44,962.67
71	XX006343	SEEDING (COMPLETE)	6,916.0	SQ YD	\$10.00	\$69,160.00	\$5.50	\$5.50	\$5.50
72	XX206400	MAILBOX POST	66.0	EACH	\$200.00	\$13,200.00	\$50.00	\$200.00	\$133.33
<b>Bid Total</b>						<b>\$3,585,242.45</b>			