

Summary of Bids Received

Project: Fairfield Road Retaining Walls
Section: 13-00000-07-GM
Description: Rehabilitation of Fairfield Road retaining walls
CPMS Pin: B-01027
Let Date: 9/24/2013

Bidder	Address	City, State, Zip	Bond	Bid Price	% Over/Under Eng. Estimate	\$ Over/Under Eng. Estimate
Illinois Constructors Corporation	39W866 Fabyan Parkway	Elburn, IL 60119	Bid Bond	\$1,107,126.80	-22.47%	-\$320,875.00
Alliance Contractors, Inc.	1166 Lake Avenue	Woodstock, IL 60098	Bid Bond	\$1,122,687.26	-21.38%	-\$305,314.54
Lorig Construction Company	250 East Touhy Avenue	Des Plaines, IL 60018	Bid Bond	\$1,212,969.35	-15.06%	-\$215,032.45
Copenhaver Construction	75 Koppie Dr.	Gilberts, IL 60136	Bid Bond	\$1,314,417.46	-7.95%	-\$113,584.34
Kovolic Construction Co.	3721 N. Carnation	Franklin Park, IL 60131-0939	Bid Bond	\$1,676,335.00	17.39%	\$248,333.20
Engineer's Estimate				\$1,428,001.80		

Design	_____	IDOT(2)	_____	Contract Bidder	_____	MGB then Plan Rack	_____
Finance	_____	Bid Tab File	_____	Resident Eng.	_____	Administrative Assistant	_____
Construction	_____	Project File	_____	Request By Mail	_____	Mgr Capital Programming	_____

Return Bid Tabulation

Project: Fairfield Road Retaining Walls
Section: 13-00000-07-GM
Description: Rehabilitation of Fairfield Road retaining walls
CPMS Pin: B-01027
Let Date: 9/24/2013

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Alliance Contractors, Inc.		Illinois Constructors Corporation		Kovolic Construction Co.		Lorig Construction Company		Copenhaver Construction	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
1	20200100	EARTH EXCAVATION	5.00	CU YD	\$34.00	\$170.00	\$100.00	\$500.00	\$67.00	\$335.00	\$100.00	\$500.00	\$65.00	\$325.00	\$100.00	\$500.00
		EXCAVATING AND GRADING EXISTING														
2	20200600	SHOULDER	25.00	UNIT	\$685.00	\$17,125.00	\$50.00	\$1,250.00	\$1,000.00	\$25,000.00	\$200.00	\$5,000.00	\$1,250.00	\$31,250.00	\$1,100.00	\$27,500.00
3	20400800	FURNISHED EXCAVATION	28.00	CU YD	\$33.00	\$924.00	\$10.00	\$280.00	\$42.00	\$1,176.00	\$100.00	\$2,800.00	\$65.00	\$1,820.00	\$30.00	\$840.00
4	28000400	PERIMETER EROSION BARRIER	2,007.00	FOOT	\$3.00	\$6,021.00	\$2.50	\$5,017.50	\$2.50	\$5,017.50	\$25.00	\$50,175.00	\$2.50	\$5,017.50	\$2.00	\$4,014.00
5	30300112	AGGREGATE SUBGRADE IMPROVEMENT, 12"	2,409.00	sq yd	\$15.00	\$36,135.00	\$7.25	\$17,465.25	\$21.00	\$50,589.00	\$18.00	\$43,362.00	\$22.00	\$52,998.00	\$15.00	\$36,135.00
6	40600100	BITUMINOUS MATERIALS (PRIME COAT)	1,206.00	GALLON	\$2.25	\$2,713.50	\$0.01	\$12.06	\$2.00	\$2,412.00	\$5.00	\$6,030.00	\$2.00	\$2,412.00	\$0.10	\$120.60
		HOT-MIX ASPHALT SURFACE COURSE,														
7	40603335	MIX "D", N50	132.00	TON	\$86.00	\$11,352.00	\$103.00	\$13,596.00	\$98.00	\$12,936.00	\$150.00	\$19,800.00	\$98.50	\$13,002.00	\$115.00	\$15,180.00
8	42001300	PROTECTIVE COAT	320.00	SQ YD	\$2.00	\$640.00	\$0.01	\$3.20	\$2.00	\$640.00	\$5.00	\$1,600.00	\$1.00	\$320.00	\$3.00	\$960.00
		HOT-MIX ASPHALT SURFACE REMOVAL, 1														
9	44000155	1/2"	1,570.00	SQ YD	\$6.00	\$9,420.00	\$6.35	\$9,969.50	\$4.20	\$6,594.00	\$13.00	\$20,410.00	\$4.25	\$6,672.50	\$7.50	\$11,775.00
		COMBINATION CURB AND GUTTER														
10	44000500	REMOVAL	95.00	FOOT	\$15.00	\$1,425.00	\$20.00	\$1,900.00	\$15.00	\$1,425.00	\$20.00	\$1,900.00	\$3.50	\$332.50	\$10.00	\$950.00
11	44004250	PAVED SHOULDER REMOVAL	2,409.00	SQ YD	\$8.50	\$20,476.50	\$5.00	\$12,045.00	\$8.00	\$19,272.00	\$27.00	\$65,043.00	\$9.00	\$21,681.00	\$7.00	\$16,863.00
12	48203021	HOT-MIX ASPHALT SHOULDERS, 6"	2,409.00	SQ YD	\$44.00	\$105,996.00	\$44.85	\$108,043.65	\$30.25	\$72,872.25	\$60.00	\$144,540.00	\$30.50	\$73,474.50	\$49.00	\$118,041.00
13	50200100	STRUCTURE EXCAVATION	82.00	CU YD	\$35.00	\$2,870.00	\$50.00	\$4,100.00	\$115.00	\$9,430.00	\$100.00	\$8,200.00	\$150.00	\$12,300.00	\$36.00	\$2,952.00
14	50300225	CONCRETE STRUCTURES	189.60	CU YD	\$750.00	\$142,200.00	\$1,800.00	\$341,280.00	\$900.00	\$170,640.00	\$1,000.00	\$189,600.00	\$850.00	\$161,160.00	\$750.00	\$142,200.00
15	50300285	FORM LINER TEXTURED SURFACE	3,192.00	SQ FT	\$7.00	\$22,344.00	\$4.00	\$12,768.00	\$10.00	\$31,920.00	\$15.00	\$47,880.00	\$8.50	\$27,132.00	\$12.00	\$38,304.00
16	50500505	STUD SHEAR CONNECTORS	1,524.00	EACH	\$10.00	\$15,240.00	\$5.00	\$7,620.00	\$10.00	\$15,240.00	\$7.00	\$10,668.00	\$15.00	\$22,860.00	\$3.00	\$4,572.00
17	50800205	REINFORCEMENT BARS, EPOXY COATED	5,730.00	POUND	\$2.00	\$11,460.00	\$0.75	\$4,297.50	\$2.05	\$11,746.50	\$2.00	\$11,460.00	\$2.20	\$12,606.00	\$2.00	\$11,460.00
		COMBINATION CONCRETE CURB AND														
18	60605000	GUTTER, TYPE B-6.24	6.00	FOOT	\$40.00	\$240.00	\$100.00	\$600.00	\$100.00	\$600.00	\$100.00	\$600.00	\$65.00	\$390.00	\$75.00	\$450.00
		STEEL PLATE BEAM GUARD RAIL, TYPE A, 6														
19	63000001	FOOT POSTS	1,525.00	FOOT	\$22.00	\$33,550.00	\$19.85	\$30,271.25	\$23.77	\$36,249.25	\$25.00	\$38,125.00	\$24.00	\$36,600.00	\$21.00	\$32,025.00
		TRAFFIC BARRIER TERMINAL, TYPE 1														
20	63100167	(SPECIAL) TANGENT	4.00	EACH	\$2,400.00	\$9,600.00	\$2,115.00	\$8,460.00	\$2,115.00	\$8,460.00	\$3,000.00	\$12,000.00	\$2,150.00	\$8,600.00	\$2,800.00	\$11,200.00
		TRAFFIC BARRIER TERMINAL, TYPE 1														
21	63100169	(SPECIAL) FLARED	2.00	EACH	\$2,400.00	\$4,800.00	\$2,014.00	\$4,028.00	\$2,014.00	\$4,028.00	\$2,700.00	\$5,400.00	\$2,025.00	\$4,050.00	\$2,400.00	\$4,800.00
22	63200310	GUARDRAIL REMOVAL	1,700.00	FOOT	\$5.00	\$8,500.00	\$4.40	\$7,480.00	\$4.40	\$7,480.00	\$5.00	\$8,500.00	\$4.50	\$7,650.00	\$5.00	\$8,500.00
23	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	5,670.00	FOOT	\$1.00	\$5,670.00	\$1.05	\$5,953.50	\$1.00	\$5,670.00	\$2.00	\$11,340.00	\$1.05	\$5,953.50	\$1.20	\$6,804.00
24	70300530	PAVEMENT MARKING TAPE, TYPE III 5"	5,670.00	FOOT	\$1.00	\$5,670.00	\$1.30	\$7,371.00	\$1.25	\$7,087.50	\$3.00	\$17,010.00	\$1.30	\$7,371.00	\$1.50	\$8,505.00
		WORK ZONE PAVEMENT MARKING														
25	70301000	REMOVAL	4,253.00	SQ FT	\$1.00	\$4,253.00	\$1.00	\$4,253.00	\$0.01	\$42.53	\$2.00	\$8,506.00	\$1.00	\$4,253.00	\$1.20	\$5,103.60

Return Bid Tabulation

Project: Fairfield Road Retaining Walls
Section: 13-00000-07-GM
Description: Rehabilitation of Fairfield Road retaining walls
CPMS Pin: B-01027
Let Date: 9/24/2013

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Alliance Contractors, Inc.		Illinois Constructors Corporation		Kovolic Construction Co.		Lorig Construction Company		Copenhaver Construction	
					Unit Price	Extn. Price	Unit Price	Extn. Price	Unit Price	Extn. Price	Unit Price	Extn. Price	Unit Price	Extn. Price	Unit Price	Extn. Price
26	70400100	TEMPORARY CONCRETE BARRIER	1,700.00	FOOT	\$25.00	\$42,500.00	\$10.00	\$17,000.00	\$17.50	\$29,750.00	\$40.00	\$68,000.00	\$21.00	\$35,700.00	\$26.00	\$44,200.00
27	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	360.00	FOOT	\$7.00	\$2,520.00	\$17.50	\$6,300.00	\$4.00	\$1,440.00	\$15.00	\$5,400.00	\$3.00	\$1,080.00	\$15.00	\$5,400.00
28	70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	4.00	EACH	\$5,400.00	\$21,600.00	\$4,500.00	\$18,000.00	\$4,500.00	\$18,000.00	\$6,000.00	\$24,000.00	\$4,500.00	\$18,000.00	\$10,000.00	\$40,000.00
29	70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	2.00	EACH	\$2,500.00	\$5,000.00	\$2,500.00	\$5,000.00	\$2,500.00	\$5,000.00	\$3,000.00	\$6,000.00	\$2,500.00	\$5,000.00	\$2,200.00	\$4,400.00
30	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	36.00	SQ FT	\$5.00	\$180.00	\$4.00	\$144.00	\$5.00	\$180.00	\$6.00	\$216.00	\$5.00	\$180.00	\$8.00	\$288.00
31	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	6,282.00	FOOT	\$0.75	\$4,711.50	\$0.70	\$4,397.40	\$1.35	\$8,480.70	\$1.00	\$6,282.00	\$0.80	\$5,025.60	\$1.00	\$6,282.00
32	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	4,870.00	FOOT	\$0.80	\$3,896.00	\$0.90	\$4,383.00	\$1.75	\$8,522.50	\$1.50	\$7,305.00	\$1.15	\$5,600.50	\$1.00	\$4,870.00
33	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	163.00	FOOT	\$1.80	\$293.40	\$1.05	\$171.15	\$2.10	\$342.30	\$2.00	\$326.00	\$1.25	\$203.75	\$1.20	\$195.60
34	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	93.00	FOOT	\$2.50	\$232.50	\$2.10	\$195.30	\$4.20	\$390.60	\$3.00	\$279.00	\$2.50	\$232.50	\$3.00	\$279.00
35	78300100	PAVEMENT MARKING REMOVAL	4,298.00	SQ FT	\$1.30	\$5,587.40	\$1.00	\$4,298.00	\$1.00	\$4,298.00	\$2.00	\$8,596.00	\$1.00	\$4,298.00	\$1.20	\$5,157.60
36	LC200501	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	10,106.00	UNIT	\$1.00	\$10,106.00	\$1.00	\$10,106.00	\$1.00	\$10,106.00	\$1.00	\$10,106.00	\$1.00	\$10,106.00	\$0.01	\$101.06
37	LC782000	GUARDRAIL REFLECTORS	105.00	EACH	\$30.00	\$3,150.00	\$10.00	\$1,050.00	\$10.00	\$1,050.00	\$10.00	\$1,050.00	\$10.00	\$1,050.00	\$16.00	\$1,680.00
38	X5121800	PERMANENT STEEL SHEET PILING	17,768.00	SQ FT	\$42.00	\$746,256.00	\$23.50	\$417,548.00	\$25.75	\$457,526.00	\$40.00	\$710,720.00	\$24.00	\$426,432.00	\$30.00	\$533,040.00
39	X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	1.00	L SUM	\$67,845.00	\$67,845.00	\$11,300.00	\$11,300.00	\$26,998.37	\$26,998.37	\$30,000.00	\$30,000.00	\$145,000.00	\$145,000.00	\$123,000.00	\$123,000.00
40	XX006343	SEEDING (COMPLETE)	1,702.00	SQ YD	\$12.00	\$20,424.00	\$3.00	\$5,106.00	\$4.90	\$8,339.80	\$8.00	\$13,616.00	\$6.50	\$11,063.00	\$5.00	\$8,510.00
41	XX007023	STAINING CONCRETE STRUCTURES	196.00	SQ YD	\$45.00	\$8,820.00	\$30.00	\$5,880.00	\$51.00	\$9,996.00	\$90.00	\$17,640.00	\$40.00	\$7,840.00	\$20.00	\$3,920.00
42	Z0055905	TEMPORARY CONSTRUCTION FENCE	670.00	FOOT	\$3.50	\$2,345.00	\$3.20	\$2,144.00	\$3.20	\$2,144.00	\$5.00	\$3,350.00	\$3.25	\$2,177.50	\$2.00	\$1,340.00
43	Z0075498	CONCRETE RETAINING WALL REMOVAL	110.00	CU YD	\$34.00	\$3,740.00	\$10.00	\$1,100.00	\$70.00	\$7,700.00	\$300.00	\$33,000.00	\$125.00	\$13,750.00	\$200.00	\$22,000.00
Bid Total						\$1,428,001.80		\$1,122,687.26		\$1,107,126.80		\$1,676,335.00		\$1,212,969.35		\$1,314,417.46

Return Bid Details

Project: Fairfield Road Retaining Walls
Section: 13-00000-07-GM
Description: Rehabilitation of Fairfield Road retaining walls
CPMS Pin: B-01027
Let Date: 9/24/2013

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
1	20200100	EARTH EXCAVATION	5	CU YD	\$34.00	\$170.00	\$65.00	\$100.00	\$86.40
		EXCAVATING AND GRADING EXISTING							
2	20200600	SHOULDER	25	UNIT	\$685.00	\$17,125.00	\$50.00	\$1,250.00	\$720.00
3	20400800	FURNISHED EXCAVATION	28	CU YD	\$33.00	\$924.00	\$10.00	\$100.00	\$49.40
4	28000400	PERIMETER EROSION BARRIER	2,007	FOOT	\$3.00	\$6,021.00	\$2.00	\$25.00	\$6.90
5	30300112	AGGREGATE SUBGRADE IMPROVEMENT, 12"	2,409	sq yd	\$15.00	\$36,135.00	\$7.25	\$22.00	\$16.65
6	40600100	BITUMINOUS MATERIALS (PRIME COAT)	1,206	GALLON	\$2.25	\$2,713.50	\$0.01	\$5.00	\$1.82
		HOT-MIX ASPHALT SURFACE COURSE,							
7	40603335	MIX "D", N50	132	TON	\$86.00	\$11,352.00	\$98.00	\$150.00	\$112.90
8	42001300	PROTECTIVE COAT	320	SQ YD	\$2.00	\$640.00	\$0.01	\$5.00	\$2.20
		HOT-MIX ASPHALT SURFACE REMOVAL, 1							
9	44000155	1/2"	1,570	SQ YD	\$6.00	\$9,420.00	\$4.20	\$13.00	\$7.06
10	44000500	COMBINATION CURB AND GUTTER REMOVAL	95	FOOT	\$15.00	\$1,425.00	\$3.50	\$20.00	\$13.70
11	44004250	PAVED SHOULDER REMOVAL	2,409	SQ YD	\$8.50	\$20,476.50	\$5.00	\$27.00	\$11.20
12	48203021	HOT-MIX ASPHALT SHOULDERS, 6"	2,409	SQ YD	\$44.00	\$105,996.00	\$30.25	\$60.00	\$42.92
13	50200100	STRUCTURE EXCAVATION	82	CU YD	\$35.00	\$2,870.00	\$36.00	\$150.00	\$90.20
14	50300225	CONCRETE STRUCTURES	190	CU YD	\$750.00	\$142,200.00	\$750.00	\$1,800.00	\$1,060.00
15	50300285	FORM LINER TEXTURED SURFACE	3,192	SQ FT	\$7.00	\$22,344.00	\$4.00	\$15.00	\$9.90

Return Bid Details

Project: Fairfield Road Retaining Walls
Section: 13-00000-07-GM
Description: Rehabilitation of Fairfield Road retaining walls
CPMS Pin: B-01027
Let Date: 9/24/2013

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
16	50500505	STUD SHEAR CONNECTORS	1,524	EACH	\$10.00	\$15,240.00	\$3.00	\$15.00	\$8.00
17	50800205	REINFORCEMENT BARS, EPOXY COATED	5,730	POUND	\$2.00	\$11,460.00	\$0.75	\$2.20	\$1.80
18	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	6	FOOT	\$40.00	\$240.00	\$65.00	\$100.00	\$88.00
19	63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, FOOT POSTS	1,525	FOOT	\$22.00	\$33,550.00	\$19.85	\$25.00	\$22.72
20	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	4	EACH	\$2,400.00	\$9,600.00	\$2,115.00	\$3,000.00	\$2,436.00
21	63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	2	EACH	\$2,400.00	\$4,800.00	\$2,014.00	\$2,700.00	\$2,230.60
22	63200310	GUARDRAIL REMOVAL	1,700	FOOT	\$5.00	\$8,500.00	\$4.40	\$5.00	\$4.66
23	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	5,670	FOOT	\$1.00	\$5,670.00	\$1.00	\$2.00	\$1.26
24	70300530	PAVEMENT MARKING TAPE, TYPE III 5"	5,670	FOOT	\$1.00	\$5,670.00	\$1.25	\$3.00	\$1.67
25	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	4,253	SQ FT	\$1.00	\$4,253.00	\$0.01	\$2.00	\$1.04
26	70400100	TEMPORARY CONCRETE BARRIER	1,700	FOOT	\$25.00	\$42,500.00	\$10.00	\$40.00	\$22.90
27	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	360	FOOT	\$7.00	\$2,520.00	\$3.00	\$17.50	\$10.90
28	70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	4	EACH	\$5,400.00	\$21,600.00	\$4,500.00	\$10,000.00	\$5,900.00

Return Bid Details

Project: Fairfield Road Retaining Walls
Section: 13-00000-07-GM
Description: Rehabilitation of Fairfield Road retaining walls
CPMS Pin: B-01027
Let Date: 9/24/2013

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price	
					Unit Price	Extnd. Price				
29	70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	2	EACH	\$2,500.00	\$5,000.00	\$2,200.00	\$3,000.00	\$2,540.00	
30	78000100	THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS	-	36	SQ FT	\$5.00	\$180.00	\$4.00	\$8.00	\$5.60
31	78000200	THERMOPLASTIC PAVEMENT MARKING LINE 4"	-	6,282	FOOT	\$0.75	\$4,711.50	\$0.70	\$1.35	\$0.97
32	78000300	THERMOPLASTIC PAVEMENT MARKING LINE 5"	-	4,870	FOOT	\$0.80	\$3,896.00	\$0.90	\$1.75	\$1.26
33	78000400	THERMOPLASTIC PAVEMENT MARKING LINE 6"	-	163	FOOT	\$1.80	\$293.40	\$1.05	\$2.10	\$1.52
34	78000600	THERMOPLASTIC PAVEMENT MARKING LINE 12"	-	93	FOOT	\$2.50	\$232.50	\$2.10	\$4.20	\$2.96
35	78300100	PAVEMENT MARKING REMOVAL	-	4,298	SQ FT	\$1.30	\$5,587.40	\$1.00	\$2.00	\$1.24
36	LC200501	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	-	10,106	UNIT	\$1.00	\$10,106.00	\$0.01	\$1.00	\$0.80
37	LC782000	GUARDRAIL REFLECTORS	-	105	EACH	\$30.00	\$3,150.00	\$10.00	\$16.00	\$11.20
38	X5121800	PERMANENT STEEL SHEET PILING	-	17,768	SQ FT	\$42.00	\$746,256.00	\$23.50	\$40.00	\$28.65
39	X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	-	1	L SUM	\$67,845.00	\$67,845.00	\$11,300.00	\$145,000.00	\$67,259.67
40.0	XX006343	SEEDING (COMPLETE)	-	1702.0	SQ YD	12.0	20424.0	3.0	8.0	5.5

Return Bid Details

Project: Fairfield Road Retaining Walls

Section: 13-00000-07-GM

Description: Rehabilitation of Fairfield Road retaining walls

CPMS Pin: B-01027

Let Date: 9/24/2013

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
41	XX007023	STAINING CONCRETE STRUCTURES	196	SQ YD	\$45.00	\$8,820.00	\$20.00	\$90.00	\$46.20
42	Z0055905	TEMPORARY CONSTRUCTION FENCE	670	FOOT	\$3.50	\$2,345.00	\$2.00	\$5.00	\$3.33
43	Z0075498	CONCRETE RETAINING WALL REMOVAL	110	CU YD	\$34.00	\$3,740.00	\$10.00	\$300.00	\$141.00
Bid Total						\$1,428,001.80			