



HT Strenger
28915 N. Herky Drive, #101
Lake Bluff, IL 60044

Phone: (847) 234-9440
Fax: (847) 816-7832
info@htstrenger.com
www.htstrenger.com

Bill to
LAKE COUNTY FACILITIES OPERATIONS
18 N. COUNTY ST.
WAUKEGAN, IL 60085

Ship to
BABCOX JAIL
20 S. COUNTY ST.
WAUKEGAN, IL 60085

Quote #: q913255

Quote Date: 7/12/2023

Quote Expiration Date: 8/11/2023

Item	Description	Amount
Proposal	We propose to replace 90 ft. of 8" cast iron with 8" PVC on existing sewer line in basement. Pipe runs above current mechanicals and extra care will be taken to remove old pipe and install new. We will install a fiberglass tank with pumps to temp in building sewer in order to provide sewer service to building during construction. This temporary tank with house two heavy duty ejector pumps and will be piped to existing 10" discharge to street. Each pump will need 120 volt 15 amp outlets for power. This will provide a capacity of 260 GPM max discharge during construction and will also provide 200 gallons of storage for peak dumps should it be required. Once temp system is installed, we will replace main run. Once new pipe is up and tested, we will tie in new system and return building to service. We have figured for standard daytime hours along with some premium time for quiet times for switch overs. All permits/fees by others. This proposal is a NTE cost.	\$55,000.00
LABOR PLUMBER STD.	Sewer rod main 10" sewer for building - pulled back sheets, shorts, shirts and misc. debris in multiple lines. Includes all overtime	\$5,693.75

Subtotal: \$60,693.75

Tax: \$0.00

Total: \$60,693.75

Payments: \$0.00

Authorization

I hereby authorize the proposed service, repair, or replacement and agree to pay the invoiced amount upon completion. I additionally certify that I am fully authorized to authorize this work and commit to payment.

Acceptance

Sign