

**CHANGE ORDER NO. 1**

Owner: Lake County Department of Public Works

Date February 6, 2012

Project FY 2011 Facilities Painting Project

Owner's Contract No. PW 2011.040

Contractor: TECORP INC.

Date of Contract Start 10-5-11

\$ 142,333.00

You are directed to make the following changes in the Contract Documents. Description:

Repair existing cracks at Brookside and Route 120 Reservoirs.

Reason for Change Order:

Install Polyurethane grout injection to eliminate floor and wall cracks discovered during preparation in advance of protective coating application.

Days)	CONTRACT PRICE		CONTRACT TIMES (Calendar	
			To substantial completion	To final completion
Original:	\$142,333.0	Original:	3/7/2011	3/22/2012
Previous COs (ADD/DEDUCT):	\$ 0	Previous COs (ADD/DEDUCT):	_____	_____
This C.O. (ADD):	\$14,040.00	This CO (ADD/DEDUCT):	_____	_____
Contract Price with all approved Change Orders:	\$156,373.00	REVISED:	_____	_____
		Original Completion Date:	3/7/2011	3/22/2012
		Revised Completion Date:	_____	_____

The Contractor agrees that this Change Order includes any and all costs associated with or resulting from the change(s) ordered herein, including all impact, delays, and acceleration costs. Other than the dollar amount and time allowance listed above, there shall be no further time or dollar compensation as a result of this Change Order.

THIS DOCUMENT SHALL BECOME AN AMENDMENT TO THE CONTRACT AND ALL STIPULATIONS AND COVENANTS OF THE CONTRACT SHALL APPLY HERETO.

RECOMMENDED:

By: \_\_\_\_\_

Engineer (Authorized Signature)

Date

2/14/2012

APPROVED:

By: \_\_\_\_\_

Owner (Authorized Signature)

Date

2/14/2012

ACCEPTED:

By: \_\_\_\_\_

Contractor (Authorized Signature)

Date

2-06-12



2221 Muriel Court  
Joliet, Illinois 60433

Phone: 815-726-9192

Fax: 815-726-9245

Email: [nvisvardis@tecorp.us](mailto:nvisvardis@tecorp.us)

January 12, 2012

Philip Speck  
Lake County Public Works  
650 W. Winchester Road  
Libertyville, Illinois 60048

Dear Phil,

We propose the following method of repairing the existing cracks at the Brookside Reservoir and Route 120 Reservoir.

**Brookside Reservoir:** Install Polyurethane grout injection to eliminate leaks from (3) each 13.5 tank wall cracks on the east wall per manufacturer's recommendations. At total of 40 LF is figured in the lump sum price.

**Lump Sum: \$6,800.00**

**Route 120 Reservoir:** Install polyurethane grout injection to eliminate leaks 20' of floor to wall joint and 30' of cold joint seam in the floor per manufacturer's recommendations.

**Lump Sum: \$7,240.00**

Upon completion of injection process all injection fittings will be removed and holes patched.

If I could be of further assistance I can be reached on my cell 709-717-9192

Respectfully Submitted

Nick Visvardis

*A Complete Professional Coating and Lining Service*