

Summary of Bids Received

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Bidder | Address | City, State, Zip | Bond | Bid Price | % Over/Under Eng. Estimate | \$ Over/Under Eng. Estimate |
|-------------------------------|------------------------|------------------------|----------|----------------|-------------------------------|--------------------------------|
| Campanella & Sons, Inc. | 39207 N Magnetics Blvd | Wadsworth, IL 60083 | Bid Bond | \$2,610,260.43 | -23.84% | -\$817,257.67 |
| Berger Excavating Contractors | 1205 Garland Road | Wauconda, IL 60084 | Bid Bond | \$2,770,038.20 | -19.18% | -\$657,479.90 |
| Lake County Grading Company | 32901 N. IL Rte 21 | Libertyville, IL 60048 | Bid Bond | \$2,816,201.47 | -17.84% | -\$611,316.63 |
| Copenhaver Construction | 75 Koppie Dr. | Gilberts, IL 60136 | Bid Bond | \$3,374,580.34 | -1.54% | -\$52,937.76 |
| Engineer's Estimate | | | | \$3,427,518.10 | | |

| | | | | | | | |
|--------------|-------|--------------|-------|-----------------|-------|-------------------------|-------|
| Design | _____ | IDOT(2) | _____ | Contract Bidder | _____ | County Engineer | _____ |
| Finance | _____ | Bid Tab File | _____ | Resident Eng. | _____ | Mgr Capital Programming | _____ |
| Construction | _____ | Project File | _____ | Request By Mail | _____ | | |

Return Bid Tabulation

Project: Fairfield Road at Monaville Road Improvements
Section: 15-00120-06-CH
Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.
CPMS Pin: B-01184A
Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Berger Excavating Contractors | | Campanella & Sons, Inc. | | Lake County Grading Company | | Copenhaver Construction | |
|----------|----------|--|----------|-------|--------------|--------------|-------------------------------|--------------|-------------------------|--------------|-----------------------------|--------------|-------------------------|--------------|
| | | | | | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price |
| 1 | 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | 1,461.0 | UNIT | \$17.00 | \$24,837.00 | \$1.10 | \$1,607.10 | \$7.00 | \$10,227.00 | \$7.50 | \$10,957.50 | \$13.00 | \$18,993.00 |
| 2 | 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | 1,023.0 | UNIT | \$27.00 | \$27,621.00 | \$1.80 | \$1,841.40 | \$9.00 | \$9,207.00 | \$9.00 | \$9,207.00 | \$18.00 | \$18,414.00 |
| 3 | 20101100 | TREE TRUNK PROTECTION | 21.0 | EACH | \$120.00 | \$2,520.00 | \$95.00 | \$1,995.00 | \$100.00 | \$2,100.00 | \$100.00 | \$2,100.00 | \$100.00 | \$2,100.00 |
| 4 | 20101200 | TREE ROOT PRUNING | 21.0 | EACH | \$100.00 | \$2,100.00 | \$68.00 | \$1,428.00 | \$70.00 | \$1,470.00 | \$70.00 | \$1,470.00 | \$70.00 | \$1,470.00 |
| 5 | 20101300 | TREE PRUNING (1 TO 10 INCH DIAMETER) | 16.0 | EACH | \$55.00 | \$880.00 | \$25.00 | \$400.00 | \$20.00 | \$320.00 | \$20.00 | \$320.00 | \$70.00 | \$1,120.00 |
| 6 | 20101350 | TREE PRUNING (OVER 10 INCH DIAMETER) | 5.0 | EACH | \$90.00 | \$450.00 | \$45.00 | \$225.00 | \$40.00 | \$200.00 | \$40.00 | \$200.00 | \$80.00 | \$400.00 |
| 7 | 20200100 | EARTH EXCAVATION | 12,172.0 | CU YD | \$22.50 | \$273,870.00 | \$0.01 | \$121.72 | \$16.32 | \$198,647.04 | \$0.01 | \$121.72 | \$24.00 | \$292,128.00 |
| 8 | 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | 753.0 | CU YD | \$32.50 | \$24,472.50 | \$22.00 | \$16,566.00 | \$26.17 | \$19,706.01 | \$24.00 | \$18,072.00 | \$24.00 | \$18,072.00 |
| 9 | 20800150 | TRENCH BACKFILL | 840.0 | CU YD | \$50.00 | \$42,000.00 | \$30.25 | \$25,410.00 | \$46.63 | \$39,169.20 | \$0.01 | \$8.40 | \$30.00 | \$25,200.00 |
| 10 | 21001000 | GEOTECHNICAL FABRIC FOR GROUND STABILIZATION | 17,202.0 | SQ YD | \$2.00 | \$34,404.00 | \$1.35 | \$23,222.70 | \$1.67 | \$28,727.34 | \$1.50 | \$25,803.00 | \$2.00 | \$34,404.00 |
| 11 | 21101505 | TOPSOIL EXCAVATION AND PLACEMENT | 2,604.0 | CU YD | \$25.00 | \$65,100.00 | \$19.50 | \$50,778.00 | \$16.72 | \$43,538.88 | \$0.01 | \$26.04 | \$12.00 | \$31,248.00 |
| 12 | 21101805 | COMPOST FURNISH AND PLACE, 2" | 732.0 | SQ YD | \$4.00 | \$2,928.00 | \$7.10 | \$5,197.20 | \$3.57 | \$2,613.24 | \$3.50 | \$2,562.00 | \$5.00 | \$3,660.00 |
| 13 | 21301052 | EXPLORATION TRENCH 52" DEPTH | 1,479.0 | FOOT | \$20.00 | \$29,580.00 | \$0.50 | \$739.50 | \$0.01 | \$14.79 | \$0.01 | \$14.79 | \$1.00 | \$1,479.00 |
| 14 | 25000210 | SEEDING, CLASS 2A | 0.3 | ACRE | \$2,100.00 | \$630.00 | \$2,991.00 | \$897.30 | \$4,936.80 | \$1,481.04 | \$4,840.00 | \$1,452.00 | \$5,000.00 | \$1,500.00 |
| 15 | 25000310 | SEEDING, CLASS 4 | 0.5 | ACRE | \$2,100.00 | \$1,050.00 | \$2,216.00 | \$1,108.00 | \$4,936.80 | \$2,468.40 | \$4,840.00 | \$2,420.00 | \$6,000.00 | \$3,000.00 |
| 16 | 25000312 | SEEDING, CLASS 4A | 1.8 | ACRE | \$2,100.00 | \$3,780.00 | \$2,278.00 | \$4,100.40 | \$4,936.80 | \$8,886.24 | \$4,840.00 | \$8,712.00 | \$6,000.00 | \$10,800.00 |
| 17 | 25000400 | NITROGEN FERTILIZER NUTRIENT | 397.0 | POUND | \$2.00 | \$794.00 | \$3.00 | \$1,191.00 | \$1.02 | \$404.94 | \$1.00 | \$397.00 | \$1.00 | \$397.00 |
| 18 | 25000600 | POTASSIUM FERTILIZER NUTRIENT | 397.0 | POUND | \$2.00 | \$794.00 | \$3.00 | \$1,191.00 | \$1.02 | \$404.94 | \$1.00 | \$397.00 | \$1.00 | \$397.00 |
| 19 | 25000700 | AGRICULTURAL GROUND LIMESTONE | 10.0 | TON | \$135.00 | \$1,350.00 | \$100.00 | \$1,000.00 | \$10.20 | \$102.00 | \$10.00 | \$100.00 | \$400.00 | \$4,000.00 |

Return Bid Tabulation

Project: Fairfield Road at Monaville Road Improvements
Section: 15-00120-06-CH
Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.
CPMS Pin: B-01184A
Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Berger Excavating Contractors | | Campanella & Sons, Inc. | | Lake County Grading Company | | Copenhaver Construction | |
|----------|----------|---|----------|-------|--------------|--------------|-------------------------------|--------------|-------------------------|--------------|-----------------------------|--------------|-------------------------|--------------|
| | | | | | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price |
| 20 | 25100630 | EROSION CONTROL BLANKET | 21,401.0 | SQ YD | \$1.50 | \$32,101.50 | \$1.10 | \$23,541.10 | \$1.28 | \$27,393.28 | \$1.25 | \$26,751.25 | \$1.70 | \$36,381.70 |
| 21 | 25200110 | SODDING, SALT TOLERANT | 5,228.0 | SQ YD | \$1.50 | \$7,842.00 | \$8.00 | \$41,824.00 | \$10.20 | \$53,325.60 | \$10.00 | \$52,280.00 | \$10.00 | \$52,280.00 |
| 22 | 25200200 | SUPPLEMENTAL WATERING | 500.0 | UNIT | \$17.00 | \$8,500.00 | \$0.01 | \$5.00 | \$0.11 | \$55.00 | \$0.10 | \$50.00 | \$0.01 | \$5.00 |
| 23 | 28000250 | TEMPORARY EROSION CONTROL SEEDING | 443.0 | POUND | \$6.50 | \$2,879.50 | \$6.00 | \$2,658.00 | \$0.11 | \$48.73 | \$0.10 | \$44.30 | \$0.01 | \$4.43 |
| 24 | 28000305 | TEMPORARY DITCH CHECK | 222.0 | FOOT | \$15.00 | \$3,330.00 | \$6.00 | \$1,332.00 | \$12.24 | \$2,717.28 | \$12.00 | \$2,664.00 | \$15.00 | \$3,330.00 |
| 25 | 28000400 | PERIMETER EROSION BARRIER | 3,254.0 | FOOT | \$3.00 | \$9,762.00 | \$3.40 | \$11,063.60 | \$2.80 | \$9,111.20 | \$2.75 | \$8,948.50 | \$2.00 | \$6,508.00 |
| 26 | 28000510 | INLET FILTERS | 27.0 | EACH | \$160.00 | \$4,320.00 | \$152.00 | \$4,104.00 | \$142.80 | \$3,855.60 | \$140.00 | \$3,780.00 | \$80.00 | \$2,160.00 |
| 27 | 28100107 | STONE RIP RAP, CLASS A4 | 198.0 | SQ YD | \$70.00 | \$13,860.00 | \$82.00 | \$16,236.00 | \$99.00 | \$19,602.00 | \$100.00 | \$19,800.00 | \$86.00 | \$17,028.00 |
| 28 | 28200200 | FILTER FABRIC | 198.0 | SQ YD | \$6.00 | \$1,188.00 | \$2.00 | \$396.00 | \$3.00 | \$594.00 | \$1.00 | \$198.00 | \$3.00 | \$594.00 |
| 29 | 30300001 | AGGREGATE SUBGRADE IMPROVEMENT | 324.0 | CU YD | \$48.00 | \$15,552.00 | \$73.50 | \$23,814.00 | \$34.24 | \$11,093.76 | \$60.00 | \$19,440.00 | \$38.00 | \$12,312.00 |
| 30 | 30300112 | AGGREGATE SUBGRADE IMPROVEMENT 12" | 15,411.0 | SQ YD | \$20.00 | \$308,220.00 | \$14.75 | \$227,312.25 | \$13.84 | \$213,288.24 | \$20.00 | \$308,220.00 | \$12.00 | \$184,932.00 |
| 31 | 35100300 | AGGREGATE BASE COURSE, TYPE A 4" | 791.0 | SQ YD | \$9.50 | \$7,514.50 | \$7.30 | \$5,774.30 | \$6.54 | \$5,173.14 | \$8.00 | \$6,328.00 | \$6.00 | \$4,746.00 |
| 32 | 35101800 | AGGREGATE BASE COURSE, TYPE B 6" | 1,184.0 | SQ YD | \$12.00 | \$14,208.00 | \$6.00 | \$7,104.00 | \$6.93 | \$8,205.12 | \$15.00 | \$17,760.00 | \$7.00 | \$8,288.00 |
| 33 | 35102000 | AGGREGATE BASE COURSE, TYPE B 8" | 192.0 | SQ YD | \$13.50 | \$2,592.00 | \$12.50 | \$2,400.00 | \$11.88 | \$2,280.96 | \$19.00 | \$3,648.00 | \$10.00 | \$1,920.00 |
| 34 | 40200800 | AGGREGATE SURFACE COURSE, TYPE B | 152.0 | TON | \$30.00 | \$4,560.00 | \$37.00 | \$5,624.00 | \$30.00 | \$4,560.00 | \$27.00 | \$4,104.00 | \$30.00 | \$4,560.00 |
| 35 | 40201000 | AGGREGATE FOR TEMPORARY ACCESS | 1,640.0 | TON | \$26.00 | \$42,640.00 | \$1.00 | \$1,640.00 | \$0.01 | \$16.40 | \$0.01 | \$16.40 | \$22.00 | \$36,080.00 |
| 36 | 40600275 | BITUMINOUS MATERIALS (PRIME COAT) | 27,952.0 | POUND | \$0.50 | \$13,976.00 | \$0.01 | \$279.52 | \$0.01 | \$279.52 | \$0.01 | \$279.52 | \$0.02 | \$559.04 |
| 37 | 40600290 | BITUMINOUS MATERIALS (TACK COAT) | 2,796.0 | POUND | \$1.00 | \$2,796.00 | \$0.01 | \$27.96 | \$0.01 | \$27.96 | \$0.01 | \$27.96 | \$0.02 | \$55.92 |
| 38 | 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS | 2.0 | TON | \$500.00 | \$1,000.00 | \$50.00 | \$100.00 | \$51.00 | \$102.00 | \$50.00 | \$100.00 | \$55.00 | \$110.00 |
| 39 | 40600525 | LEVELING BINDER (HAND METHOD), N50 | 6.0 | TON | \$95.00 | \$570.00 | \$50.00 | \$300.00 | \$51.00 | \$306.00 | \$50.00 | \$300.00 | \$55.00 | \$330.00 |

Return Bid Tabulation

Project: Fairfield Road at Monaville Road Improvements
Section: 15-00120-06-CH
Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.
CPMS Pin: B-01184A
Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Berger Excavating Contractors | | Campanella & Sons, Inc. | | Lake County Grading Company | | Copenhaver Construction | |
|----------|----------|--|----------|-------|--------------|--------------|-------------------------------|--------------|-------------------------|--------------|-----------------------------|--------------|-------------------------|--------------|
| | | | | | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price |
| 40 | 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0 N50 | 4,595.0 | TON | \$95.00 | \$436,525.00 | \$59.25 | \$272,253.75 | \$63.09 | \$289,898.55 | \$60.30 | \$277,078.50 | \$68.03 | \$312,597.85 |
| 41 | 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | 1,424.0 | TON | \$110.00 | \$156,640.00 | \$69.00 | \$98,256.00 | \$70.79 | \$100,804.96 | \$66.65 | \$94,909.60 | \$76.34 | \$108,708.16 |
| 42 | 42001300 | PROTECTIVE COAT | 2,129.0 | SQ YD | \$2.50 | \$5,322.50 | \$2.90 | \$6,174.10 | \$1.02 | \$2,171.58 | \$0.01 | \$21.29 | \$1.00 | \$2,129.00 |
| 43 | 42300200 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH | 36.0 | SQ YD | \$55.00 | \$1,980.00 | \$70.00 | \$2,520.00 | \$73.44 | \$2,643.84 | \$60.00 | \$2,160.00 | \$67.00 | \$2,412.00 |
| 44 | 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | 275.0 | SQ FT | \$7.00 | \$1,925.00 | \$8.25 | \$2,268.75 | \$8.67 | \$2,384.25 | \$7.00 | \$1,925.00 | \$10.00 | \$2,750.00 |
| 45 | 42400800 | DETECTABLE WARNINGS | 352.0 | SQ FT | \$32.00 | \$11,264.00 | \$31.60 | \$11,123.20 | \$33.15 | \$11,668.80 | \$29.00 | \$10,208.00 | \$27.00 | \$9,504.00 |
| 46 | 44000100 | PAVEMENT REMOVAL | 9,794.0 | SQ YD | \$9.00 | \$88,146.00 | \$13.00 | \$127,322.00 | \$3.68 | \$36,041.92 | \$12.00 | \$117,528.00 | \$12.00 | \$117,528.00 |
| 47 | 44000200 | DRIVEWAY PAVEMENT REMOVAL | 725.0 | SQ YD | \$9.50 | \$6,887.50 | \$7.00 | \$5,075.00 | \$11.08 | \$8,033.00 | \$5.00 | \$3,625.00 | \$15.00 | \$10,875.00 |
| 48 | 44000500 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL | 480.0 | FOOT | \$7.00 | \$3,360.00 | \$4.00 | \$1,920.00 | \$3.57 | \$1,713.60 | \$6.00 | \$2,880.00 | \$6.00 | \$2,880.00 |
| 49 | 44213200 | SAW CUTS | 77.0 | FOOT | \$3.00 | \$231.00 | \$7.00 | \$539.00 | \$5.00 | \$385.00 | \$2.50 | \$192.50 | \$10.00 | \$770.00 |
| 50 | 44300200 | STRIP REFLECTIVE CRACK CONTROL TREATMENT | 579.0 | FOOT | \$3.00 | \$1,737.00 | \$4.25 | \$2,460.75 | \$4.34 | \$2,512.86 | \$4.25 | \$2,460.75 | \$4.67 | \$2,703.93 |
| 51 | 48101200 | AGGREGATE SHOULDERS, TYPE B | 246.0 | TON | \$13.00 | \$3,198.00 | \$41.55 | \$10,221.30 | \$42.38 | \$10,425.48 | \$41.55 | \$10,221.30 | \$45.70 | \$11,242.20 |
| 52 | 48203021 | HOT-MIX ASPHALT SHOULDERS, 6" | 29.0 | SQ YD | \$95.00 | \$2,755.00 | \$30.00 | \$870.00 | \$30.60 | \$887.40 | \$30.00 | \$870.00 | \$33.00 | \$957.00 |
| 53 | 50105220 | PIPE CULVERT REMOVAL | 284.0 | FOOT | \$14.00 | \$3,976.00 | \$18.00 | \$5,112.00 | \$4.86 | \$1,380.24 | \$20.00 | \$5,680.00 | \$40.00 | \$11,360.00 |
| 54 | 52200800 | SEGMENTAL CONCRETE BLOCK WALL | 311.0 | SQ FT | \$50.00 | \$15,550.00 | \$45.00 | \$13,995.00 | \$43.86 | \$13,640.46 | \$43.00 | \$13,373.00 | \$45.00 | \$13,995.00 |
| 55 | 54001001 | BOX CULVERT END SECTIONS, CULVERT NO. 1 | 2.0 | EACH | \$6,500.00 | \$13,000.00 | \$5,700.00 | \$11,400.00 | \$5,378.68 | \$10,757.36 | \$11,000.00 | \$22,000.00 | \$5,500.00 | \$11,000.00 |
| 56 | 54010402 | PRECAST CONCRETE BOX CULVERTS 4' X 2' | 46.0 | FOOT | \$400.00 | \$18,400.00 | \$295.00 | \$13,570.00 | \$339.81 | \$15,631.26 | \$580.00 | \$26,680.00 | \$245.00 | \$11,270.00 |
| 57 | 542A0229 | PIPE CULVERTS, CLASS A, TYPE 1 24" | 54.0 | FOOT | \$65.00 | \$3,510.00 | \$60.00 | \$3,240.00 | \$55.10 | \$2,975.40 | \$60.00 | \$3,240.00 | \$100.00 | \$5,400.00 |

Return Bid Tabulation

Project: Fairfield Road at Monaville Road Improvements
Section: 15-00120-06-CH
Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.
CPMS Pin: B-01184A
Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Berger Excavating Contractors | | Campanella & Sons, Inc. | | Lake County Grading Company | | Copenhaver Construction | |
|----------|----------|--|----------|------|--------------|--------------|-------------------------------|--------------|-------------------------|--------------|-----------------------------|--------------|-------------------------|--------------|
| | | | | | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price |
| 58 | 542A1081 | PIPE CULVERTS, CLASS A, TYPE 2 36" | 123.0 | FOOT | \$70.00 | \$8,610.00 | \$99.00 | \$12,177.00 | \$89.78 | \$11,042.94 | \$97.00 | \$11,931.00 | \$130.00 | \$15,990.00 |
| 59 | 54213657 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" | 7.0 | EACH | \$1,300.00 | \$9,100.00 | \$1,260.00 | \$8,820.00 | \$1,046.95 | \$7,328.65 | \$1,710.00 | \$11,970.00 | \$700.00 | \$4,900.00 |
| 60 | 54213660 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15" | 2.0 | EACH | \$1,500.00 | \$3,000.00 | \$1,290.00 | \$2,580.00 | \$1,134.65 | \$2,269.30 | \$1,750.00 | \$3,500.00 | \$740.00 | \$1,480.00 |
| 61 | 54213669 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24" | 2.0 | EACH | \$1,800.00 | \$3,600.00 | \$1,650.00 | \$3,300.00 | \$1,798.08 | \$3,596.16 | \$2,200.00 | \$4,400.00 | \$940.00 | \$1,880.00 |
| 62 | 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | 49.0 | FOOT | \$50.00 | \$2,450.00 | \$54.00 | \$2,646.00 | \$45.17 | \$2,213.33 | \$48.00 | \$2,352.00 | \$85.00 | \$4,165.00 |
| 63 | 550A0120 | STORM SEWERS, CLASS A, TYPE 1 24" | 23.0 | FOOT | \$70.00 | \$1,610.00 | \$79.00 | \$1,817.00 | \$115.37 | \$2,653.51 | \$66.00 | \$1,518.00 | \$97.00 | \$2,231.00 |
| 64 | 550A0340 | STORM SEWERS, CLASS A, TYPE 2 12" | 409.0 | FOOT | \$60.00 | \$24,540.00 | \$54.00 | \$22,086.00 | \$45.96 | \$18,797.64 | \$47.00 | \$19,223.00 | \$85.00 | \$34,765.00 |
| 65 | 550A0360 | STORM SEWERS, CLASS A, TYPE 2 15" | 504.0 | FOOT | \$65.00 | \$32,760.00 | \$55.00 | \$27,720.00 | \$49.29 | \$24,842.16 | \$41.00 | \$20,664.00 | \$88.00 | \$44,352.00 |
| 66 | 550A0410 | STORM SEWERS, CLASS A, TYPE 2 24" | 49.0 | FOOT | \$100.00 | \$4,900.00 | \$79.00 | \$3,871.00 | \$68.84 | \$3,373.16 | \$65.00 | \$3,185.00 | \$105.00 | \$5,145.00 |
| 67 | 55100500 | STORM SEWER REMOVAL 12" | 535.0 | FOOT | \$13.00 | \$6,955.00 | \$16.00 | \$8,560.00 | \$6.27 | \$3,354.45 | \$20.00 | \$10,700.00 | \$12.00 | \$6,420.00 |
| 68 | 55100700 | STORM SEWER REMOVAL 15" | 70.0 | FOOT | \$16.00 | \$1,120.00 | \$16.00 | \$1,120.00 | \$9.15 | \$640.50 | \$20.00 | \$1,400.00 | \$17.00 | \$1,190.00 |
| 69 | 60100060 | CONCRETE HEADWALLS FOR PIPE DRAINS | 4.0 | EACH | \$315.00 | \$1,260.00 | \$340.00 | \$1,360.00 | \$384.50 | \$1,538.00 | \$420.00 | \$1,680.00 | \$500.00 | \$2,000.00 |
| 70 | 60100905 | PIPE DRAINS 4" | 61.0 | FOOT | \$26.00 | \$1,586.00 | \$31.00 | \$1,891.00 | \$37.46 | \$2,285.06 | \$40.00 | \$2,440.00 | \$15.00 | \$915.00 |
| 71 | 60100915 | PIPE DRAINS 6" | 132.0 | FOOT | \$26.00 | \$3,432.00 | \$33.00 | \$4,356.00 | \$39.42 | \$5,203.44 | \$40.00 | \$5,280.00 | \$19.00 | \$2,508.00 |
| 72 | 60108104 | PIPE UNDERDRAINS, TYPE I, 4" | 3,944.0 | FOOT | \$5.00 | \$19,720.00 | \$3.75 | \$14,790.00 | \$3.11 | \$12,265.84 | \$3.00 | \$11,832.00 | \$10.00 | \$39,440.00 |
| 73 | 60201340 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE | 13.0 | EACH | \$3,000.00 | \$39,000.00 | \$2,800.00 | \$36,400.00 | \$2,506.01 | \$32,578.13 | \$2,350.00 | \$30,550.00 | \$2,600.00 | \$33,800.00 |
| 74 | 60218400 | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | 6.0 | EACH | \$2,200.00 | \$13,200.00 | \$2,600.00 | \$15,600.00 | \$2,488.92 | \$14,933.52 | \$2,325.00 | \$13,950.00 | \$2,600.00 | \$15,600.00 |
| 75 | 60237470 | INLETS, TYPE A, TYPE 24 FRAME AND GRATE | 10.0 | EACH | \$1,200.00 | \$12,000.00 | \$1,200.00 | \$12,000.00 | \$1,200.66 | \$12,006.60 | \$1,600.00 | \$16,000.00 | \$1,100.00 | \$11,000.00 |

Return Bid Tabulation

Project: Fairfield Road at Monaville Road Improvements
Section: 15-00120-06-CH
Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.
CPMS Pin: B-01184A
Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Berger Excavating Contractors | | Campanella & Sons, Inc. | | Lake County Grading Company | | Copenhaver Construction | |
|----------|----------|--|----------|--------|--------------|--------------|-------------------------------|--------------|-------------------------|--------------|-----------------------------|--------------|-------------------------|--------------|
| | | | | | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price |
| 76 | 60500050 | REMOVING CATCH BASINS | 2.0 | EACH | \$400.00 | \$800.00 | \$300.00 | \$600.00 | \$350.00 | \$700.00 | \$440.00 | \$880.00 | \$550.00 | \$1,100.00 |
| 77 | 60500040 | REMOVING MANHOLES | 4.0 | EACH | \$350.00 | \$1,400.00 | \$600.00 | \$2,400.00 | \$350.00 | \$1,400.00 | \$440.00 | \$1,760.00 | \$600.00 | \$2,400.00 |
| 78 | 60603800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 | 2,042.0 | FOOT | \$24.00 | \$49,008.00 | \$23.50 | \$47,987.00 | \$23.46 | \$47,905.32 | \$24.00 | \$49,008.00 | \$24.00 | \$49,008.00 |
| 79 | 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | 3,196.0 | FOOT | \$29.00 | \$92,684.00 | \$25.50 | \$81,498.00 | \$25.50 | \$81,498.00 | \$30.00 | \$95,880.00 | \$24.00 | \$76,704.00 |
| 80 | 60608300 | COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12 | 241.0 | FOOT | \$34.00 | \$8,194.00 | \$23.50 | \$5,663.50 | \$23.46 | \$5,653.86 | \$26.00 | \$6,266.00 | \$25.00 | \$6,025.00 |
| 81 | 60619600 | CONCRETE MEDIAN, TYPE SB-6.12 | 99.0 | SQ FT | \$15.00 | \$1,485.00 | \$14.50 | \$1,435.50 | \$15.30 | \$1,514.70 | \$10.00 | \$990.00 | \$17.00 | \$1,683.00 |
| 82 | 61100605 | MISCELLANEOUS CONCRETE | 0.3 | CU YD | \$1,160.00 | \$348.00 | \$1,500.00 | \$450.00 | \$2,500.00 | \$750.00 | \$3,000.00 | \$900.00 | \$3,000.00 | \$900.00 |
| 83 | 61133100 | FIELD TILE JUNCTION VAULTS, 2' DIA. | 5.0 | EACH | \$1,000.00 | \$5,000.00 | \$900.00 | \$4,500.00 | \$1,201.17 | \$6,005.85 | \$1,530.00 | \$7,650.00 | \$1,500.00 | \$7,500.00 |
| 84 | 61139800 | STORM SEWERS (SPECIAL), 4" | 545.0 | FOOT | \$20.00 | \$10,900.00 | \$28.00 | \$15,260.00 | \$29.57 | \$16,115.65 | \$28.00 | \$15,260.00 | \$40.00 | \$21,800.00 |
| 85 | 67100100 | MOBILIZATION | 1.0 | L SUM | \$183,390.00 | \$183,390.00 | \$165,000.00 | \$165,000.00 | \$63,872.08 | \$63,872.08 | \$168,000.00 | \$168,000.00 | \$188,185.00 | \$188,185.00 |
| 86 | 70106800 | CHANGEABLE MESSAGE SIGN | 45.0 | CAL MO | \$1,200.00 | \$54,000.00 | \$25.00 | \$1,125.00 | \$25.50 | \$1,147.50 | \$25.00 | \$1,125.00 | \$1,100.00 | \$49,500.00 |
| 87 | 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | 5,451.0 | FOOT | \$0.20 | \$1,090.20 | \$0.30 | \$1,635.30 | \$0.31 | \$1,689.81 | \$0.30 | \$1,635.30 | \$0.50 | \$2,725.50 |
| 88 | 72400100 | REMOVE SIGN PANEL ASSEMBLY - TYPE A | 19.0 | EACH | \$65.00 | \$1,235.00 | \$60.00 | \$1,140.00 | \$61.20 | \$1,162.80 | \$60.00 | \$1,140.00 | \$110.00 | \$2,090.00 |
| 89 | 72400200 | REMOVE SIGN PANEL ASSEMBLY - TYPE B | 1.0 | EACH | \$230.00 | \$230.00 | \$100.00 | \$100.00 | \$102.00 | \$102.00 | \$100.00 | \$100.00 | \$150.00 | \$150.00 |
| 90 | 72400310 | REMOVE SIGN PANEL - TYPE 1 | 52.0 | SQ FT | \$11.00 | \$572.00 | \$15.00 | \$780.00 | \$15.30 | \$795.60 | \$15.00 | \$780.00 | \$17.00 | \$884.00 |
| 91 | 72400320 | REMOVE SIGN PANEL - TYPE 2 | 53.0 | SQ FT | \$13.00 | \$689.00 | \$15.00 | \$795.00 | \$15.30 | \$810.90 | \$15.00 | \$795.00 | \$22.00 | \$1,166.00 |
| 92 | 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | 126.0 | SQ FT | \$6.50 | \$819.00 | \$4.00 | \$504.00 | \$4.08 | \$514.08 | \$4.00 | \$504.00 | \$5.00 | \$630.00 |
| 93 | 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | 1,610.0 | FOOT | \$1.00 | \$1,610.00 | \$1.00 | \$1,610.00 | \$1.02 | \$1,642.20 | \$1.00 | \$1,610.00 | \$1.10 | \$1,771.00 |

Return Bid Tabulation

Project: Fairfield Road at Monaville Road Improvements
Section: 15-00120-06-CH
Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.
CPMS Pin: B-01184A
Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Berger Excavating Contractors | | Campanella & Sons, Inc. | | Lake County Grading Company | | Copenhaver Construction | |
|----------|----------|---|----------|------|--------------|--------------|-------------------------------|--------------|-------------------------|--------------|-----------------------------|--------------|-------------------------|--------------|
| | | | | | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price |
| 94 | 78000500 | THERMOPLASTIC PAVEMENT MARKING - LINE 8" | 249.0 | FOOT | \$1.60 | \$398.40 | \$2.00 | \$498.00 | \$2.04 | \$507.96 | \$2.00 | \$498.00 | \$3.00 | \$747.00 |
| 95 | 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | 1,282.0 | FOOT | \$2.10 | \$2,692.20 | \$3.00 | \$3,846.00 | \$3.06 | \$3,922.92 | \$3.00 | \$3,846.00 | \$3.30 | \$4,230.60 |
| 96 | 80400100 | ELECTRIC SERVICE INSTALLATION | 1.0 | EACH | \$2,400.00 | \$2,400.00 | \$3,206.00 | \$3,206.00 | \$3,270.12 | \$3,270.12 | \$3,206.00 | \$3,206.00 | \$3,206.00 | \$3,206.00 |
| 97 | 80400200 | ELECTRIC UTILITY SERVICE CONNECTION | 1.0 | EACH | \$4,000.00 | \$4,000.00 | \$2,500.00 | \$2,500.00 | \$1.00 | \$1.00 | \$5,000.00 | \$5,000.00 | \$0.00 | \$0.00 |
| 98 | 81028220 | UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA. | 385.0 | FOOT | \$30.00 | \$11,550.00 | \$30.60 | \$11,781.00 | \$31.21 | \$12,015.85 | \$30.60 | \$11,781.00 | \$30.60 | \$11,781.00 |
| 99 | 81603000 | UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE | 3,481.0 | FOOT | \$4.50 | \$15,664.50 | \$8.30 | \$28,892.30 | \$8.47 | \$29,484.07 | \$8.30 | \$28,892.30 | \$8.30 | \$28,892.30 |
| 100 | 81702150 | ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2 | 225.0 | FOOT | \$6.50 | \$1,462.50 | \$2.50 | \$562.50 | \$2.55 | \$573.75 | \$2.50 | \$562.50 | \$2.50 | \$562.50 |
| 101 | 81800240 | AERIAL CABLE, 2-1/C NO. 8 WITH MESSENGER WIRE | 2,954.0 | FOOT | \$3.95 | \$11,668.30 | \$4.00 | \$11,816.00 | \$4.08 | \$12,052.32 | \$4.00 | \$11,816.00 | \$4.00 | \$11,816.00 |
| 102 | 82500360 | LIGHTING CONTROLLER, BASE MOUNTED, 480 VOLT, 100 AMP | 1.0 | EACH | \$8,500.00 | \$8,500.00 | \$19,984.00 | \$19,984.00 | \$20,383.68 | \$20,383.68 | \$19,984.00 | \$19,984.00 | \$19,984.00 | \$19,984.00 |
| 103 | 83060150 | LIGHT POLE, GALVANIZED STEEL, 30 FT. M.H., 15 FT. MAST ARM | 16.0 | EACH | \$4,750.00 | \$76,000.00 | \$9,188.00 | \$147,008.00 | \$9,371.76 | \$149,948.16 | \$9,188.00 | \$147,008.00 | \$9,738.00 | \$155,808.00 |
| 104 | 83057215 | LIGHT POLE, WOOD, 40 FOOT, CLASS 3, WITH 15FT MAST ARM | 16.0 | EACH | \$2,600.00 | \$41,600.00 | \$420.00 | \$6,720.00 | \$428.40 | \$6,854.40 | \$420.00 | \$6,720.00 | \$420.00 | \$6,720.00 |
| 105 | 83600300 | LIGHT POLE FOUNDATION, 30" DIAMETER | 16.0 | EACH | \$450.00 | \$7,200.00 | \$1,830.00 | \$29,280.00 | \$1,866.60 | \$29,865.60 | \$1,830.00 | \$29,280.00 | \$1,830.00 | \$29,280.00 |
| 106 | 83800105 | BREAKAWAY DEVICE, TRANSFORMER BASE, 11 1/2 INCH BOLT CIRCLE | 16.0 | EACH | \$400.00 | \$6,400.00 | \$518.00 | \$8,288.00 | \$528.36 | \$8,453.76 | \$518.00 | \$8,288.00 | \$518.00 | \$8,288.00 |
| 107 | 85000500 | MAINTENANCE OF EXISTING FLASHING BEACON INSTALLATION | 1.0 | EACH | \$1,800.00 | \$1,800.00 | \$420.00 | \$420.00 | \$428.40 | \$428.40 | \$420.00 | \$420.00 | \$420.00 | \$420.00 |
| 108 | 89502400 | REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE | 1.0 | EACH | \$950.00 | \$950.00 | \$1,680.00 | \$1,680.00 | \$1,713.60 | \$1,713.60 | \$1,680.00 | \$1,680.00 | \$1,680.00 | \$1,680.00 |

Return Bid Tabulation

Project: Fairfield Road at Monaville Road Improvements
Section: 15-00120-06-CH
Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.
CPMS Pin: B-01184A
Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Berger Excavating Contractors | | Campanella & Sons, Inc. | | Lake County Grading Company | | Copenhaver Construction | |
|----------|----------|---|----------|----------|--------------|--------------|-------------------------------|--------------|-------------------------|--------------|-----------------------------|--------------|-------------------------|--------------|
| | | | | | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price |
| 109 | B2006120 | TREE, SYRINGA PEKINENSIS MORTON (CHINA SNOW PEKING LILAC), 2 1/2" CALIPER, TREE FORM, BALLED AND BURPLAPPED | 3.0 | EACH | \$650.00 | \$1,950.00 | \$503.00 | \$1,509.00 | \$535.50 | \$1,606.50 | \$525.00 | \$1,575.00 | \$750.00 | \$2,250.00 |
| 110 | K1003679 | MULCH | 61.0 | CU YD | \$65.00 | \$3,965.00 | \$95.00 | \$5,795.00 | \$66.30 | \$4,044.30 | \$65.00 | \$3,965.00 | \$55.00 | \$3,355.00 |
| 111 | LC200051 | REJECTED LOAD TRANSPORTATION | 34.0 | LOAD | \$200.00 | \$6,800.00 | \$1.00 | \$34.00 | \$0.01 | \$0.34 | \$0.01 | \$0.34 | \$100.00 | \$3,400.00 |
| 112 | LC200100 | LANDSCAPE PERFORMANCE GUARANTEE | 1.0 | _UMP SUM | \$10,000.00 | \$10,000.00 | \$30,000.00 | \$30,000.00 | \$17,340.00 | \$17,340.00 | \$17,000.00 | \$17,000.00 | \$10,000.00 | \$10,000.00 |
| 113 | LC200321 | SHRUB, SPECIAL | 48.0 | EACH | \$75.00 | \$3,600.00 | \$126.00 | \$6,048.00 | \$66.30 | \$3,182.40 | \$65.00 | \$3,120.00 | \$150.00 | \$7,200.00 |
| 114 | LC200322 | SHRUB, SPECIAL I | 84.0 | EACH | \$75.00 | \$6,300.00 | \$119.00 | \$9,996.00 | \$66.30 | \$5,569.20 | \$65.00 | \$5,460.00 | \$150.00 | \$12,600.00 |
| 115 | LC200323 | SHRUB, SPECIAL II | 73.0 | EACH | \$75.00 | \$5,475.00 | \$111.00 | \$8,103.00 | \$66.30 | \$4,839.90 | \$65.00 | \$4,745.00 | \$150.00 | \$10,950.00 |
| 116 | LC200324 | SHRUB, SPECIAL III | 61.0 | EACH | \$75.00 | \$4,575.00 | \$111.00 | \$6,771.00 | \$66.30 | \$4,044.30 | \$65.00 | \$3,965.00 | \$150.00 | \$9,150.00 |
| 117 | LC200360 | PERENNIAL PLANTINGS, SPECIAL I | 141.0 | EACH | \$22.50 | \$3,172.50 | \$33.00 | \$4,653.00 | \$22.44 | \$3,164.04 | \$22.00 | \$3,102.00 | \$19.00 | \$2,679.00 |
| 118 | LC200361 | PERENNIAL PLANTINGS, SPECIAL II | 218.0 | EACH | \$22.50 | \$4,905.00 | \$23.00 | \$5,014.00 | \$22.44 | \$4,891.92 | \$22.00 | \$4,796.00 | \$19.00 | \$4,142.00 |
| 119 | LC200362 | PERENNIAL PLANTINGS, SPECIAL III | 379.0 | EACH | \$22.50 | \$8,527.50 | \$23.00 | \$8,717.00 | \$22.44 | \$8,504.76 | \$22.00 | \$8,338.00 | \$19.00 | \$7,201.00 |
| 120 | LC200363 | PERENNIAL PLANTINGS, SPECIAL IV | 112.0 | EACH | \$22.50 | \$2,520.00 | \$23.00 | \$2,576.00 | \$22.44 | \$2,513.28 | \$22.00 | \$2,464.00 | \$19.00 | \$2,128.00 |
| 121 | LC200365 | PERENNIAL PLANTINGS, SPECIAL VI | 967.0 | EACH | \$22.50 | \$21,757.50 | \$22.20 | \$21,467.40 | \$22.44 | \$21,699.48 | \$22.00 | \$21,274.00 | \$19.00 | \$18,373.00 |
| 122 | LC200366 | PERENNIAL PLANTINGS, SPECIAL VII | 406.0 | EACH | \$22.50 | \$9,135.00 | \$23.00 | \$9,338.00 | \$22.44 | \$9,110.64 | \$22.00 | \$8,932.00 | \$19.00 | \$7,714.00 |
| 123 | LC200367 | PERENNIAL PLANTINGS, SPECIAL IX | 184.0 | EACH | \$22.50 | \$4,140.00 | \$23.00 | \$4,232.00 | \$22.44 | \$4,128.96 | \$22.00 | \$4,048.00 | \$19.00 | \$3,496.00 |
| 124 | LC200471 | SEEDING, SPECIAL I | 3,095.0 | SQ YD | \$0.90 | \$2,785.50 | \$4.00 | \$12,380.00 | \$2.55 | \$7,892.25 | \$2.50 | \$7,737.50 | \$2.00 | \$6,190.00 |
| 125 | LC200472 | SEEDING, SPECIAL II | 2,466.0 | SQ YD | \$0.90 | \$2,219.40 | \$4.00 | \$9,864.00 | \$18.36 | \$45,275.76 | \$18.00 | \$44,388.00 | \$2.00 | \$4,932.00 |
| 126 | LC200501 | MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS | 18,252.0 | UNIT | \$1.00 | \$18,252.00 | \$1.00 | \$18,252.00 | \$1.00 | \$18,252.00 | \$1.00 | \$18,252.00 | \$1.00 | \$18,252.00 |

Return Bid Tabulation

Project: Fairfield Road at Monaville Road Improvements
Section: 15-00120-06-CH
Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.
CPMS Pin: B-01184A
Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Berger Excavating Contractors | | Campanella & Sons, Inc. | | Lake County Grading Company | | Copenhaver Construction | |
|----------|----------|--|----------|-------|--------------|--------------|-------------------------------|--------------|-------------------------|--------------|-----------------------------|--------------|-------------------------|--------------|
| | | | | | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price |
| 127 | LC500228 | GRATED CULVERT END SECTIONS, 24" DIAMETER | 2.0 | EACH | \$2,500.00 | \$5,000.00 | \$2,150.00 | \$4,300.00 | \$1,694.78 | \$3,389.56 | \$2,650.00 | \$5,300.00 | \$4,200.00 | \$8,400.00 |
| 128 | LC500230 | GRATED CULVERT END SECTIONS, 36" DIAMETER | 2.0 | EACH | \$3,000.00 | \$6,000.00 | \$3,100.00 | \$6,200.00 | \$2,146.80 | \$4,293.60 | \$4,160.00 | \$8,320.00 | \$7,300.00 | \$14,600.00 |
| 129 | LC500600 | HIGH DENSITY POLYETHYLENE PIPE 14" | 551.0 | FOOT | \$115.00 | \$63,365.00 | \$170.00 | \$93,670.00 | \$114.57 | \$63,128.07 | \$97.00 | \$53,447.00 | \$145.00 | \$79,895.00 |
| 130 | LC600200 | INSTALL SURVEY MONUMENTS | 14.0 | EACH | \$4,000.00 | \$56,000.00 | \$750.00 | \$10,500.00 | \$596.70 | \$8,353.80 | \$585.00 | \$8,190.00 | \$643.50 | \$9,009.00 |
| 131 | LC780031 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 4" | 3,812.0 | FOOT | \$3.00 | \$11,436.00 | \$2.50 | \$9,530.00 | \$2.55 | \$9,720.60 | \$2.50 | \$9,530.00 | \$3.00 | \$11,436.00 |
| 132 | LC780032 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 5" | 5,092.0 | FOOT | \$3.00 | \$15,276.00 | \$6.00 | \$30,552.00 | \$6.12 | \$31,163.04 | \$6.00 | \$30,552.00 | \$7.00 | \$35,644.00 |
| 133 | LC780033 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 6" | 432.0 | FOOT | \$5.00 | \$2,160.00 | \$7.00 | \$3,024.00 | \$7.14 | \$3,084.48 | \$7.00 | \$3,024.00 | \$8.00 | \$3,456.00 |
| 134 | LC780034 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 8" | 1,557.0 | FOOT | \$7.00 | \$10,899.00 | \$7.75 | \$12,066.75 | \$7.90 | \$12,300.30 | \$7.75 | \$12,066.75 | \$8.30 | \$12,923.10 |
| 135 | LC800874 | TEMPORARY TRAFFIC SIGNAL TIMING | 4.0 | EACH | \$1,300.00 | \$5,200.00 | \$548.00 | \$2,192.00 | \$558.96 | \$2,235.84 | \$548.00 | \$2,192.00 | \$548.00 | \$2,192.00 |
| 136 | X0320100 | GROOVING FOR RECESSED PAVEMENT MARKING 10" | 432.0 | FOOT | \$1.20 | \$518.40 | \$1.00 | \$432.00 | \$1.02 | \$440.64 | \$1.00 | \$432.00 | \$1.10 | \$475.20 |
| 137 | X0323260 | SEDIMENT BASIN | 1.0 | EACH | \$3,700.00 | \$3,700.00 | \$11,500.00 | \$11,500.00 | \$8,817.75 | \$8,817.75 | \$10,000.00 | \$10,000.00 | \$7,500.00 | \$7,500.00 |
| 138 | X0323859 | DOWNSPOUT CONNECTION | 1.0 | EACH | \$600.00 | \$600.00 | \$560.00 | \$560.00 | \$310.00 | \$310.00 | \$350.00 | \$350.00 | \$800.00 | \$800.00 |
| 139 | X0324597 | CLOSED CIRCUIT TELEVISION CABINET | 1.0 | EACH | \$10,000.00 | \$10,000.00 | \$6,064.00 | \$6,064.00 | \$6,185.28 | \$6,185.28 | \$6,064.00 | \$6,064.00 | \$6,064.00 | \$6,064.00 |
| 140 | X0325922 | CELLULAR MODEM | 1.0 | EACH | \$4,500.00 | \$4,500.00 | \$1,242.00 | \$1,242.00 | \$1,266.84 | \$1,266.84 | \$1,242.00 | \$1,242.00 | \$1,242.00 | \$1,242.00 |
| 141 | X0326712 | ABANDON AND FILL EXISTING SANITARY SEWER | 1.0 | EACH | \$35,000.00 | \$35,000.00 | \$200.00 | \$200.00 | \$1.00 | \$1.00 | \$9,400.00 | \$9,400.00 | \$5,000.00 | \$5,000.00 |
| 142 | X0327691 | GRATING FOR CONCRETE HEADWALL NO 1 | 2.0 | EACH | \$5,800.00 | \$11,600.00 | \$4,575.00 | \$9,150.00 | \$3,690.00 | \$7,380.00 | \$3,250.00 | \$6,500.00 | \$7,000.00 | \$14,000.00 |
| 143 | X0327980 | PAVEMENT MARKING REMOVAL - WATER BLASTING | 671.0 | SQ FT | \$0.60 | \$402.60 | \$6.00 | \$4,026.00 | \$6.12 | \$4,106.52 | \$6.00 | \$4,026.00 | \$2.00 | \$1,342.00 |

Return Bid Tabulation

Project: Fairfield Road at Monaville Road Improvements
Section: 15-00120-06-CH
Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.
CPMS Pin: B-01184A
Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Berger Excavating Contractors | | Campanella & Sons, Inc. | | Lake County Grading Company | | Copenhaver Construction | |
|----------|----------|---|----------|--------|--------------|--------------|-------------------------------|--------------|-------------------------|--------------|-----------------------------|--------------|-------------------------|--------------|
| | | | | | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price |
| 144 | X0426200 | DEWATERING | 1.0 | L SUM | \$15,000.00 | \$15,000.00 | \$9,000.00 | \$9,000.00 | \$3,370.00 | \$3,370.00 | \$100,000.00 | \$100,000.00 | \$17,000.00 | \$17,000.00 |
| 145 | X1200068 | FORCE MAIN BYPASS PUMPING | 1.0 | L SUM | \$30,000.00 | \$30,000.00 | \$2,400.00 | \$2,400.00 | \$80,519.94 | \$80,519.94 | \$30,000.00 | \$30,000.00 | \$15,000.00 | \$15,000.00 |
| 146 | X1400102 | OUTDOOR RATED NETWORK CABLE | 50.0 | FOOT | \$3.00 | \$150.00 | \$2.50 | \$125.00 | \$2.55 | \$127.50 | \$2.50 | \$125.00 | \$2.50 | \$125.00 |
| 147 | X1400215 | REMOTE CONTROLLED VIDEO SYSTEM | 1.0 | EACH | \$7,500.00 | \$7,500.00 | \$5,824.00 | \$5,824.00 | \$5,940.48 | \$5,940.48 | \$5,824.00 | \$5,824.00 | \$5,824.00 | \$5,824.00 |
| 148 | X1400238 | LUMINAIRE, LED, SPECIAL | 16.0 | EACH | \$500.00 | \$8,000.00 | \$515.00 | \$8,240.00 | \$525.30 | \$8,404.80 | \$515.00 | \$8,240.00 | \$515.00 | \$8,240.00 |
| 149 | X1700066 | POTHOLING | 2.0 | EACH | \$200.00 | \$400.00 | \$525.00 | \$1,050.00 | \$300.00 | \$600.00 | \$1,400.00 | \$2,800.00 | \$1,500.00 | \$3,000.00 |
| 150 | X2070304 | POROUS GRANULAR EMBANKMENT, SPECIAL | 600.0 | CU YD | \$60.00 | \$36,000.00 | \$73.00 | \$43,800.00 | \$46.07 | \$27,642.00 | \$65.00 | \$39,000.00 | \$33.00 | \$19,800.00 |
| 151 | X2700003 | GROOVING FOR RECESSED PAVEMENT MARKING 8" | 3,812.0 | FOOT | \$1.00 | \$3,812.00 | \$0.50 | \$1,906.00 | \$0.51 | \$1,944.12 | \$0.50 | \$1,906.00 | \$0.60 | \$2,287.20 |
| 152 | X2700007 | GROOVING FOR RECESSED PAVEMENT MARKING 12" | 1,557.0 | FOOT | \$1.20 | \$1,868.40 | \$1.20 | \$1,868.40 | \$1.22 | \$1,899.54 | \$1.20 | \$1,868.40 | \$1.40 | \$2,179.80 |
| 153 | X2800500 | INLET PROTECTION, SPECIAL | 11.0 | EACH | \$250.00 | \$2,750.00 | \$96.00 | \$1,056.00 | \$307.00 | \$3,377.00 | \$96.00 | \$1,056.00 | \$200.00 | \$2,200.00 |
| 154 | X4401198 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | 760.0 | SQ YD | \$6.00 | \$4,560.00 | \$6.20 | \$4,712.00 | \$6.32 | \$4,803.20 | \$6.20 | \$4,712.00 | \$6.82 | \$5,183.20 |
| 155 | X5420636 | PIPE CULVERTS TO BE CLEANED 36" | 122.0 | FOOT | \$50.00 | \$6,100.00 | \$53.00 | \$6,466.00 | \$41.82 | \$5,102.04 | \$81.97 | \$10,000.34 | \$90.00 | \$10,980.00 |
| 156 | X5630400 | WATER SERVICE APPURTENANCE TO BE ADJUSTED | 4.0 | EACH | \$500.00 | \$2,000.00 | \$655.00 | \$2,620.00 | \$227.50 | \$910.00 | \$1,380.00 | \$5,520.00 | \$500.00 | \$2,000.00 |
| 157 | X5631212 | CONNECTION TO EXISTING FORCE MAIN 12" | 2.0 | EACH | \$2,000.00 | \$4,000.00 | \$16,900.00 | \$33,800.00 | \$4,045.60 | \$8,091.20 | \$5,000.00 | \$10,000.00 | \$4,500.00 | \$9,000.00 |
| 158 | X5632000 | ABANDON EXISTING FORCE MAIN, FILL WITH CLSM | 546.0 | FOOT | \$65.00 | \$35,490.00 | \$17.35 | \$9,473.10 | \$10.60 | \$5,787.60 | \$0.01 | \$5.46 | \$18.00 | \$9,828.00 |
| 159 | X6020094 | MANHOLES, TYPE A, 6' DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE | 1.0 | EACH | \$8,000.00 | \$8,000.00 | \$13,350.00 | \$13,350.00 | \$11,271.24 | \$11,271.24 | \$10,300.00 | \$10,300.00 | \$14,700.00 | \$14,700.00 |
| 160 | X6700405 | ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED) | 8.0 | CAL MO | \$3,000.00 | \$24,000.00 | \$2,300.00 | \$18,400.00 | \$2,500.00 | \$20,000.00 | \$4,000.00 | \$32,000.00 | \$2,000.00 | \$16,000.00 |

Return Bid Tabulation

Project: Fairfield Road at Monaville Road Improvements
Section: 15-00120-06-CH
Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.
CPMS Pin: B-01184A
Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Berger Excavating Contractors | | Campanella & Sons, Inc. | | Lake County Grading Company | | Copenhaver Construction | |
|----------|----------|--|----------|--------|--------------|--------------|-------------------------------|--------------|-------------------------|--------------|-----------------------------|--------------|-------------------------|--------------|
| | | | | | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price |
| 161 | X7010216 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | 1.0 | L SUM | \$91,725.00 | \$91,725.00 | \$197,500.00 | \$197,500.00 | \$31,992.30 | \$31,992.30 | \$125,900.00 | \$125,900.00 | \$290,000.00 | \$290,000.00 |
| 162 | X7030005 | TEMPORARY PAVEMENT MARKING REMOVAL | 1,817.0 | SQ FT | \$1.00 | \$1,817.00 | \$0.75 | \$1,362.75 | \$0.76 | \$1,380.92 | \$0.75 | \$1,362.75 | \$2.00 | \$3,634.00 |
| 163 | X7810300 | RECESSED REFLECTIVE PAVEMENT MARKER | 26.0 | EACH | \$150.00 | \$3,900.00 | \$78.00 | \$2,028.00 | \$79.56 | \$2,068.56 | \$78.00 | \$2,028.00 | \$85.00 | \$2,210.00 |
| 164 | X7830060 | GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS | 126.0 | SQ FT | \$8.50 | \$1,071.00 | \$2.00 | \$252.00 | \$2.04 | \$257.04 | \$2.00 | \$252.00 | \$3.00 | \$378.00 |
| 165 | X7830070 | GROOVING FOR RECESSED PAVEMENT MARKING 5" | 1,610.0 | FOOT | \$0.85 | \$1,368.50 | \$0.35 | \$563.50 | \$0.36 | \$579.60 | \$0.35 | \$563.50 | \$0.40 | \$644.00 |
| 166 | X7830076 | GROOVING FOR RECESSED PAVEMENT MARKING 9" | 5,341.0 | FOOT | \$1.70 | \$9,079.70 | \$0.65 | \$3,471.65 | \$0.68 | \$3,631.88 | \$0.65 | \$3,471.65 | \$0.75 | \$4,005.75 |
| 167 | X7830078 | GROOVING FOR RECESSED PAVEMENT MARKING 13" | 1,282.0 | FOOT | \$3.00 | \$3,846.00 | \$1.50 | \$1,923.00 | \$1.53 | \$1,961.46 | \$1.50 | \$1,923.00 | \$1.80 | \$2,307.60 |
| 168 | XX000856 | MAILBOX REMOVAL AND RELOCATION | 4.0 | EACH | \$300.00 | \$1,200.00 | \$295.00 | \$1,180.00 | \$270.00 | \$1,080.00 | \$350.00 | \$1,400.00 | \$300.00 | \$1,200.00 |
| 169 | XX006522 | FURNISH WITNESS POST | 22.0 | EACH | \$75.00 | \$1,650.00 | \$150.00 | \$3,300.00 | \$75.00 | \$1,650.00 | \$75.00 | \$1,650.00 | \$400.00 | \$8,800.00 |
| 170 | XX006652 | STAMPED COLORED PORTLAND CEMENT CONCRETE MEDIAN SURFACE 4 INCH (SPECIAL) | 2,119.0 | SQ FT | \$12.00 | \$25,428.00 | \$11.75 | \$24,898.25 | \$12.24 | \$25,936.56 | \$8.20 | \$17,375.80 | \$17.00 | \$36,023.00 |
| 171 | XX006658 | FLOCCULATION LOGS | 20.0 | EACH | \$100.00 | \$2,000.00 | \$1.00 | \$20.00 | \$10.20 | \$204.00 | \$10.00 | \$200.00 | \$150.00 | \$3,000.00 |
| 172 | XX006659 | FLOCCULATION POWDER | 200.0 | POUNDS | \$8.00 | \$1,600.00 | \$0.25 | \$50.00 | \$1.02 | \$204.00 | \$1.00 | \$200.00 | \$10.00 | \$2,000.00 |
| 173 | XX006898 | STAMPED COLORED PORTLAND CEMENT CONCRETE PAVEMENT | 2,586.0 | SQ FT | \$16.00 | \$41,376.00 | \$16.00 | \$41,376.00 | \$16.32 | \$42,203.52 | \$15.50 | \$40,083.00 | \$20.00 | \$51,720.00 |
| 174 | XX007092 | RECESSED REFLECTIVE PAVEMENT MARKER REMOVAL | 40.0 | EACH | \$30.00 | \$1,200.00 | \$15.00 | \$600.00 | \$15.75 | \$630.00 | \$15.00 | \$600.00 | \$16.50 | \$660.00 |
| 175 | XX008865 | PERMEABLE PLASTIC BERM | 222.0 | FOOT | \$11.00 | \$2,442.00 | \$12.50 | \$2,775.00 | \$15.30 | \$3,396.60 | \$15.00 | \$3,330.00 | \$15.00 | \$3,330.00 |
| 176 | Z0013797 | STABILIZED CONSTRUCTION ENTRANCE | 516.0 | SQ YD | \$21.00 | \$10,836.00 | \$21.00 | \$10,836.00 | \$1.00 | \$516.00 | \$0.01 | \$5.16 | \$25.00 | \$12,900.00 |

Return Bid Tabulation

Project: Fairfield Road at Monaville Road Improvements
Section: 15-00120-06-CH
Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.
CPMS Pin: B-01184A
Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Berger Excavating Contractors | | Campanella & Sons, Inc. | | Lake County Grading Company | | Copenhaver Construction | |
|------------------|----------|---------------------------------|----------|-------|--------------|-----------------------|-------------------------------|-----------------------|-------------------------|-----------------------|-----------------------------|-----------------------|-------------------------|-----------------------|
| | | | | | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price | Unit Price | Extnd. Price |
| 177 | Z0019600 | DUST CONTROL WATERING | 13.0 | UNIT | \$30.00 | \$390.00 | \$75.00 | \$975.00 | \$1.00 | \$13.00 | \$100.00 | \$1,300.00 | \$120.00 | \$1,560.00 |
| 178 | Z0022800 | FENCE REMOVAL | 1,362.0 | FOOT | \$6.50 | \$8,853.00 | \$5.00 | \$6,810.00 | \$2.50 | \$3,405.00 | \$5.00 | \$6,810.00 | \$5.00 | \$6,810.00 |
| 179 | Z0030850 | TEMPORARY INFORMATION SIGNING | 100.0 | SQ FT | \$18.00 | \$1,800.00 | \$18.00 | \$1,800.00 | \$12.24 | \$1,224.00 | \$18.00 | \$1,800.00 | \$22.00 | \$2,200.00 |
| 180 | Z0033700 | LONGITUDINAL JOINT SEALANT | 6,424.0 | FOOT | \$3.00 | \$19,272.00 | \$2.85 | \$18,308.40 | \$2.91 | \$18,693.84 | \$2.85 | \$18,308.40 | \$3.14 | \$20,171.36 |
| 181 | Z0036200 | PAINT CURB | 2,148.0 | FOOT | \$5.00 | \$10,740.00 | \$2.00 | \$4,296.00 | \$3.00 | \$6,444.00 | \$0.75 | \$1,611.00 | \$1.00 | \$2,148.00 |
| 182 | Z0055905 | TEMPORARY CONSTRUCTION FENCE | 239.0 | FOOT | \$5.00 | \$1,195.00 | \$3.00 | \$717.00 | \$3.06 | \$731.34 | \$3.00 | \$717.00 | \$7.00 | \$1,673.00 |
| 183 | Z0067900 | STEEL CASINGS 24" | 113.0 | FOOT | \$200.00 | \$22,600.00 | \$140.00 | \$15,820.00 | \$163.14 | \$18,434.82 | \$230.00 | \$25,990.00 | \$170.00 | \$19,210.00 |
| 184 | Z0073510 | TEMPORARY TRAFFIC SIGNAL TIMING | 4.0 | EACH | \$1,300.00 | \$5,200.00 | \$548.00 | \$2,192.00 | \$558.96 | \$2,235.84 | \$548.00 | \$2,192.00 | \$548.00 | \$2,192.00 |
| Bid Total | | | | | | \$3,427,518.10 | | \$2,770,038.20 | | \$2,610,260.43 | | \$2,816,201.47 | | \$3,374,580.34 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|--|----------|-------|--------------|--------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extnd. Price | | | |
| 1 | 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | 1,461.0 | UNIT | \$17.00 | \$24,837.00 | \$1.10 | \$13.00 | \$7.15 |
| 2 | 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | 1,023.0 | UNIT | \$27.00 | \$27,621.00 | \$1.80 | \$18.00 | \$9.45 |
| 3 | 20101100 | TREE TRUNK PROTECTION | 21.0 | EACH | \$120.00 | \$2,520.00 | \$95.00 | \$100.00 | \$98.75 |
| 4 | 20101200 | TREE ROOT PRUNING | 21.0 | EACH | \$100.00 | \$2,100.00 | \$68.00 | \$70.00 | \$69.50 |
| 5 | 20101300 | TREE PRUNING (1 TO 10 INCH DIAMETER) | 16.0 | EACH | \$55.00 | \$880.00 | \$20.00 | \$70.00 | \$33.75 |
| 6 | 20101350 | TREE PRUNING (OVER 10 INCH DIAMETER) | 5.0 | EACH | \$90.00 | \$450.00 | \$40.00 | \$80.00 | \$51.25 |
| 7 | 20200100 | EARTH EXCAVATION | 12,172.0 | CU YD | \$22.50 | \$273,870.00 | \$0.01 | \$24.00 | \$10.09 |
| 8 | 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | 753.0 | CU YD | \$32.50 | \$24,472.50 | \$22.00 | \$26.17 | \$24.04 |
| 9 | 20800150 | TRENCH BACKFILL | 840.0 | CU YD | \$50.00 | \$42,000.00 | \$0.01 | \$46.63 | \$26.72 |
| 10 | 21001000 | GEOTECHNICAL FABRIC FOR GROUND STABILIZATION | 17,202.0 | SQ YD | \$2.00 | \$34,404.00 | \$1.35 | \$2.00 | \$1.63 |
| 11 | 21101505 | TOPSOIL EXCAVATION AND PLACEMENT | 2,604.0 | CU YD | \$25.00 | \$65,100.00 | \$0.01 | \$19.50 | \$12.06 |
| 12 | 21101805 | COMPOST FURNISH AND PLACE, 2" | 732.0 | SQ YD | \$4.00 | \$2,928.00 | \$3.50 | \$7.10 | \$4.79 |
| 13 | 21301052 | EXPLORATION TRENCH 52" DEPTH | 1,479.0 | FOOT | \$20.00 | \$29,580.00 | \$0.01 | \$1.00 | \$0.38 |
| 14 | 25000210 | SEEDING, CLASS 2A | 0.3 | ACRE | \$2,100.00 | \$630.00 | \$2,991.00 | \$5,000.00 | \$4,441.95 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|------------------------------------|----------|-------|--------------|--------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extn. Price | | | |
| 15 | 25000310 | SEEDING, CLASS 4 | 0.5 | ACRE | \$2,100.00 | \$1,050.00 | \$2,216.00 | \$6,000.00 | \$4,498.20 |
| 16 | 25000312 | SEEDING, CLASS 4A | 1.8 | ACRE | \$2,100.00 | \$3,780.00 | \$2,278.00 | \$6,000.00 | \$4,513.70 |
| 17 | 25000400 | NITROGEN FERTILIZER NUTRIENT | 397.0 | POUND | \$2.00 | \$794.00 | \$1.00 | \$3.00 | \$1.51 |
| 18 | 25000600 | POTASSIUM FERTILIZER NUTRIENT | 397.0 | POUND | \$2.00 | \$794.00 | \$1.00 | \$3.00 | \$1.51 |
| 19 | 25000700 | AGRICULTURAL GROUND LIMESTONE | 10.0 | TON | \$135.00 | \$1,350.00 | \$10.00 | \$400.00 | \$130.05 |
| 20 | 25100630 | EROSION CONTROL BLANKET | 21,401.0 | SQ YD | \$1.50 | \$32,101.50 | \$1.10 | \$1.70 | \$1.33 |
| 21 | 25200110 | SODDING, SALT TOLERANT | 5,228.0 | SQ YD | \$1.50 | \$7,842.00 | \$8.00 | \$10.20 | \$9.55 |
| 22 | 25200200 | SUPPLEMENTAL WATERING | 500.0 | UNIT | \$17.00 | \$8,500.00 | \$0.01 | \$0.11 | \$0.06 |
| 23 | 28000250 | TEMPORARY EROSION CONTROL SEEDING | 443.0 | POUND | \$6.50 | \$2,879.50 | \$0.01 | \$6.00 | \$1.56 |
| 24 | 28000305 | TEMPORARY DITCH CHECK | 222.0 | FOOT | \$15.00 | \$3,330.00 | \$6.00 | \$15.00 | \$11.31 |
| 25 | 28000400 | PERIMETER EROSION BARRIER | 3,254.0 | FOOT | \$3.00 | \$9,762.00 | \$2.00 | \$3.40 | \$2.74 |
| 26 | 28000510 | INLET FILTERS | 27.0 | EACH | \$160.00 | \$4,320.00 | \$80.00 | \$152.00 | \$128.70 |
| 27 | 28100107 | STONE RIP RAP, CLASS A4 | 198.0 | SQ YD | \$70.00 | \$13,860.00 | \$82.00 | \$100.00 | \$91.75 |
| 28 | 28200200 | FILTER FABRIC | 198.0 | SQ YD | \$6.00 | \$1,188.00 | \$1.00 | \$3.00 | \$2.25 |
| 29 | 30300001 | AGGREGATE SUBGRADE IMPROVEMENT | 324.0 | CU YD | \$48.00 | \$15,552.00 | \$34.24 | \$73.50 | \$51.44 |
| 30 | 30300112 | AGGREGATE SUBGRADE IMPROVEMENT 12" | 15,411.0 | SQ YD | \$20.00 | \$308,220.00 | \$12.00 | \$20.00 | \$15.15 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|--|----------|-------|--------------|--------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extn. Price | | | |
| 31 | 35100300 | AGGREGATE BASE COURSE, TYPE A 4" | 791.0 | SQ YD | \$9.50 | \$7,514.50 | \$6.00 | \$8.00 | \$6.96 |
| 32 | 35101800 | AGGREGATE BASE COURSE, TYPE B 6" | 1,184.0 | SQ YD | \$12.00 | \$14,208.00 | \$6.00 | \$15.00 | \$8.73 |
| 33 | 35102000 | AGGREGATE BASE COURSE, TYPE B 8" | 192.0 | SQ YD | \$13.50 | \$2,592.00 | \$10.00 | \$19.00 | \$13.35 |
| 34 | 40200800 | AGGREGATE SURFACE COURSE, TYPE B | 152.0 | TON | \$30.00 | \$4,560.00 | \$27.00 | \$37.00 | \$31.00 |
| 35 | 40201000 | AGGREGATE FOR TEMPORARY ACCESS | 1,640.0 | TON | \$26.00 | \$42,640.00 | \$0.01 | \$22.00 | \$5.76 |
| 36 | 40600275 | BITUMINOUS MATERIALS (PRIME COAT) | 27,952.0 | POUND | \$0.50 | \$13,976.00 | \$0.01 | \$0.02 | \$0.01 |
| 37 | 40600290 | BITUMINOUS MATERIALS (TACK COAT) | 2,796.0 | POUND | \$1.00 | \$2,796.00 | \$0.01 | \$0.02 | \$0.01 |
| 38 | 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | 2.0 | TON | \$500.00 | \$1,000.00 | \$50.00 | \$55.00 | \$51.50 |
| 39 | 40600525 | LEVELING BINDER (HAND METHOD), N50 | 6.0 | TON | \$95.00 | \$570.00 | \$50.00 | \$55.00 | \$51.50 |
| 40 | 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0 N50 | 4,595.0 | TON | \$95.00 | \$436,525.00 | \$59.25 | \$68.03 | \$62.67 |
| 41 | 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | 1,424.0 | TON | \$110.00 | \$156,640.00 | \$66.65 | \$76.34 | \$70.70 |
| 42 | 42001300 | PROTECTIVE COAT | 2,129.0 | SQ YD | \$2.50 | \$5,322.50 | \$0.01 | \$2.90 | \$1.23 |
| 43 | 42300200 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH | 36.0 | SQ YD | \$55.00 | \$1,980.00 | \$60.00 | \$73.44 | \$67.61 |
| 44 | 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | 275.0 | SQ FT | \$7.00 | \$1,925.00 | \$7.00 | \$10.00 | \$8.48 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|--|----------|-------|--------------|--------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extnd. Price | | | |
| 45 | 42400800 | DETECTABLE WARNINGS | 352.0 | SQ FT | \$32.00 | \$11,264.00 | \$27.00 | \$33.15 | \$30.19 |
| 46 | 44000100 | PAVEMENT REMOVAL | 9,794.0 | SQ YD | \$9.00 | \$88,146.00 | \$3.68 | \$13.00 | \$10.17 |
| 47 | 44000200 | DRIVEWAY PAVEMENT REMOVAL | 725.0 | SQ YD | \$9.50 | \$6,887.50 | \$5.00 | \$15.00 | \$9.52 |
| 48 | 44000500 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL | 480.0 | FOOT | \$7.00 | \$3,360.00 | \$3.57 | \$6.00 | \$4.89 |
| 49 | 44213200 | SAW CUTS | 77.0 | FOOT | \$3.00 | \$231.00 | \$2.50 | \$10.00 | \$6.13 |
| 50 | 44300200 | STRIP REFLECTIVE CRACK CONTROL TREATMENT | 579.0 | FOOT | \$3.00 | \$1,737.00 | \$4.25 | \$4.67 | \$4.38 |
| 51 | 48101200 | AGGREGATE SHOULDERS, TYPE B | 246.0 | TON | \$13.00 | \$3,198.00 | \$41.55 | \$45.70 | \$42.80 |
| 52 | 48203021 | HOT-MIX ASPHALT SHOULDERS, 6" | 29.0 | SQ YD | \$95.00 | \$2,755.00 | \$30.00 | \$33.00 | \$30.90 |
| 53 | 50105220 | PIPE CULVERT REMOVAL | 284.0 | FOOT | \$14.00 | \$3,976.00 | \$4.86 | \$40.00 | \$20.72 |
| 54 | 52200800 | SEGMENTAL CONCRETE BLOCK WALL | 311.0 | SQ FT | \$50.00 | \$15,550.00 | \$43.00 | \$45.00 | \$44.22 |
| 55 | 54001001 | BOX CULVERT END SECTIONS, CULVERT NO. 1 | 2.0 | EACH | \$6,500.00 | \$13,000.00 | \$5,378.68 | \$11,000.00 | \$6,894.67 |
| 56 | 54010402 | PRECAST CONCRETE BOX CULVERTS 4' X 2' | 46.0 | FOOT | \$400.00 | \$18,400.00 | \$245.00 | \$580.00 | \$364.95 |
| 57 | 542A0229 | PIPE CULVERTS, CLASS A, TYPE 1 24" | 54.0 | FOOT | \$65.00 | \$3,510.00 | \$55.10 | \$100.00 | \$68.78 |
| 58 | 542A1081 | PIPE CULVERTS, CLASS A, TYPE 2 36" | 123.0 | FOOT | \$70.00 | \$8,610.00 | \$89.78 | \$130.00 | \$103.95 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|---|----------|------|--------------|-------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extn. Price | | | |
| 59 | 54213657 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" | 7.0 | EACH | \$1,300.00 | \$9,100.00 | \$700.00 | \$1,710.00 | \$1,179.24 |
| 60 | 54213660 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15" | 2.0 | EACH | \$1,500.00 | \$3,000.00 | \$740.00 | \$1,750.00 | \$1,228.66 |
| 61 | 54213669 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24" | 2.0 | EACH | \$1,800.00 | \$3,600.00 | \$940.00 | \$2,200.00 | \$1,647.02 |
| 62 | 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | 49.0 | FOOT | \$50.00 | \$2,450.00 | \$45.17 | \$85.00 | \$58.04 |
| 63 | 550A0120 | STORM SEWERS, CLASS A, TYPE 1 24" | 23.0 | FOOT | \$70.00 | \$1,610.00 | \$66.00 | \$115.37 | \$89.34 |
| 64 | 550A0340 | STORM SEWERS, CLASS A, TYPE 2 12" | 409.0 | FOOT | \$60.00 | \$24,540.00 | \$45.96 | \$85.00 | \$57.99 |
| 65 | 550A0360 | STORM SEWERS, CLASS A, TYPE 2 15" | 504.0 | FOOT | \$65.00 | \$32,760.00 | \$41.00 | \$88.00 | \$58.32 |
| 66 | 550A0410 | STORM SEWERS, CLASS A, TYPE 2 24" | 49.0 | FOOT | \$100.00 | \$4,900.00 | \$65.00 | \$105.00 | \$79.46 |
| 67 | 55100500 | STORM SEWER REMOVAL 12" | 535.0 | FOOT | \$13.00 | \$6,955.00 | \$6.27 | \$20.00 | \$13.57 |
| 68 | 55100700 | STORM SEWER REMOVAL 15" | 70.0 | FOOT | \$16.00 | \$1,120.00 | \$9.15 | \$20.00 | \$15.54 |
| 69 | 60100060 | CONCRETE HEADWALLS FOR PIPE DRAINS | 4.0 | EACH | \$315.00 | \$1,260.00 | \$340.00 | \$500.00 | \$411.13 |
| 70 | 60100905 | PIPE DRAINS 4" | 61.0 | FOOT | \$26.00 | \$1,586.00 | \$15.00 | \$40.00 | \$30.87 |
| 71 | 60100915 | PIPE DRAINS 6" | 132.0 | FOOT | \$26.00 | \$3,432.00 | \$19.00 | \$40.00 | \$32.86 |
| 72 | 60108104 | PIPE UNDERDRAINS, TYPE I, 4" | 3,944.0 | FOOT | \$5.00 | \$19,720.00 | \$3.00 | \$10.00 | \$4.97 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|--|----------|--------|--------------|--------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extnd. Price | | | |
| 73 | 60201340 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE | 13.0 | EACH | \$3,000.00 | \$39,000.00 | \$2,350.00 | \$2,800.00 | \$2,564.00 |
| 74 | 60218400 | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | 6.0 | EACH | \$2,200.00 | \$13,200.00 | \$2,325.00 | \$2,600.00 | \$2,503.48 |
| 75 | 60237470 | INLETS, TYPE A, TYPE 24 FRAME AND GRATE | 10.0 | EACH | \$1,200.00 | \$12,000.00 | \$1,100.00 | \$1,600.00 | \$1,275.17 |
| 76 | 60500050 | REMOVING CATCH BASINS | 2.0 | EACH | \$400.00 | \$800.00 | \$300.00 | \$550.00 | \$410.00 |
| 77 | 60500040 | REMOVING MANHOLES | 4.0 | EACH | \$350.00 | \$1,400.00 | \$350.00 | \$600.00 | \$497.50 |
| 78 | 60603800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 | 2,042.0 | FOOT | \$24.00 | \$49,008.00 | \$23.46 | \$24.00 | \$23.74 |
| 79 | 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | 3,196.0 | FOOT | \$29.00 | \$92,684.00 | \$24.00 | \$30.00 | \$26.25 |
| 80 | 60608300 | COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12 | 241.0 | FOOT | \$34.00 | \$8,194.00 | \$23.46 | \$26.00 | \$24.49 |
| 81 | 60619600 | CONCRETE MEDIAN, TYPE SB-6.12 | 99.0 | SQ FT | \$15.00 | \$1,485.00 | \$10.00 | \$17.00 | \$14.20 |
| 82 | 61100605 | MISCELLANEOUS CONCRETE | 0.3 | CU YD | \$1,160.00 | \$348.00 | \$1,500.00 | \$3,000.00 | \$2,500.00 |
| 83 | 61133100 | FIELD TILE JUNCTION VAULTS, 2' DIA. | 5.0 | EACH | \$1,000.00 | \$5,000.00 | \$900.00 | \$1,530.00 | \$1,282.79 |
| 84 | 61139800 | STORM SEWERS (SPECIAL), 4" | 545.0 | FOOT | \$20.00 | \$10,900.00 | \$28.00 | \$40.00 | \$31.39 |
| 85 | 67100100 | MOBILIZATION | 1.0 | L SUM | \$183,390.00 | \$183,390.00 | \$63,872.08 | \$188,185.00 | \$146,264.27 |
| 86 | 70106800 | CHANGEABLE MESSAGE SIGN | 45.0 | CAL MO | \$1,200.00 | \$54,000.00 | \$25.00 | \$1,100.00 | \$293.88 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|--|----------|-------|--------------|-------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extn. Price | | | |
| 87 | 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | 5,451.0 | FOOT | \$0.20 | \$1,090.20 | \$0.30 | \$0.50 | \$0.35 |
| 88 | 72400100 | REMOVE SIGN PANEL ASSEMBLY - TYPE A | 19.0 | EACH | \$65.00 | \$1,235.00 | \$60.00 | \$110.00 | \$72.80 |
| 89 | 72400200 | REMOVE SIGN PANEL ASSEMBLY - TYPE B | 1.0 | EACH | \$230.00 | \$230.00 | \$100.00 | \$150.00 | \$113.00 |
| 90 | 72400310 | REMOVE SIGN PANEL - TYPE 1 | 52.0 | SQ FT | \$11.00 | \$572.00 | \$15.00 | \$17.00 | \$15.58 |
| 91 | 72400320 | REMOVE SIGN PANEL - TYPE 2 | 53.0 | SQ FT | \$13.00 | \$689.00 | \$15.00 | \$22.00 | \$16.83 |
| 92 | 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | 126.0 | SQ FT | \$6.50 | \$819.00 | \$4.00 | \$5.00 | \$4.27 |
| 93 | 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | 1,610.0 | FOOT | \$1.00 | \$1,610.00 | \$1.00 | \$1.10 | \$1.03 |
| 94 | 78000500 | THERMOPLASTIC PAVEMENT MARKING - LINE 8" | 249.0 | FOOT | \$1.60 | \$398.40 | \$2.00 | \$3.00 | \$2.26 |
| 95 | 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | 1,282.0 | FOOT | \$2.10 | \$2,692.20 | \$3.00 | \$3.30 | \$3.09 |
| 96 | 80400100 | ELECTRIC SERVICE INSTALLATION | 1.0 | EACH | \$2,400.00 | \$2,400.00 | \$3,206.00 | \$3,270.12 | \$3,222.03 |
| 97 | 80400200 | ELECTRIC UTILITY SERVICE CONNECTION | 1.0 | EACH | \$4,000.00 | \$4,000.00 | \$0.00 | \$5,000.00 | \$1,875.25 |
| 98 | 81028220 | UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA. | 385.0 | FOOT | \$30.00 | \$11,550.00 | \$30.60 | \$31.21 | \$30.75 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|---|----------|------|--------------|--------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extnd. Price | | | |
| 99 | 81603000 | UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE | 3,481.0 | FOOT | \$4.50 | \$15,664.50 | \$8.30 | \$8.47 | \$8.34 |
| 100 | 81702150 | ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2 | 225.0 | FOOT | \$6.50 | \$1,462.50 | \$2.50 | \$2.55 | \$2.51 |
| 101 | 81800240 | AERIAL CABLE, 2-1/C NO. 8 WITH MESSENGER WIRE | 2,954.0 | FOOT | \$3.95 | \$11,668.30 | \$4.00 | \$4.08 | \$4.02 |
| 102 | 82500360 | LIGHTING CONTROLLER, BASE MOUNTED, 480 VOLT, 100 AMP | 1.0 | EACH | \$8,500.00 | \$8,500.00 | \$19,984.00 | \$20,383.68 | \$20,083.92 |
| 103 | 83060150 | LIGHT POLE, GALVANIZED STEEL, 30 FT. M.H., 15 FT. MAST ARM | 16.0 | EACH | \$4,750.00 | \$76,000.00 | \$9,188.00 | \$9,738.00 | \$9,371.44 |
| 104 | 83057215 | LIGHT POLE, WOOD, 40 FOOT, CLASS 3, WITH 15FT MAST ARM | 16.0 | EACH | \$2,600.00 | \$41,600.00 | \$420.00 | \$428.40 | \$422.10 |
| 105 | 83600300 | LIGHT POLE FOUNDATION, 30" DIAMETER | 16.0 | EACH | \$450.00 | \$7,200.00 | \$1,830.00 | \$1,866.60 | \$1,839.15 |
| 106 | 83800105 | BREAKAWAY DEVICE, TRANSFORMER BASE, 11 1/2 INCH BOLT CIRCLE | 16.0 | EACH | \$400.00 | \$6,400.00 | \$518.00 | \$528.36 | \$520.59 |
| 107 | 85000500 | MAINTENANCE OF EXISTING FLASHING BEACON INSTALLATION | 1.0 | EACH | \$1,800.00 | \$1,800.00 | \$420.00 | \$428.40 | \$422.10 |
| 108 | 89502400 | REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE | 1.0 | EACH | \$950.00 | \$950.00 | \$1,680.00 | \$1,713.60 | \$1,688.40 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|---|----------|----------|--------------|-------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extn. Price | | | |
| 109 | B2006120 | TREE, SYRINGA PEKINENSIS MORTON (CHINA SNOW PEKING LILAC), 2 1/2" CALIPER, TREE FORM, BALLED AND BURPLAPPED | 3.0 | EACH | \$650.00 | \$1,950.00 | \$503.00 | \$750.00 | \$578.38 |
| 110 | K1003679 | MULCH | 61.0 | CU YD | \$65.00 | \$3,965.00 | \$55.00 | \$95.00 | \$70.33 |
| 111 | LC200051 | REJECTED LOAD TRANSPORTATION | 34.0 | LOAD | \$200.00 | \$6,800.00 | \$0.01 | \$100.00 | \$25.26 |
| 112 | LC200100 | LANDSCAPE PERFORMANCE GUARANTEE | 1.0 | _UMP SUM | \$10,000.00 | \$10,000.00 | \$10,000.00 | \$30,000.00 | \$18,585.00 |
| 113 | LC200321 | SHRUB, SPECIAL | 48.0 | EACH | \$75.00 | \$3,600.00 | \$65.00 | \$150.00 | \$101.83 |
| 114 | LC200322 | SHRUB, SPECIAL I | 84.0 | EACH | \$75.00 | \$6,300.00 | \$65.00 | \$150.00 | \$100.08 |
| 115 | LC200323 | SHRUB, SPECIAL II | 73.0 | EACH | \$75.00 | \$5,475.00 | \$65.00 | \$150.00 | \$98.08 |
| 116 | LC200324 | SHRUB, SPECIAL III | 61.0 | EACH | \$75.00 | \$4,575.00 | \$65.00 | \$150.00 | \$98.08 |
| 117 | LC200360 | PERENNIAL PLANTINGS, SPECIAL I | 141.0 | EACH | \$22.50 | \$3,172.50 | \$19.00 | \$33.00 | \$24.11 |
| 118 | LC200361 | PERENNIAL PLANTINGS, SPECIAL II | 218.0 | EACH | \$22.50 | \$4,905.00 | \$19.00 | \$23.00 | \$21.61 |
| 119 | LC200362 | PERENNIAL PLANTINGS, SPECIAL III | 379.0 | EACH | \$22.50 | \$8,527.50 | \$19.00 | \$23.00 | \$21.61 |
| 120 | LC200363 | PERENNIAL PLANTINGS, SPECIAL IV | 112.0 | EACH | \$22.50 | \$2,520.00 | \$19.00 | \$23.00 | \$21.61 |
| 121 | LC200365 | PERENNIAL PLANTINGS, SPECIAL VI | 967.0 | EACH | \$22.50 | \$21,757.50 | \$19.00 | \$22.44 | \$21.41 |
| 122 | LC200366 | PERENNIAL PLANTINGS, SPECIAL VII | 406.0 | EACH | \$22.50 | \$9,135.00 | \$19.00 | \$23.00 | \$21.61 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|--|----------|-------|--------------|--------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extnd. Price | | | |
| 123 | LC200367 | PERENNIAL PLANTINGS, SPECIAL IX | 184.0 | EACH | \$22.50 | \$4,140.00 | \$19.00 | \$23.00 | \$21.61 |
| 124 | LC200471 | SEEDING, SPECIAL I | 3,095.0 | SQ YD | \$0.90 | \$2,785.50 | \$2.00 | \$4.00 | \$2.76 |
| 125 | LC200472 | SEEDING, SPECIAL II | 2,466.0 | SQ YD | \$0.90 | \$2,219.40 | \$2.00 | \$18.36 | \$10.59 |
| 126 | LC200501 | MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS | 18,252.0 | UNIT | \$1.00 | \$18,252.00 | \$1.00 | \$1.00 | \$1.00 |
| 127 | LC500228 | GRATED CULVERT END SECTIONS, 24" DIAMETER | 2.0 | EACH | \$2,500.00 | \$5,000.00 | \$1,694.78 | \$4,200.00 | \$2,673.70 |
| 128 | LC500230 | GRATED CULVERT END SECTIONS, 36" DIAMETER | 2.0 | EACH | \$3,000.00 | \$6,000.00 | \$2,146.80 | \$7,300.00 | \$4,176.70 |
| 129 | LC500600 | HIGH DENSITY POLYETHYLENE PIPE 14" | 551.0 | FOOT | \$115.00 | \$63,365.00 | \$97.00 | \$170.00 | \$131.64 |
| 130 | LC600200 | INSTALL SURVEY MONUMENTS | 14.0 | EACH | \$4,000.00 | \$56,000.00 | \$585.00 | \$750.00 | \$643.80 |
| 131 | LC780031 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 4" | 3,812.0 | FOOT | \$3.00 | \$11,436.00 | \$2.50 | \$3.00 | \$2.64 |
| 132 | LC780032 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 5" | 5,092.0 | FOOT | \$3.00 | \$15,276.00 | \$6.00 | \$7.00 | \$6.28 |
| 133 | LC780033 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 6" | 432.0 | FOOT | \$5.00 | \$2,160.00 | \$7.00 | \$8.00 | \$7.29 |
| 134 | LC780034 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 8" | 1,557.0 | FOOT | \$7.00 | \$10,899.00 | \$7.75 | \$8.30 | \$7.93 |
| 135 | LC800874 | TEMPORARY TRAFFIC SIGNAL TIMING | 4.0 | EACH | \$1,300.00 | \$5,200.00 | \$548.00 | \$558.96 | \$550.74 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|--|----------|-------|--------------|--------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extnd. Price | | | |
| 136 | X0320100 | GROOVING FOR RECESSED PAVEMENT MARKING 10" | 432.0 | FOOT | \$1.20 | \$518.40 | \$1.00 | \$1.10 | \$1.03 |
| 137 | X0323260 | SEDIMENT BASIN | 1.0 | EACH | \$3,700.00 | \$3,700.00 | \$7,500.00 | \$11,500.00 | \$9,454.44 |
| 138 | X0323859 | DOWNSPOUT CONNECTION | 1.0 | EACH | \$600.00 | \$600.00 | \$310.00 | \$800.00 | \$505.00 |
| 139 | X0324597 | CLOSED CIRCUIT TELEVISION CABINET | 1.0 | EACH | \$10,000.00 | \$10,000.00 | \$6,064.00 | \$6,185.28 | \$6,094.32 |
| 140 | X0325922 | CELLULAR MODEM | 1.0 | EACH | \$4,500.00 | \$4,500.00 | \$1,242.00 | \$1,266.84 | \$1,248.21 |
| 141 | X0326712 | ABANDON AND FILL EXISTING SANITARY SEWER | 1.0 | EACH | \$35,000.00 | \$35,000.00 | \$1.00 | \$9,400.00 | \$3,650.25 |
| 142 | X0327691 | GRATING FOR CONCRETE HEADWALL NO 1 | 2.0 | EACH | \$5,800.00 | \$11,600.00 | \$3,250.00 | \$7,000.00 | \$4,628.75 |
| 143 | X0327980 | PAVEMENT MARKING REMOVAL - WATER BLASTING | 671.0 | SQ FT | \$0.60 | \$402.60 | \$2.00 | \$6.12 | \$5.03 |
| 144 | X0426200 | DEWATERING | 1.0 | L SUM | \$15,000.00 | \$15,000.00 | \$3,370.00 | \$100,000.00 | \$32,342.50 |
| 145 | X1200068 | FORCE MAIN BYPASS PUMPING | 1.0 | L SUM | \$30,000.00 | \$30,000.00 | \$2,400.00 | \$80,519.94 | \$31,979.99 |
| 146 | X1400102 | OUTDOOR RATED NETWORK CABLE | 50.0 | FOOT | \$3.00 | \$150.00 | \$2.50 | \$2.55 | \$2.51 |
| 147 | X1400215 | REMOTE CONTROLLED VIDEO SYSTEM | 1.0 | EACH | \$7,500.00 | \$7,500.00 | \$5,824.00 | \$5,940.48 | \$5,853.12 |
| 148 | X1400238 | LUMINAIRE, LED, SPECIAL | 16.0 | EACH | \$500.00 | \$8,000.00 | \$515.00 | \$525.30 | \$517.58 |
| 149 | X1700066 | POTHOLING | 2.0 | EACH | \$200.00 | \$400.00 | \$300.00 | \$1,500.00 | \$931.25 |
| 150 | X2070304 | POROUS GRANULAR EMBANKMENT, SPECIAL | 600.0 | CU YD | \$60.00 | \$36,000.00 | \$33.00 | \$73.00 | \$54.27 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|---|----------|--------|--------------|-------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extd. Price | | | |
| 151 | X2700003 | GROOVING FOR RECESSED PAVEMENT MARKING 8" | 3,812.0 | FOOT | \$1.00 | \$3,812.00 | \$0.50 | \$0.60 | \$0.53 |
| 152 | X2700007 | GROOVING FOR RECESSED PAVEMENT MARKING 12" | 1,557.0 | FOOT | \$1.20 | \$1,868.40 | \$1.20 | \$1.40 | \$1.26 |
| 153 | X2800500 | INLET PROTECTION, SPECIAL | 11.0 | EACH | \$250.00 | \$2,750.00 | \$96.00 | \$307.00 | \$174.75 |
| 154 | X4401198 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | 760.0 | SQ YD | \$6.00 | \$4,560.00 | \$6.20 | \$6.82 | \$6.39 |
| 155 | X5420636 | PIPE CULVERTS TO BE CLEANED 36" | 122.0 | FOOT | \$50.00 | \$6,100.00 | \$41.82 | \$90.00 | \$66.70 |
| 156 | X5630400 | WATER SERVICE APPURTENANCE TO BE ADJUSTED | 4.0 | EACH | \$500.00 | \$2,000.00 | \$227.50 | \$1,380.00 | \$690.63 |
| 157 | X5631212 | CONNECTION TO EXISTING FORCE MAIN 12" | 2.0 | EACH | \$2,000.00 | \$4,000.00 | \$4,045.60 | \$16,900.00 | \$7,611.40 |
| 158 | X5632000 | ABANDON EXISTING FORCE MAIN, FILL WITH CLSM | 546.0 | FOOT | \$65.00 | \$35,490.00 | \$0.01 | \$18.00 | \$11.49 |
| 159 | X6020094 | MANHOLES, TYPE A, 6' DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE | 1.0 | EACH | \$8,000.00 | \$8,000.00 | \$10,300.00 | \$14,700.00 | \$12,405.31 |
| 160 | X6700405 | ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED) | 8.0 | CAL MO | \$3,000.00 | \$24,000.00 | \$2,000.00 | \$4,000.00 | \$2,700.00 |
| 161 | X7010216 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | 1.0 | L SUM | \$91,725.00 | \$91,725.00 | \$31,992.30 | \$290,000.00 | \$161,348.08 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|----------|----------|--|----------|--------|--------------|-------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extd. Price | | | |
| 162 | X7030005 | TEMPORARY PAVEMENT MARKING REMOVAL | 1,817.0 | SQ FT | \$1.00 | \$1,817.00 | \$0.75 | \$2.00 | \$1.07 |
| 163 | X7810300 | RECESSED REFLECTIVE PAVEMENT MARKER | 26.0 | EACH | \$150.00 | \$3,900.00 | \$78.00 | \$85.00 | \$80.14 |
| 164 | X7830060 | GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS | 126.0 | SQ FT | \$8.50 | \$1,071.00 | \$2.00 | \$3.00 | \$2.26 |
| 165 | X7830070 | GROOVING FOR RECESSED PAVEMENT MARKING 5" | 1,610.0 | FOOT | \$0.85 | \$1,368.50 | \$0.35 | \$0.40 | \$0.37 |
| 166 | X7830076 | GROOVING FOR RECESSED PAVEMENT MARKING 9" | 5,341.0 | FOOT | \$1.70 | \$9,079.70 | \$0.65 | \$0.75 | \$0.68 |
| 167 | X7830078 | GROOVING FOR RECESSED PAVEMENT MARKING 13" | 1,282.0 | FOOT | \$3.00 | \$3,846.00 | \$1.50 | \$1.80 | \$1.58 |
| 168 | XX000856 | MAILBOX REMOVAL AND RELOCATION | 4.0 | EACH | \$300.00 | \$1,200.00 | \$270.00 | \$350.00 | \$303.75 |
| 169 | XX006522 | FURNISH WITNESS POST | 22.0 | EACH | \$75.00 | \$1,650.00 | \$75.00 | \$400.00 | \$175.00 |
| 170 | XX006652 | STAMPED COLORED PORTLAND CEMENT CONCRETE MEDIAN SURFACE 4 INCH (SPECIAL) | 2,119.0 | SQ FT | \$12.00 | \$25,428.00 | \$8.20 | \$17.00 | \$12.30 |
| 171 | XX006658 | FLOCCULATION LOGS | 20.0 | EACH | \$100.00 | \$2,000.00 | \$1.00 | \$150.00 | \$42.80 |
| 172 | XX006659 | FLOCCULATION POWDER | 200.0 | POUNDS | \$8.00 | \$1,600.00 | \$0.25 | \$10.00 | \$3.07 |
| 173 | XX006898 | STAMPED COLORED PORTLAND CEMENT CONCRETE PAVEMENT | 2,586.0 | SQ FT | \$16.00 | \$41,376.00 | \$15.50 | \$20.00 | \$16.96 |

Return Bid Details

Project: Fairfield Road at Monaville Road Improvements

Section: 15-00120-06-CH

Description: The project involves the construction of a roundabout at an existing 4-way stop controlled intersection.

CPMS Pin: B-01184A

Let Date: 3/16/2021

| Item No. | Pay Code | Description | Quantity | Unit | Eng Estimate | | Min. Bid Price | Max. Bid Price | Avg. Bid Price |
|------------------|----------|---|----------|-------|-----------------------|--------------|----------------|----------------|----------------|
| | | | | | Unit Price | Extnd. Price | | | |
| 174 | XX007092 | RECESSED REFLECTIVE PAVEMENT MARKER REMOVAL | 40.0 | EACH | \$30.00 | \$1,200.00 | \$15.00 | \$16.50 | \$15.56 |
| 175 | XX008865 | PERMEABLE PLASTIC BERM | 222.0 | FOOT | \$11.00 | \$2,442.00 | \$12.50 | \$15.30 | \$14.45 |
| 176 | Z0013797 | STABILIZED CONSTRUCTION ENTRANCE | 516.0 | SQ YD | \$21.00 | \$10,836.00 | \$0.01 | \$25.00 | \$11.75 |
| 177 | Z0019600 | DUST CONTROL WATERING | 13.0 | UNIT | \$30.00 | \$390.00 | \$1.00 | \$120.00 | \$74.00 |
| 178 | Z0022800 | FENCE REMOVAL | 1,362.0 | FOOT | \$6.50 | \$8,853.00 | \$2.50 | \$5.00 | \$4.38 |
| 179 | Z0030850 | TEMPORARY INFORMATION SIGNING | 100.0 | SQ FT | \$18.00 | \$1,800.00 | \$12.24 | \$22.00 | \$17.56 |
| 180 | Z0033700 | LONGITUDINAL JOINT SEALANT | 6,424.0 | FOOT | \$3.00 | \$19,272.00 | \$2.85 | \$3.14 | \$2.94 |
| 181 | Z0036200 | PAINT CURB | 2,148.0 | FOOT | \$5.00 | \$10,740.00 | \$0.75 | \$3.00 | \$1.69 |
| 182 | Z0055905 | TEMPORARY CONSTRUCTION FENCE | 239.0 | FOOT | \$5.00 | \$1,195.00 | \$3.00 | \$7.00 | \$4.02 |
| 183 | Z0067900 | STEEL CASINGS 24" | 113.0 | FOOT | \$200.00 | \$22,600.00 | \$140.00 | \$230.00 | \$175.79 |
| 184 | Z0073510 | TEMPORARY TRAFFIC SIGNAL TIMING | 4.0 | EACH | \$1,300.00 | \$5,200.00 | \$548.00 | \$558.96 | \$550.74 |
| Bid Total | | | | | \$3,427,518.10 | | | | |