

Summary of Bids Received

Project: Gages Lake Road Resurfacing

Section: 20-00999-78-RS

Description: This project consists of resurfacing Gages Lake Road from US Route 45 to IL Route 21. The project will be a 1.5" mill and fill from US Route 45 to Hunt Club Road and a 2.25" mill and fill from Hunt Club Road to IL Route 21.

CPMS Pin: B-01537

Let Date: 3/15/2022

Bidder	Address	City, State, Zip	Bond	Bid Price	% Over/Under Eng. Estimate	\$ Over/Under Eng. Estimate
Peter Baker & Son Company	1349 Rockland Road	Lake Bluff, IL 60044	Bid Bond	\$1,781,075.60	-18.43%	-\$402,389.75
Payne & Dolan, Inc.	28435 W. Route 173	Antioch, IL 60002	Bid Bond	\$2,266,702.52	3.81%	\$83,237.17
Engineer's Estimate				\$2,183,465.35		

Design	_____	IDOT(2)	_____	Contract Bidder	_____	County Engineer	_____
Finance	_____	Bid Tab File	_____	Resident Eng.	_____	Mgr Capital Programming	_____
Construction	_____	Project File	_____	Request By Mail	_____		

Return Bid Tabulation

Project: Gages Lake Road Resurfacing

Section: 20-00999-78-RS

Description: This project consists of resurfacing Gages Lake Road from US Route 45 to IL Route 21. The project will be a 1.5" mill and fill from US Route 45 to Hunt Club Road and a 2.25" mill and fill from Hunt Club Road to IL Route 21.

CPMS Pin: B-01537

Let Date: 3/15/2022

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
1	20200600	EXCAVATING AND GRADING EXISTING SHOULDER	113.0	UNIT	\$250.00	\$28,250.00	\$340.00	\$38,420.00	\$387.10	\$43,742.30
2	20800150	TRENCH BACKFILL	9.0	CU YD	\$125.00	\$1,125.00	\$15.00	\$135.00	\$36.15	\$325.35
3	21301052	EXPLORATION TRENCH 52 INCH DEPTH	150.0	FOOT	\$20.00	\$3,000.00	\$50.00	\$7,500.00	\$30.95	\$4,642.50
4	25200200	SUPPLEMENTAL WATERING	124.0	UNIT	\$50.00	\$6,200.00	\$0.10	\$12.40	\$0.10	\$12.40
5	28000510	INLET FILTERS	96.0	EACH	\$175.00	\$16,800.00	\$145.00	\$13,920.00	\$145.00	\$13,920.00
6	35101400	AGGREGATE BASE COURSE, TYPE B	149.0	TON	\$35.00	\$5,215.00	\$45.00	\$6,705.00	\$12.00	\$1,788.00
7	40600290	BITUMINOUS MATERIALS (TACK COAT)	48,579.0	POUND	\$0.15	\$7,286.85	\$0.01	\$485.79	\$0.01	\$485.79
8	40600370	LONGITUDINAL JOINT SEALANT	23,874.0	FOOT	\$2.50	\$59,685.00	\$2.07	\$49,419.18	\$2.05	\$48,941.70
9	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	20.0	TON	\$200.00	\$4,000.00	\$500.00	\$10,000.00	\$150.00	\$3,000.00
10	40600901	HOT-MIX ASPHALT BINDER COURSE (HAND METHOD), N70	20.0	TON	\$200.00	\$4,000.00	\$500.00	\$10,000.00	\$150.00	\$3,000.00
11	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	1,260.0	TON	\$75.00	\$94,500.00	\$82.00	\$103,320.00	\$80.45	\$101,367.00
12	40603200	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50	898.0	TON	\$110.00	\$98,780.00	\$111.00	\$99,678.00	\$93.85	\$84,277.30
13	40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	6,433.0	TON	\$80.00	\$514,640.00	\$82.00	\$527,506.00	\$89.00	\$572,537.00
14	42001300	PROTECTIVE COAT	234.0	SQ YD	\$7.50	\$1,755.00	\$2.50	\$585.00	\$2.00	\$468.00
15	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	50,556.0	SQ YD	\$3.00	\$151,668.00	\$2.25	\$113,751.00	\$2.10	\$106,167.60
16	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	20,228.0	SQ YD	\$3.50	\$70,798.00	\$2.75	\$55,627.00	\$2.85	\$57,649.80
17	44000500	COMBINATION CURB AND GUTTER REMOVAL	1,000.0	FOOT	\$7.50	\$7,500.00	\$22.75	\$22,750.00	\$5.00	\$5,000.00

Return Bid Tabulation

Project: Gages Lake Road Resurfacing

Section: 20-00999-78-RS

Description: This project consists of resurfacing Gages Lake Road from US Route 45 to IL Route 21. The project will be a 1.5" mill and fill from US Route 45 to Hunt Club Road and a 2.25" mill and fill from Hunt Club Road to IL Route 21.

CPMS Pin: B-01537

Let Date: 3/15/2022

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extn. Price	Unit Price	Extn. Price	Unit Price	Extn. Price
18	44201785	CLASS D PATCHES, TYPE I, 12 INCH	183.0	SQ YD	\$75.00	\$13,725.00	\$145.00	\$26,535.00	\$40.00	\$7,320.00
19	44201789	CLASS D PATCHES, TYPE II, 12 INCH	274.0	SQ YD	\$75.00	\$20,550.00	\$105.00	\$28,770.00	\$40.00	\$10,960.00
20	44201794	CLASS D PATCHES, TYPE III, 12 INCH	822.0	SQ YD	\$75.00	\$61,650.00	\$71.50	\$58,773.00	\$40.00	\$32,880.00
21	44201796	CLASS D PATCHES, TYPE IV, 12 INCH	548.0	SQ YD	\$75.00	\$41,100.00	\$61.00	\$33,428.00	\$40.00	\$21,920.00
22	44201823	CLASS D PATCHES, TYPE I, 15 INCH	170.0	SQ YD	\$90.00	\$15,300.00	\$180.00	\$30,600.00	\$45.00	\$7,650.00
23	44201827	CLASS D PATCHES, TYPE II, 15 INCH	255.0	SQ YD	\$90.00	\$22,950.00	\$120.00	\$30,600.00	\$45.00	\$11,475.00
24	44201831	CLASS D PATCHES, TYPE III, 15 INCH	764.0	SQ YD	\$90.00	\$68,760.00	\$90.00	\$68,760.00	\$45.00	\$34,380.00
25	44201833	CLASS D PATCHES, TYPE IV, 15 INCH	510.0	SQ YD	\$90.00	\$45,900.00	\$77.00	\$39,270.00	\$45.00	\$22,950.00
26	48101200	AGGREGATE SHOULDERS, TYPE B	1,640.0	TON	\$25.00	\$41,000.00	\$43.00	\$70,520.00	\$25.00	\$41,000.00
27	50105220	PIPE CULVERT REMOVAL	216.0	FOOT	\$35.00	\$7,560.00	\$10.00	\$2,160.00	\$34.75	\$7,506.00
28	54262715	METAL FLARED END SECTIONS 15"	16.0	EACH	\$700.00	\$11,200.00	\$350.00	\$5,600.00	\$419.65	\$6,714.40
29	542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	181.0	FOOT	\$60.00	\$10,860.00	\$125.00	\$22,625.00	\$63.35	\$11,466.35
30	60100905	PIPE DRAINS 4"	100.0	FOOT	\$35.00	\$3,500.00	\$30.00	\$3,000.00	\$25.00	\$2,500.00
31	60100915	PIPE DRAINS 6"	100.0	FOOT	\$35.00	\$3,500.00	\$35.00	\$3,500.00	\$25.00	\$2,500.00
32	60300105	FRAMES AND GRATES TO BE ADJUSTED	96.0	EACH	\$500.00	\$48,000.00	\$400.00	\$38,400.00	\$175.00	\$16,800.00
33	60300305	FRAMES AND LIDS TO BE ADJUSTED	59.0	EACH	\$500.00	\$29,500.00	\$690.00	\$40,710.00	\$200.00	\$11,800.00
34	60603900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (ABUTTING EXISTING PAVEMENT)	500.0	FOOT	\$50.00	\$25,000.00	\$39.25	\$19,625.00	\$55.00	\$27,500.00
35	60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	500.0	FOOT	\$60.00	\$30,000.00	\$53.50	\$26,750.00	\$65.00	\$32,500.00
36	67100100	MOBILIZATION	1.0	L SUM	\$105,000.00	\$105,000.00	\$375,000.00	\$375,000.00	\$107,740.00	\$107,740.00
37	70300100	SHORT TERM PAVEMENT MARKING	28,521.0	FOOT	\$0.10	\$2,852.10	\$0.01	\$285.21	\$0.01	\$285.21

Return Bid Tabulation

Project: Gages Lake Road Resurfacing

Section: 20-00999-78-RS

Description: This project consists of resurfacing Gages Lake Road from US Route 45 to IL Route 21. The project will be a 1.5" mill and fill from US Route 45 to Hunt Club Road and a 2.25" mill and fill from Hunt Club Road to IL Route 21.

CPMS Pin: B-01537

Let Date: 3/15/2022

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
38	70300211	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS - PAINT	219.0	SQ FT	\$1.00	\$219.00	\$0.01	\$2.19	\$0.01	\$2.19
39	70300221	TEMPORARY PAVEMENT MARKING - LINE 4" - PAINT	14,847.0	FOOT	\$0.25	\$3,711.75	\$0.01	\$148.47	\$0.01	\$148.47
40	70300231	TEMPORARY PAVEMENT MARKING - LINE 5" - PAINT	11,570.0	FOOT	\$0.35	\$4,049.50	\$0.01	\$115.70	\$0.01	\$115.70
41	70300241	TEMPORARY PAVEMENT MARKING - LINE 6" - PAINT	746.0	FOOT	\$0.40	\$298.40	\$0.01	\$7.46	\$0.01	\$7.46
42	70300261	TEMPORARY PAVEMENT MARKING - LINE 12" - PAINT	646.0	FOOT	\$0.75	\$484.50	\$0.01	\$6.46	\$0.01	\$6.46
43	70300281	TEMPORARY PAVEMENT MARKING - LINE 24" - PAINT	60.0	FOOT	\$2.00	\$120.00	\$0.01	\$0.60	\$0.01	\$0.60
44	70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	11,436.0	FOOT	\$1.25	\$14,295.00	\$1.10	\$12,579.60	\$0.01	\$114.36
45	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	1,233.0	SQ FT	\$4.00	\$4,932.00	\$4.00	\$4,932.00	\$4.00	\$4,932.00
46	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	41,892.0	FOOT	\$0.60	\$25,135.20	\$0.55	\$23,040.60	\$0.55	\$23,040.60
47	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	32,170.0	FOOT	\$0.65	\$20,910.50	\$0.65	\$20,910.50	\$0.65	\$20,910.50
48	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	4,299.0	FOOT	\$0.75	\$3,224.25	\$0.85	\$3,654.15	\$0.85	\$3,654.15
49	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	2,066.0	FOOT	\$1.50	\$3,099.00	\$1.75	\$3,615.50	\$1.75	\$3,615.50
50	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	278.0	FOOT	\$4.00	\$1,112.00	\$4.00	\$1,112.00	\$4.00	\$1,112.00
51	78011000	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	1,453.0	SQ FT	\$3.00	\$4,359.00	\$2.00	\$2,906.00	\$2.00	\$2,906.00

Return Bid Tabulation

Project: Gages Lake Road Resurfacing

Section: 20-00999-78-RS

Description: This project consists of resurfacing Gages Lake Road from US Route 45 to IL Route 21. The project will be a 1.5" mill and fill from US Route 45 to Hunt Club Road and a 2.25" mill and fill from Hunt Club Road to IL Route 21.

CPMS Pin: B-01537

Let Date: 3/15/2022

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
52	78011025	GROOVING FOR RECESSED PAVEMENT MARKING 5"	41,767.0	FOOT	\$0.50	\$20,883.50	\$0.28	\$11,694.76	\$0.28	\$11,694.76
53	78011030	GROOVING FOR RECESSED PAVEMENT MARKING 6"	29,743.0	FOOT	\$0.55	\$16,358.65	\$0.35	\$10,410.05	\$0.35	\$10,410.05
54	78011035	GROOVING FOR RECESSED PAVEMENT MARKING 7"	4,299.0	FOOT	\$0.65	\$2,794.35	\$0.45	\$1,934.55	\$0.45	\$1,934.55
55	78011065	GROOVING FOR RECESSED PAVEMENT MARKING 13"	2,056.0	FOOT	\$2.00	\$4,112.00	\$1.00	\$2,056.00	\$1.00	\$2,056.00
56	78011125	GROOVING FOR RECESSED PAVEMENT MARKING 25"	192.0	FOOT	\$2.50	\$480.00	\$2.00	\$384.00	\$2.00	\$384.00
57	LC200051	REJECTED LOAD TRANSPORTATION	5.0	LOAD	\$500.00	\$2,500.00	\$200.00	\$1,000.00	\$150.00	\$750.00
58	LC200501	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	19,940.0	UNIT	\$1.00	\$19,940.00	\$1.00	\$19,940.00	\$1.00	\$19,940.00
59	LC400202	SEAL COAT	739.0	SQ YD	\$2.00	\$1,478.00	\$9.00	\$6,651.00	\$2.35	\$1,736.65
60	LC600200	INSTALL SURVEY MONUMENTS	8.0	EACH	\$1,000.00	\$8,000.00	\$1,450.00	\$11,600.00	\$620.00	\$4,960.00
61	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	5,797.0	SQ YD	\$20.00	\$115,940.00	\$4.00	\$23,188.00	\$5.95	\$34,492.15
62	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	3.0	CAL MO	\$3,000.00	\$9,000.00	\$3,400.00	\$10,200.00	\$1,000.00	\$3,000.00
63	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	1.0	L SUM	\$100,000.00	\$100,000.00	\$10,675.00	\$10,675.00	\$82,387.00	\$82,387.00
64	X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	11,683.0	SQ FT	\$0.60	\$7,009.80	\$1.50	\$17,524.50	\$0.01	\$116.83
65	X7810300	RECESSED REFLECTIVE PAVEMENT MARKER	161.0	EACH	\$50.00	\$8,050.00	\$32.50	\$5,232.50	\$32.50	\$5,232.50
66	XX006343	SEEDING (COMPLETE)	8,217.0	SQ YD	\$6.00	\$49,302.00	\$5.75	\$47,247.75	\$5.75	\$47,247.75
67	XX006658	FLOCCULATION LOGS	5.0	EACH	\$230.00	\$1,150.00	\$5.00	\$25.00	\$5.00	\$25.00

Return Bid Tabulation

Project: Gages Lake Road Resurfacing

Section: 20-00999-78-RS

Description: This project consists of resurfacing Gages Lake Road from US Route 45 to IL Route 21. The project will be a 1.5" mill and fill from US Route 45 to Hunt Club Road and a 2.25" mill and fill from Hunt Club Road to IL Route 21.

CPMS Pin: B-01537

Let Date: 3/15/2022

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
68	XX006659	FLOCCULATION POWDER	5.0	POUND	\$25.00	\$125.00	\$5.00	\$25.00	\$5.00	\$25.00
69	XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	483.0	SQ YD	\$90.00	\$43,470.00	\$58.00	\$28,014.00	\$59.85	\$28,907.55
70	XX009142	PAVEMENT MARKING REMOVAL (SPECIAL)	3,812.0	SQ FT	\$1.00	\$3,812.00	\$0.30	\$1,143.60	\$0.01	\$38.12
Bid Total						\$2,183,465.35		\$2,266,702.52		\$1,781,075.60

Return Bid Details

Project: Gages Lake Road Resurfacing

Section: 20-00999-78-RS

Description: This project consists of resurfacing Gages Lake Road from US Route 45 to IL Route 21. The project will be a 1.5" mill and fill from US Route 45 to Hunt Club Road and a 2.25" mill and fill from Hunt Club Road to IL Route 21.

CPMS Pin: B-01537

Let Date: 3/15/2022

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extn. Price			
1	20200600	EXCAVATING AND GRADING EXISTING SHOULDER	113.0	UNIT	\$250.00	\$28,250.00	\$340.00	\$387.10	\$363.55
2	20800150	TRENCH BACKFILL	9.0	CU YD	\$125.00	\$1,125.00	\$15.00	\$36.15	\$25.58
3	21301052	EXPLORATION TRENCH 52 INCH DEPTH	150.0	FOOT	\$20.00	\$3,000.00	\$30.95	\$50.00	\$40.48
4	25200200	SUPPLEMENTAL WATERING	124.0	UNIT	\$50.00	\$6,200.00	\$0.10	\$0.10	\$0.10
5	28000510	INLET FILTERS	96.0	EACH	\$175.00	\$16,800.00	\$145.00	\$145.00	\$145.00
6	35101400	AGGREGATE BASE COURSE, TYPE B	149.0	TON	\$35.00	\$5,215.00	\$12.00	\$45.00	\$28.50
7	40600290	BITUMINOUS MATERIALS (TACK COAT)	48,579.0	POUND	\$0.15	\$7,286.85	\$0.01	\$0.01	\$0.01
8	40600370	LONGITUDINAL JOINT SEALANT	23,874.0	FOOT	\$2.50	\$59,685.00	\$2.05	\$2.07	\$2.06
9	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	20.0	TON	\$200.00	\$4,000.00	\$150.00	\$500.00	\$325.00
10	40600901	HOT-MIX ASPHALT BINDER COURSE (HAND METHOD), N70	20.0	TON	\$200.00	\$4,000.00	\$150.00	\$500.00	\$325.00
11	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	1,260.0	TON	\$75.00	\$94,500.00	\$80.45	\$82.00	\$81.23
12	40603200	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50	898.0	TON	\$110.00	\$98,780.00	\$93.85	\$111.00	\$102.43

Return Bid Details

Project: Gages Lake Road Resurfacing

Section: 20-00999-78-RS

Description: This project consists of resurfacing Gages Lake Road from US Route 45 to IL Route 21. The project will be a 1.5" mill and fill from US Route 45 to Hunt Club Road and a 2.25" mill and fill from Hunt Club Road to IL Route 21.

CPMS Pin: B-01537

Let Date: 3/15/2022

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
13	40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	6,433.0	TON	\$80.00	\$514,640.00	\$82.00	\$89.00	\$85.50
14	42001300	PROTECTIVE COAT	234.0	SQ YD	\$7.50	\$1,755.00	\$2.00	\$2.50	\$2.25
15	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	50,556.0	SQ YD	\$3.00	\$151,668.00	\$2.10	\$2.25	\$2.18
16	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	20,228.0	SQ YD	\$3.50	\$70,798.00	\$2.75	\$2.85	\$2.80
17	44000500	COMBINATION CURB AND GUTTER REMOVAL	1,000.0	FOOT	\$7.50	\$7,500.00	\$5.00	\$22.75	\$13.88
18	44201785	CLASS D PATCHES, TYPE I, 12 INCH	183.0	SQ YD	\$75.00	\$13,725.00	\$40.00	\$145.00	\$92.50
19	44201789	CLASS D PATCHES, TYPE II, 12 INCH	274.0	SQ YD	\$75.00	\$20,550.00	\$40.00	\$105.00	\$72.50
20	44201794	CLASS D PATCHES, TYPE III, 12 INCH	822.0	SQ YD	\$75.00	\$61,650.00	\$40.00	\$71.50	\$55.75
21	44201796	CLASS D PATCHES, TYPE IV, 12 INCH	548.0	SQ YD	\$75.00	\$41,100.00	\$40.00	\$61.00	\$50.50
22	44201823	CLASS D PATCHES, TYPE I, 15 INCH	170.0	SQ YD	\$90.00	\$15,300.00	\$45.00	\$180.00	\$112.50
23	44201827	CLASS D PATCHES, TYPE II, 15 INCH	255.0	SQ YD	\$90.00	\$22,950.00	\$45.00	\$120.00	\$82.50
24	44201831	CLASS D PATCHES, TYPE III, 15 INCH	764.0	SQ YD	\$90.00	\$68,760.00	\$45.00	\$90.00	\$67.50
25	44201833	CLASS D PATCHES, TYPE IV, 15 INCH	510.0	SQ YD	\$90.00	\$45,900.00	\$45.00	\$77.00	\$61.00

Return Bid Details

Project: Gages Lake Road Resurfacing

Section: 20-00999-78-RS

Description: This project consists of resurfacing Gages Lake Road from US Route 45 to IL Route 21. The project will be a 1.5" mill and fill from US Route 45 to Hunt Club Road and a 2.25" mill and fill from Hunt Club Road to IL Route 21.

CPMS Pin: B-01537

Let Date: 3/15/2022

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
26	48101200	AGGREGATE SHOULDERS, TYPE B	1,640.0	TON	\$25.00	\$41,000.00	\$25.00	\$43.00	\$34.00
27	50105220	PIPE CULVERT REMOVAL	216.0	FOOT	\$35.00	\$7,560.00	\$10.00	\$34.75	\$22.38
28	54262715	METAL FLARED END SECTIONS 15"	16.0	EACH	\$700.00	\$11,200.00	\$350.00	\$419.65	\$384.83
29	542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	181.0	FOOT	\$60.00	\$10,860.00	\$63.35	\$125.00	\$94.18
30	60100905	PIPE DRAINS 4"	100.0	FOOT	\$35.00	\$3,500.00	\$25.00	\$30.00	\$27.50
31	60100915	PIPE DRAINS 6"	100.0	FOOT	\$35.00	\$3,500.00	\$25.00	\$35.00	\$30.00
32	60300105	FRAMES AND GRATES TO BE ADJUSTED	96.0	EACH	\$500.00	\$48,000.00	\$175.00	\$400.00	\$287.50
33	60300305	FRAMES AND LIDS TO BE ADJUSTED	59.0	EACH	\$500.00	\$29,500.00	\$200.00	\$690.00	\$445.00
34	60603900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (ABUTTING EXISTING PAVEMENT)	500.0	FOOT	\$50.00	\$25,000.00	\$39.25	\$55.00	\$47.13
35	60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	500.0	FOOT	\$60.00	\$30,000.00	\$53.50	\$65.00	\$59.25
36	67100100	MOBILIZATION	1.0	L SUM	\$105,000.00	\$105,000.00	\$107,740.00	\$375,000.00	\$241,370.00
37	70300100	SHORT TERM PAVEMENT MARKING	28,521.0	FOOT	\$0.10	\$2,852.10	\$0.01	\$0.01	\$0.01
38	70300211	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS - PAINT	219.0	SQ FT	\$1.00	\$219.00	\$0.01	\$0.01	\$0.01

Return Bid Details

Project: Gages Lake Road Resurfacing

Section: 20-00999-78-RS

Description: This project consists of resurfacing Gages Lake Road from US Route 45 to IL Route 21. The project will be a 1.5" mill and fill from US Route 45 to Hunt Club Road and a 2.25" mill and fill from Hunt Club Road to IL Route 21.

CPMS Pin: B-01537

Let Date: 3/15/2022

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
39	70300221	TEMPORARY PAVEMENT MARKING - LINE 4" - PAINT	14,847.0	FOOT	\$0.25	\$3,711.75	\$0.01	\$0.01	\$0.01
40	70300231	TEMPORARY PAVEMENT MARKING - LINE 5" - PAINT	11,570.0	FOOT	\$0.35	\$4,049.50	\$0.01	\$0.01	\$0.01
41	70300241	TEMPORARY PAVEMENT MARKING - LINE 6" - PAINT	746.0	FOOT	\$0.40	\$298.40	\$0.01	\$0.01	\$0.01
42	70300261	TEMPORARY PAVEMENT MARKING - LINE 12" - PAINT	646.0	FOOT	\$0.75	\$484.50	\$0.01	\$0.01	\$0.01
43	70300281	TEMPORARY PAVEMENT MARKING - LINE 24" - PAINT	60.0	FOOT	\$2.00	\$120.00	\$0.01	\$0.01	\$0.01
44	70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	11,436.0	FOOT	\$1.25	\$14,295.00	\$0.01	\$1.10	\$0.56
45	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	1,233.0	SQ FT	\$4.00	\$4,932.00	\$4.00	\$4.00	\$4.00
46	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	41,892.0	FOOT	\$0.60	\$25,135.20	\$0.55	\$0.55	\$0.55
47	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	32,170.0	FOOT	\$0.65	\$20,910.50	\$0.65	\$0.65	\$0.65
48	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	4,299.0	FOOT	\$0.75	\$3,224.25	\$0.85	\$0.85	\$0.85

Return Bid Details

Project: Gages Lake Road Resurfacing

Section: 20-00999-78-RS

Description: This project consists of resurfacing Gages Lake Road from US Route 45 to IL Route 21. The project will be a 1.5" mill and fill from US Route 45 to Hunt Club Road and a 2.25" mill and fill from Hunt Club Road to IL Route 21.

CPMS Pin: B-01537

Let Date: 3/15/2022

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
49	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	2,066.0	FOOT	\$1.50	\$3,099.00	\$1.75	\$1.75	\$1.75
50	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	278.0	FOOT	\$4.00	\$1,112.00	\$4.00	\$4.00	\$4.00
51	78011000	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	1,453.0	SQ FT	\$3.00	\$4,359.00	\$2.00	\$2.00	\$2.00
52	78011025	GROOVING FOR RECESSED PAVEMENT MARKING 5"	41,767.0	FOOT	\$0.50	\$20,883.50	\$0.28	\$0.28	\$0.28
53	78011030	GROOVING FOR RECESSED PAVEMENT MARKING 6"	29,743.0	FOOT	\$0.55	\$16,358.65	\$0.35	\$0.35	\$0.35
54	78011035	GROOVING FOR RECESSED PAVEMENT MARKING 7"	4,299.0	FOOT	\$0.65	\$2,794.35	\$0.45	\$0.45	\$0.45
55	78011065	GROOVING FOR RECESSED PAVEMENT MARKING 13"	2,056.0	FOOT	\$2.00	\$4,112.00	\$1.00	\$1.00	\$1.00
56	78011125	GROOVING FOR RECESSED PAVEMENT MARKING 25"	192.0	FOOT	\$2.50	\$480.00	\$2.00	\$2.00	\$2.00
57	LC200051	REJECTED LOAD TRANSPORTATION	5.0	LOAD	\$500.00	\$2,500.00	\$150.00	\$200.00	\$175.00
58	LC200501	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	19,940.0	UNIT	\$1.00	\$19,940.00	\$1.00	\$1.00	\$1.00
59	LC400202	SEAL COAT	739.0	SQ YD	\$2.00	\$1,478.00	\$2.35	\$9.00	\$5.68

Return Bid Details

Project: Gages Lake Road Resurfacing

Section: 20-00999-78-RS

Description: This project consists of resurfacing Gages Lake Road from US Route 45 to IL Route 21. The project will be a 1.5" mill and fill from US Route 45 to Hunt Club Road and a 2.25" mill and fill from Hunt Club Road to IL Route 21.

CPMS Pin: B-01537

Let Date: 3/15/2022

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
60	LC600200	INSTALL SURVEY MONUMENTS	8.0	EACH	\$1,000.00	\$8,000.00	\$620.00	\$1,450.00	\$1,035.00
61	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	5,797.0	SQ YD	\$20.00	\$115,940.00	\$4.00	\$5.95	\$4.98
62	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	3.0	CAL MO	\$3,000.00	\$9,000.00	\$1,000.00	\$3,400.00	\$2,200.00
63	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	1.0	L SUM	\$100,000.00	\$100,000.00	\$10,675.00	\$82,387.00	\$46,531.00
64	X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	11,683.0	SQ FT	\$0.60	\$7,009.80	\$0.01	\$1.50	\$0.76
65	X7810300	RECESSED REFLECTIVE PAVEMENT MARKER	161.0	EACH	\$50.00	\$8,050.00	\$32.50	\$32.50	\$32.50
66	XX006343	SEEDING (COMPLETE)	8,217.0	SQ YD	\$6.00	\$49,302.00	\$5.75	\$5.75	\$5.75
67	XX006658	FLOCCULATION LOGS	5.0	EACH	\$230.00	\$1,150.00	\$5.00	\$5.00	\$5.00
68	XX006659	FLOCCULATION POWDER	5.0	POUND	\$25.00	\$125.00	\$5.00	\$5.00	\$5.00
69	XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	483.0	SQ YD	\$90.00	\$43,470.00	\$58.00	\$59.85	\$58.93
70	XX009142	PAVEMENT MARKING REMOVAL (SPECIAL)	3,812.0	SQ FT	\$1.00	\$3,812.00	\$0.01	\$0.30	\$0.16
Bid Total					\$2,183,465.35				