



## Lake County Sheriff

Prepared for:  
Kurt Schultz

Lake County Sheriff's Department  
25 South Martin Luther King Jr. Drive  
Waukegan, IL 60085

Submitted by:  
Dave Bradford  
847.344.8989  
[dave@bradfordsystems.com](mailto:dave@bradfordsystems.com)

January 30, 2017  
BSC Project #22363

Bradford Systems Corporation is a qualified National IPA Contract provider and is proposing the following Spacesaver equipment and related services through:  
**Contract # P15-150-DT**

### Corporate

430 Country Club Drive  
Bensenville, IL 60106

630-350-3453 office  
630-350-3454 facsimile  
800-696-3453 toll-free

### Merchandise Mart

222 Merchandise Mart Plaza  
Suite 11-117  
Chicago, Illinois 60654

312-467-1727 office  
312-467-1447 facsimile

### Missouri & So. Illinois

1735 Larkin Williams Rd.  
Fenton, Missouri 63026

636-343-1515 office  
636-343-3588 facsimile  
800-696-3453 toll-free

### Central Illinois

125 Thunderbird Lane  
Suite 211  
East Peoria, Illinois 61611

309-698-0490 office  
309-698-0491 facsimile

### Indiana

3815 River Crossing Parkway  
Suite 100  
Indianapolis, Indiana 46240

317-895-0670 office  
317-895-0672 facsimile  
800-862-5036 toll-free

January 30, 2017

Kurt Schultz  
Lake County Sheriff's Department  
25 South Martin Luther King Jr. Drive  
Waukegan, IL 60085

Dear Kurt:


On behalf of Bradford Systems Corporation, I would like to thank you for the opportunity to present this proposal. The following solution has been designed and tailored to meet your storage needs.

We value the opportunity to present our unique capabilities, and look forward to showing you why thousands of clients over the last 48 years have chosen Bradford Systems Corporation to help them solve their most challenging storage dilemmas.

If you have any questions regarding this proposal or if we can make any changes to better accommodate your needs or requirements, please call me at 847.344.8989.

Again, thank you for your consideration.

Sincerely,



Dave Bradford  
Storage Planner

Bradford Systems Corporation  
430 Country Club Drive  
Bensenville, IL 60106  
(m) 847.344.8989  
[dave@bradfordsystems.com](mailto:dave@bradfordsystems.com)

**Lake County Sheriff**  
**Base Bid**  
Project #22363

**System #1 Main Evidence—High Density Storage Solution:**

**Spacesaver Eclipse Powered High-Density Mobile System:**

- 9 Mobile carriages with dual flange guidance, 48" D x 29' L
- 1 Mobile carriage with dual flange guidance, 52" D x 29' L
- 1 Mobile carriage with dual flange guidance, 60" D x 29' L
- Carriages have a continuous, full-length drive shaft driving all wheels on one side of the carriage
- 1 Stationary platforms, 48" D x 29' L
- 1 Fixed shelving range (to sit directly on the floor), 15" D x 29' L
- 1 B Rail system with 5 recessed rails @ 60' 11" L
- 13 Photo sweep beams—1 per aisle
- 13 Aisle entry sensors—1 per aisle
- 15 Steel end panels
- 1 Rechargeable power override unit with safety override key(s)

**Shelving Components:**

- 6 Four-post single-entry shelving sections, 15" D x 42" W x 143-3/4" H
- 2 Four-post single-entry shelving sections, 15" D x 48" W x 143-3/4" H
- 120 Four-post back to back single-entry shelving sections, 24" D x 42" W x 143-3/4" H
- 40 Four-post back to back single-entry shelving sections, 24" D x 48" W x 143-3/4" H
- 12 Four-post back to back single-entry shelving sections, 26" D x 42" W x 143-3/4" H
- 4 Four-post back to back single-entry shelving sections, 26" D x 48" W x 143-3/4" H
- 12 Four-post back to back single-entry shelving sections, 30" D x 42" W x 143-3/4" H
- 4 Four-post back to back single-entry shelving sections, 30" D x 48" W x 143-3/4" H
- All shelves are heavy-duty
- 8 Steel back panels

**Main Evidence Bike Racks:**

**Bike Storage Consists of:**

- 20 Bike hooks, 5"
- 2 Wall mounted 2" x 8" x 30' 6"
  - Rack will provide storage for 20 bikes. First bike hook is located 8" from wall and then each hook is places 16" on centers.

**System #4 Main Evidence—Rails for Future High Density Storage Solution:**

**Spacesaver Rail System:**

- 1 B Rail system with 5 recessed rails @ 14' L—for future high-density mobile system

**Lake County Sheriff**  
**Base Bid**  
Project #22363

**Systems #2 & #4 Main Evidence—Rails for Future ActivRAC Electric High Density Mobile Systems:**

**Spacesaver Rail Systems:**

- 1 B-rail system with 5 recessed rails @ 27' L—for future high-density mobile system
- 1 R-rail systems with 5 recessed rails @ 15' 4-3/8" L—for future high-density mobile system

**System #5 Clerk's Evidence—Rails for Future Mechanical Assist High Density Storage Rack Systems:**

**Spacesaver Mechanical Assist High-Density Mobile System:**

- 1 B Rail system with 5 recessed rails @ 14' 6" L—for future high-density mobile system

**Drug Vault**

**Spacesaver Fixed Shelving Storage System:**

- 1 Fixed shelving range (to sit directly on the floor), 30" D x 28' L
- 1 Fixed shelving range (to sit directly on the floor), 30" D x 29' L

**Shelving Components:**

- D1—3 Four-post single-entry shelving sections, 30" D x 42" W x 100-1/4" H
  - Each sections include 8 adjustable heavy-duty shelves, 1 top shelf and 1 front base 4-1/4" H
- D2—2 Four-post single-entry shelving sections, 30" D x 48" W x 100-1/4" H
  - Each sections include 8 adjustable heavy-duty shelves, 1 top shelf and 1 front base 4-1/4" H
- D3—11 Four-post single-entry shelving sections, 30" D x 42" W x 100-1/4" H
  - Each sections include 8 adjustable heavy-duty shelves, 1 top shelf and 1 front base 4-1/4" H

**Internal Records—Spacesaver Fixed Shelving Storage System:**

- 1 Fixed shelving range (to sit directly on the floor), 12" D x 28' L

**Shelving Components:**

- 8 Four-post single-entry shelving sections, 12" D x 42" W x 88-1/4" H
  - Each sections include 7 slotted shelves, 1 top shelf , 21 file dividers & 1 front base 4-1/4"H

**Lake County Sheriff**  
**Base Bid**  
Project #22363

**Pass-Thru Lockers at Evidence:**

- (1) Pass-thru evidence locker #ED3P01MS, 36" W x 24" D X 82" H
- Locker #ED3P04MS has 1 "B" door, 1 "D" door, 1 "E" door and 1 "E" door with a mail slot
  
- (1) Pass-thru evidence locker #ED3P04MSF4, 36" W x 24" D X 82" H
- Locker #ED3P04MS has 1 "D" door, 1 "D" door with refrigerator insert, 3 "E" doors and 1 "E" door with a mail slot
  
- (1) Pass-thru evidence lockers #ED3P10MS, 36" W x 24" D X 82" H
- Locker #ED3P10MS has 2 "E" doors, 2 "E" doors with a mail slot and 4 "FF" doors
  
- (1) Pass-thru evidence locker #ED3P17MS, 36" W x 24" D X 82" H
- Locker #ED3P17MS has 1 "A" door, 1 "D" door, 1 "E" door and 1 "E" door with a mail slot

**Door Sizes:**

- "A" door, 32-3/8" W x 37-5/16" H
- "D" door, 14-9/16" W x 37-5/16" H
- "E" door, 14-9/16" W x 18-19/32" H
- "FF" door, 14-9/16" W x 18-19/32" H

**Base Bid Total—Materials, Delivered & Installed:**

**\$348,255.00**

**Notes:**

1. The above quote is based on the drawings.
2. A non-refundable down payment of one-third (1/3) of the contract, is due upon order. A payment of 1/3 is due upon shipment and 1/3 payment upon completion.
3. This agreement is based on a normal eight hour working day Monday through Friday and no provisions have been made for overtime or shift premium pay. If overtime is required, additional costs will be incurred.
4. Pricing valid for 30 days.

**Lake County Sheriff**  
**Add Alternates**  
Project #22363

**Alternate 1—Clerk’s Evidence System—System #5 Balance:**

**Spacesaver Mechanical Assist High-Density Mobile System:**

- 2 Mobile carriages with dual flange guidance, 40” D x 21’ L
- Carriages have a continuous, full-length drive shaft driving all wheels on one side of the carriage
- 1 Stationary platform, 40” D x 21’ L
- 1 Fixed shelving range (to sit directly on the floor), 15” D x 28’ L
- 1 Fixed shelving range (to sit directly on the floor), 30” D x 15’ L
- 3 Steel end panels
- 1 Waist high lock

**Shelving Components:**

- 8 Four-post single-entry shelving sections, 15” D x 36” W x 101-3/4” H
- 5 Four-post single-entry shelving sections, 30” D x 36” W x 100-1/4” H
- 42 Four-post back to back single-entry shelving sections, 20” D x 36” W x 97-1/4” H
- 21 Steel back panels
- 168 Adjustable file dividers

**Bike Storage Consists of:**

- 5 Bike hooks, 5”
- 2 Wall mounted 2” x 8” x 8’ 6”
  - Rack will provide storage for 5 bikes. First bike hook is located 8” from wall and then each hook is places 16” on centers.

**Alternate 1—System #5 Clerk Evidence Balance—Total: \$46,400.00**

**Alternate 2—Main Evidence System #2—System Balance:**

**Spacesaver ActiveRAC™ 7P Electric Mobile System:**

- 4 Electric mobile carriages, 60-13/16” D x 29’ 9-1/2” L
- 4 Stanchions with electric controls
- 2 Fixed shelving ranges (to sit directly on the floor), 30-13/16” D x 29’ 9-1/2” L

**Shelving Components:**

- 40 Wide Span shelving sections, 30-13/16” D x 84” W x 144” H

**Alternate 2—Main Evidence Systems #2 Balance—Total: \$68,900.00**

**Notes:**

1. The above quote is based on the drawings.
2. A non-refundable down payment of one-third (1/3) of the contract, is due upon order. A payment of 1/3 is due upon shipment and 1/3 payment upon completion.
3. This agreement is based on a normal eight hour working day Monday through Friday and no provisions have been made for overtime or shift premium pay. If overtime is required, additional costs will be incurred.
4. Pricing valid for 30 day.

**Lake County Sheriff**  
**Add Alternates**  
Project #22363

**Alternate 3—Main Evidence System #4—System Balance:**

**Spacesaver ActiveRAC™ 7P Electric Mobile System:**

- 2 Electric mobile carriages, 60-13/16" D x 29' 9-1/2" L
- 2 Stanchions with electric controls
- 1 Fixed shelving ranges (to sit directly on the floor), 30-13/16" D x 29' 9-1/2" L

**Shelving Components:**

- 20 Wide Span shelving sections, 30-13/16" D x 84" W x 144" H

**Alternate 3—Main Evidence System #4 Balance—Total: \$35,900.00**

**Alternate 4—Main Evidence System #3—System Balance**

**Spacesaver Eclipse High-Density Mobile System:**

- 1 Mobile carriage with dual flange guidance, 48" D x 29' L
- 1 Mobile carriage with dual flange guidance, 54" D x 29' L
- Carriages have a continuous, full-length drive shaft driving all wheels on one side of the carriage
- 1 Fixed shelving range (to sit directly on the floor), 15" D x 29' L
- 3 Photo sweep beams—1 per aisle
- 3 Aisle entry sensors—1 per aisle
- 3 Steel end panels
- 1 Rechargeable power override unit with safety override key(s)

**Shelving Components:**

- 2 Four-post single-entry shelving sections, 15" D x 48" W x 143-3/4" H
- 6 Four-post single-entry shelving sections, 15" D x 42" W x 143-3/4" H
- 4 Four-post back to back single-entry shelving sections, 24" D x 48" W x 143-3/4" H
- 12 Four-post back to back single-entry shelving sections, 24" D x 42" W x 143-3/4" H
- 2 Four-post single-entry shelving sections, 15" D x 48" W x 143-3/4" H
- 6 Four-post single-entry shelving sections, 15" D x 42" W x 143-3/4" H
- 4 Four-post back to back single-entry shelving sections, 26" D x 48" W x 143-3/4" H
- 12 Four-post back to back single-entry shelving sections, 26" D x 42" W x 143-3/4" H

**Alternate 4—Main Evidence System #3 Balance—Total: \$56,400.00**

**Notes:**

1. The above quote is based on the drawings.
2. A non-refundable down payment of one-third (1/3) of the contract, is due upon order. A payment of 1/3 is due upon shipment and 1/3 payment upon completion.
3. This agreement is based on a normal eight hour working day Monday through Friday and no provisions have been made for overtime or shift premium pay. If overtime is required, additional costs will be incurred.
4. Pricing valid for 30 days.

**Lake County Sheriff**  
**Add Alternates**  
Project #22363

**Alternate 5—EMA Garage Bays—Shelving:**

**Spacesaver RaptorRAC Shelving:**

- 1 Fixed shelving ranges (to sit directly on the floor), 30-13/16" D x 18' 10-1/4" L

**Shelving Components:**

- 3 Wide Span shelving sections, 30-13/16" D x 72" W x 120" H
  - Each section has 5 levels with ribbed decking

**Alternate 5—EMA Garage Bays Shelving—Total: \$4,400.00**

**Alternate 6—Health Department Garage Bays—Shelving:**

**Spacesaver RaptorRAC Shelving:**

- 1 Fixed shelving ranges (to sit directly on the floor), 30-13/16" D x 18' 10-1/4" L

**Shelving Components:**

- 3 Wide Span shelving sections, 30-13/16" D x 72" W x 120" H
  - Each section has 5 levels with ribbed decking

**Alternate 6—Health Department Garage Bays Shelving—Total: \$5,600.00**

**Notes:**

1. The above quote is based on the drawings.
2. A non-refundable down payment of one-third (1/3) of the contract, is due upon order. A payment of 1/3 is due upon shipment and 1/3 payment upon completion.
3. This agreement is based on a normal eight hour working day Monday through Friday and no provisions have been made for overtime or shift premium pay. If overtime is required, additional costs will be incurred.
4. Pricing valid for 30 days.



**Lake County Sheriff  
Totals**

Project #22363

**PROJECT TOTALS:**

<b>Base Bid</b>	<b>\$348,255.00</b>
Alternate 1—Clerk Evidence System #5	\$46,400.00
Alternate 2—Main Evidence System #2	\$68,900.00
Alternate 3—Main Evidence System #3	\$35,900.00
Alternate 4—Main Evidence System #4	\$56,400.00
Alternate 5—EMA Garage Bays	\$4,400.00
Alternate 6—Health Dept. Garage Bays	\$5,600.00
<b>Total Alternates</b>	<b>\$217,600.00</b>
 <b>Project Grand Total</b>	 <b>\$565,855.00</b>