

Summary of Bids Received

Project: Almond Road Resurfacing

Section: 17-00999-33-RS

Description: Resurfacing of Almond Road from Fairfield Lane to Washington Street

CPMS Pin: B-01389

Let Date: 3/20/2018

Bidder	Address	City, State, Zip	Bond	Bid Price	% Over/Under Eng. Estimate	\$ Over/Under Eng. Estimate
Peter Baker & Son Company	1349 Rockland Road	Lake Bluff, IL 60044	Bid Bond	\$930,226.84	-29.34%	-\$386,250.52
J. A. Johnson Paving Company	1025 E. Addison Court	Arlington Heights, IL 60005	Bid Bond	\$966,281.15	-26.60%	-\$350,196.21
Payne & Dolan, Inc.	28435 W. Route 173	Antioch, IL 60002	Bid Bond	\$1,123,540.79	-14.66%	-\$192,936.57
Engineer's Estimate				\$1,316,477.36		

Design	_____	IDOT(2)	_____	Contract Bidder	_____	SES then Plan Rack	_____
Finance	_____	Bid Tab File	_____	Resident Eng.	_____	Administrative Assistant	_____
Construction	_____	Project File	_____	Request By Mail	_____	Mgr Capital Programming	_____

Bid Tabulation

Project: Almond Road Resurfacing
Section: 17-00999-33-RS
Description: Resurfacing of Almond Road from Fairfield Lane to Washington Street
CPMS Pin: B-01389
Let Date: 3/20/2018

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		J. A. Johnson Paving Company		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
1	20200100	EARTH EXCAVATION	505.0	CU YD	\$45.00	\$22,725.00	\$15.00	\$7,575.00	\$63.00	\$31,815.00	\$53.35	\$26,941.75
2	25200200	SUPPLEMENTAL WATERING	26.0	UNIT	\$50.00	\$1,300.00	\$25.00	\$650.00	\$0.10	\$2.60	\$40.00	\$1,040.00
3	35101400	AGGREGATE BASE COURSE, TYPE B	368.0	TON	\$30.00	\$11,040.00	\$20.00	\$7,360.00	\$32.00	\$11,776.00	\$5.00	\$1,840.00
4	40600290	BITUMINOUS MATERIALS (TACK COAT)	15,561.0	POUND	\$0.01	\$155.61	\$0.01	\$155.61	\$0.01	\$155.61	\$1.10	\$17,117.10
5	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	5.0	TON	\$500.00	\$2,500.00	\$500.00	\$2,500.00	\$135.00	\$675.00	\$50.00	\$250.00
6	40600525	LEVELING BINDER (HAND METHOD), N50	5.0	TON	\$140.00	\$700.00	\$500.00	\$2,500.00	\$120.00	\$600.00	\$50.00	\$250.00
7	40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	1,599.0	TON	\$75.00	\$119,925.00	\$80.00	\$127,920.00	\$100.00	\$159,900.00	\$78.10	\$124,881.90
8	40600990	TEMPORARY RAMP	151.0	SQ YD	\$10.00	\$1,510.00	\$10.00	\$1,510.00	\$32.00	\$4,832.00	\$5.00	\$755.00
9	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	223.0	TON	\$70.00	\$15,610.00	\$5.00	\$1,115.00	\$107.00	\$23,861.00	\$69.35	\$15,465.05
10	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	3,158.0	TON	\$70.00	\$221,060.00	\$64.00	\$202,112.00	\$92.00	\$290,536.00	\$59.25	\$187,111.50
11	42001300	PROTECTIVE COAT	1,482.0	SQ YD	\$2.00	\$2,964.00	\$1.00	\$1,482.00	\$2.50	\$3,705.00	\$2.50	\$3,705.00
12	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	9,398.0	SQ FT	\$8.00	\$75,184.00	\$6.25	\$58,737.50	\$6.60	\$62,026.80	\$6.60	\$62,026.80
13	42400800	DETECTABLE WARNINGS	980.0	SQ FT	\$25.00	\$24,500.00	\$24.00	\$23,520.00	\$35.00	\$34,300.00	\$35.00	\$34,300.00
14	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	32,262.0	SQ YD	\$3.00	\$96,786.00	\$2.25	\$72,589.50	\$2.15	\$69,363.30	\$2.00	\$64,524.00
15	44000500	COMBINATION CURB AND GUTTER REMOVAL	2,191.0	FOOT	\$10.00	\$21,910.00	\$6.00	\$13,146.00	\$7.00	\$15,337.00	\$7.00	\$15,337.00
16	44000600	SIDEWALK REMOVAL	6,808.0	SQ FT	\$3.00	\$20,424.00	\$2.15	\$14,637.20	\$1.25	\$8,510.00	\$0.25	\$1,702.00
17	44004250	PAVED SHOULDER REMOVAL	224.0	SQ YD	\$15.00	\$3,360.00	\$45.00	\$10,080.00	\$1.90	\$425.60	\$2.00	\$448.00
18	44201725	CLASS D PATCHES, TYPE I, 7 INCH	60.0	SQ YD	\$50.00	\$3,000.00	\$10.00	\$600.00	\$20.00	\$1,200.00	\$20.00	\$1,200.00
19	44201729	CLASS D PATCHES, TYPE II, 7 INCH	90.0	SQ YD	\$50.00	\$4,500.00	\$10.00	\$900.00	\$20.00	\$1,800.00	\$20.00	\$1,800.00
20	44201733	CLASS D PATCHES, TYPE III, 7 INCH	269.0	SQ YD	\$50.00	\$13,450.00	\$10.00	\$2,690.00	\$20.00	\$5,380.00	\$20.00	\$5,380.00
21	44201735	CLASS D PATCHES, TYPE IV, 7 INCH	180.0	SQ YD	\$50.00	\$9,000.00	\$10.00	\$1,800.00	\$20.00	\$3,600.00	\$20.00	\$3,600.00
22	44201749	CLASS D PATCHES, TYPE I, 9 INCH	72.0	SQ YD	\$50.00	\$3,600.00	\$11.00	\$792.00	\$25.00	\$1,800.00	\$22.00	\$1,584.00
23	44201753	CLASS D PATCHES, TYPE II, 9 INCH	107.0	SQ YD	\$50.00	\$5,350.00	\$11.00	\$1,177.00	\$25.00	\$2,675.00	\$22.00	\$2,354.00
24	44201757	CLASS D PATCHES, TYPE III, 9 INCH	321.0	SQ YD	\$50.00	\$16,050.00	\$11.00	\$3,531.00	\$25.00	\$8,025.00	\$22.00	\$7,062.00
25	44201759	CLASS D PATCHES, TYPE IV, 9 INCH	214.0	SQ YD	\$50.00	\$10,700.00	\$11.00	\$2,354.00	\$25.00	\$5,350.00	\$22.00	\$4,708.00
26	44201859	CLASS D PATCHES, TYPE I, 18 INCH	23.0	SQ YD	\$50.00	\$1,150.00	\$12.00	\$276.00	\$50.00	\$1,150.00	\$30.00	\$690.00
27	44201863	CLASS D PATCHES, TYPE II, 18 INCH	34.0	SQ YD	\$50.00	\$1,700.00	\$12.00	\$408.00	\$50.00	\$1,700.00	\$30.00	\$1,020.00
28	44201867	CLASS D PATCHES, TYPE III, 18 INCH	102.0	SQ YD	\$50.00	\$5,100.00	\$12.00	\$1,224.00	\$50.00	\$5,100.00	\$30.00	\$3,060.00
29	44201869	CLASS D PATCHES, TYPE IV, 18 INCH	68.0	SQ YD	\$50.00	\$3,400.00	\$12.00	\$816.00	\$50.00	\$3,400.00	\$30.00	\$2,040.00

Bid Tabulation

Project: Almond Road Resurfacing
Section: 17-00999-33-RS
Description: Resurfacing of Almond Road from Fairfield Lane to Washington Street
CPMS Pin: B-01389
Let Date: 3/20/2018

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		J. A. Johnson Paving Company		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
30	48101500	AGGREGATE SHOULDERS, TYPE B 6"	664.0	SQ YD	\$15.00	\$9,960.00	\$17.00	\$11,288.00	\$15.75	\$10,458.00	\$6.25	\$4,150.00
31	56109210	WATER VALVES TO BE ADJUSTED	2.0	EACH	\$1,000.00	\$2,000.00	\$180.00	\$360.00	\$350.00	\$700.00	\$595.00	\$1,190.00
32	60300105	FRAMES AND GRATES TO BE ADJUSTED	54.0	EACH	\$750.00	\$40,500.00	\$375.00	\$20,250.00	\$400.00	\$21,600.00	\$100.00	\$5,400.00
33	60300305	FRAMES AND LIDS TO BE ADJUSTED	9.0	EACH	\$750.00	\$6,750.00	\$300.00	\$2,700.00	\$800.00	\$7,200.00	\$100.00	\$900.00
34	60600605	CONCRETE CURB, TYPE B	4.0	FOOT	\$40.00	\$160.00	\$19.00	\$76.00	\$18.00	\$72.00	\$18.00	\$72.00
35	60603900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (ABUTTING EXISTING PAVEMENT)	470.0	FOOT	\$50.00	\$23,500.00	\$24.00	\$11,280.00	\$18.00	\$8,460.00	\$18.00	\$8,460.00
36	60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	912.0	FOOT	\$55.00	\$50,160.00	\$28.00	\$25,536.00	\$20.00	\$18,240.00	\$20.00	\$18,240.00
37	60609300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12 (ABUTTING EXISTING PAVEMENT)	823.0	FOOT	\$50.00	\$41,150.00	\$23.00	\$18,929.00	\$18.00	\$14,814.00	\$18.00	\$14,814.00
38	67100100	MOBILIZATION	1.0	L SUM	\$60,948.03	\$60,948.03	\$48,000.00	\$48,000.00	\$16,500.00	\$16,500.00	\$48,260.00	\$48,260.00
39	70300100	SHORT TERM PAVEMENT MARKING	33,561.0	FOOT	\$0.10	\$3,356.10	\$0.01	\$335.61	\$0.55	\$18,458.55	\$0.35	\$11,746.35
40	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	291.2	SQ FT	\$1.00	\$291.20	\$0.01	\$2.91	\$0.15	\$43.68	\$0.01	\$2.91
41	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	17,297.0	FOOT	\$0.25	\$4,324.25	\$0.01	\$172.97	\$0.15	\$2,594.55	\$0.01	\$172.97
42	70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	15,416.0	FOOT	\$0.25	\$3,854.00	\$0.01	\$154.16	\$0.15	\$2,312.40	\$0.01	\$154.16
43	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	1,951.0	FOOT	\$0.25	\$487.75	\$0.01	\$19.51	\$0.15	\$292.65	\$0.01	\$19.51
44	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	285.0	FOOT	\$0.50	\$142.50	\$0.01	\$2.85	\$0.15	\$42.75	\$0.01	\$2.85
45	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	2,364.0	FOOT	\$1.25	\$2,955.00	\$0.01	\$23.64	\$0.15	\$354.60	\$0.01	\$23.64
46	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	240.0	FOOT	\$2.50	\$600.00	\$0.01	\$2.40	\$0.15	\$36.00	\$0.01	\$2.40
47	70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	8,391.0	FOOT	\$1.20	\$10,069.20	\$0.01	\$83.91	\$1.15	\$9,649.65	\$0.80	\$6,712.80
48	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	38.0	FOOT	\$1.25	\$47.50	\$0.79	\$30.02	\$0.50	\$19.00	\$0.50	\$19.00
49	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	1,060.0	FOOT	\$1.50	\$1,590.00	\$0.97	\$1,028.20	\$0.60	\$636.00	\$0.60	\$636.00

Bid Tabulation

Project: Almond Road Resurfacing
Section: 17-00999-33-RS
Description: Resurfacing of Almond Road from Fairfield Lane to Washington Street
CPMS Pin: B-01389
Let Date: 3/20/2018

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		J. A. Johnson Paving Company		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
50	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	234.0	FOOT	\$4.00	\$936.00	\$1.49	\$348.66	\$1.40	\$327.60	\$1.40	\$327.60
51	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	23.0	FOOT	\$8.00	\$184.00	\$3.89	\$89.47	\$4.00	\$92.00	\$4.00	\$92.00
52	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	50.0	FOOT	\$25.00	\$1,250.00	\$19.80	\$990.00	\$44.60	\$2,230.00	\$44.10	\$2,205.00
53	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	1.0	EACH	\$1,500.00	\$1,500.00	\$964.20	\$964.20	\$2,200.00	\$2,200.00	\$2,080.00	\$2,080.00
54	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	350.0	FOOT	\$1.00	\$350.00	\$1.30	\$455.00	\$1.20	\$420.00	\$1.20	\$420.00
55	87600200	PEDESTRIAN PUSH-BUTTON POST, TYPE II	2.0	EACH	\$2,000.00	\$4,000.00	\$911.40	\$1,822.80	\$1,900.00	\$3,800.00	\$1,869.00	\$3,738.00
56	87800100	CONCRETE FOUNDATION, TYPE A	4.0	FOOT	\$125.00	\$500.00	\$361.60	\$1,446.40	\$440.00	\$1,760.00	\$432.50	\$1,730.00
57	87900200	DRILL EXISTING HANDHOLE	2.0	EACH	\$300.00	\$600.00	\$328.20	\$656.40	\$545.00	\$1,090.00	\$537.00	\$1,074.00
58	88800100	PEDESTRIAN PUSH-BUTTON	4.0	EACH	\$400.00	\$1,600.00	\$741.80	\$2,967.20	\$565.00	\$2,260.00	\$559.00	\$2,236.00
59	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	1.0	EACH	\$1,000.00	\$1,000.00	\$89.00	\$89.00	\$1,060.00	\$1,060.00	\$1,040.00	\$1,040.00
60	LC200051	REJECTED LOAD TRANSPORTATION	5.0	LOAD	\$500.00	\$2,500.00	\$160.00	\$800.00	\$750.00	\$3,750.00	\$250.00	\$1,250.00
61	LC400202	SEAL COAT	7,266.0	SQ YD	\$2.00	\$14,532.00	\$1.50	\$10,899.00	\$2.00	\$14,532.00	\$1.35	\$9,809.10
62	LC600200	INSTALL SURVEY MONUMENTS	1.0	EACH	\$1,000.00	\$1,000.00	\$1,500.00	\$1,500.00	\$1,000.00	\$1,000.00	\$820.00	\$820.00
63	LC780020	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LETTERS AND SYMBOLS	291.2	SQ FT	\$7.00	\$2,038.40	\$5.59	\$1,627.81	\$5.50	\$1,601.60	\$5.50	\$1,601.60
64	LC780021	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LINE 4"	17,260.0	FOOT	\$1.25	\$21,575.00	\$0.89	\$15,361.40	\$0.75	\$12,945.00	\$0.75	\$12,945.00
65	LC780022	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LINE 5"	14,356.0	FOOT	\$1.50	\$21,534.00	\$1.09	\$15,648.04	\$0.85	\$12,202.60	\$0.85	\$12,202.60
66	LC780023	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LINE 6"	1,951.0	FOOT	\$2.00	\$3,902.00	\$1.39	\$2,711.89	\$0.95	\$1,853.45	\$0.95	\$1,853.45
67	LC780024	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LINE 8"	285.0	FOOT	\$3.00	\$855.00	\$2.40	\$684.00	\$1.50	\$427.50	\$1.50	\$427.50
68	LC780025	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LINE 12"	2,364.0	FOOT	\$4.00	\$9,456.00	\$2.79	\$6,595.56	\$2.00	\$4,728.00	\$2.00	\$4,728.00
69	LC780026	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LINE 24"	217.0	FOOT	\$8.00	\$1,736.00	\$5.59	\$1,213.03	\$5.00	\$1,085.00	\$5.00	\$1,085.00
70	X0325476	RADAR VEHICLE DETECTION SYSTEM	1.0	EACH	\$35,000.00	\$35,000.00	\$35,174.40	\$35,174.40	\$36,200.00	\$36,200.00	\$35,786.00	\$35,786.00
71	X0327036	BIKE PATH REMOVAL	1,377.0	SQ YD	\$15.00	\$20,655.00	\$5.03	\$6,926.31	\$10.00	\$13,770.00	\$8.00	\$11,016.00

Bid Tabulation

Project: Almond Road Resurfacing
Section: 17-00999-33-RS
Description: Resurfacing of Almond Road from Fairfield Lane to Washington Street
CPMS Pin: B-01389
Let Date: 3/20/2018

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		J. A. Johnson Paving Company		Payne & Dolan, Inc.		Peter Baker & Son Company	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
72	X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	117.0	SQ FT	\$5.00	\$585.00	\$17.00	\$1,989.00	\$15.40	\$1,801.80	\$15.40	\$1,801.80
73	X1400102	OUTDOOR RATED NETWORK CABLE	163.0	FOOT	\$5.00	\$815.00	\$1.60	\$260.80	\$2.85	\$464.55	\$2.80	\$456.40
74	X1400215	REMOTE CONTROLLED VIDEO SYSTEM	1.0	EACH	\$8,000.00	\$8,000.00	\$5,045.70	\$5,045.70	\$4,820.00	\$4,820.00	\$4,766.00	\$4,766.00
75	X1400216	LAYER II (DATALINK) SWITCH	1.0	EACH	\$5,500.00	\$5,500.00	\$5,071.80	\$5,071.80	\$5,175.00	\$5,175.00	\$5,120.00	\$5,120.00
76	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	2,316.0	SQ YD	\$5.50	\$12,738.00	\$2.00	\$4,632.00	\$5.30	\$12,274.80	\$5.55	\$12,853.80
77	X4810200	AGGREGATE SHOULDER REMOVAL	148.0	CU YD	\$15.00	\$2,220.00	\$25.00	\$3,700.00	\$16.00	\$2,368.00	\$67.15	\$9,938.20
78	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	3.0	CAL MO	\$3,000.00	\$9,000.00	\$3,000.00	\$9,000.00	\$1,150.00	\$3,450.00	\$1,000.00	\$3,000.00
79	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	1.0	L SUM	\$36,568.82	\$36,568.82	\$65,000.00	\$65,000.00	\$7,000.00	\$7,000.00	\$14,100.00	\$14,100.00
80	X7810300	RECESSED REFLECTIVE PAVEMENT MARKER	107.0	EACH	\$30.00	\$3,210.00	\$30.00	\$3,210.00	\$42.00	\$4,494.00	\$42.00	\$4,494.00
81	X8570215	FULL-ACTUATED CONTROLLER IN EXISTING CABINET	1.0	EACH	\$4,000.00	\$4,000.00	\$3,819.90	\$3,819.90	\$5,560.00	\$5,560.00	\$5,501.00	\$5,501.00
82	XX003168	WORK ZONE PAVEMENT MARKING REMOVAL, SPECIAL	8,391.0	FOOT	\$1.00	\$8,391.00	\$0.01	\$83.91	\$0.35	\$2,936.85	\$0.25	\$2,097.75
83	XX006344	SODDING (COMPLETE)	1,685.0	SQ YD	\$35.00	\$58,975.00	\$10.00	\$16,850.00	\$13.50	\$22,747.50	\$14.75	\$24,853.75
84	Z0010688	CAMERA MOUNTING ASSEMBLY	1.0	EACH	\$1,500.00	\$1,500.00	\$2,294.00	\$2,294.00	\$4,115.00	\$4,115.00	\$4,070.00	\$4,070.00
85	Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	1.0	EACH	\$3,500.00	\$3,500.00	\$1,476.60	\$1,476.60	\$1,410.00	\$1,410.00	\$1,395.00	\$1,395.00
86	Z0033700	LONGITUDINAL JOINT SEALANT	16,636.0	FOOT	\$2.00	\$33,272.00	\$1.83	\$30,443.88	\$2.05	\$34,103.80	\$0.85	\$14,140.60
Bid Total						\$1,316,477.36		\$966,281.15		\$1,123,540.79		\$930,226.84

Return Bid Details

Project: Almond Road Resurfacing
Section: 17-00999-33-RS
Description: Resurfacing of Almond Road from Fairfield Lane to Washington Street
CPMS Pin: B-01389
Let Date: 3/20/2018

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
1	20200100	EARTH EXCAVATION	505.0	CU YD	\$45.00	\$22,725.00	\$15.00	\$63.00	\$43.78
2	25200200	SUPPLEMENTAL WATERING	26.0	UNIT	\$50.00	\$1,300.00	\$0.10	\$40.00	\$21.70
3	35101400	AGGREGATE BASE COURSE, TYPE B	368.0	TON	\$30.00	\$11,040.00	\$5.00	\$32.00	\$19.00
4	40600290	BITUMINOUS MATERIALS (TACK COAT)	15,561.0	POUND	\$0.01	\$155.61	\$0.01	\$1.10	\$0.37
5	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	5.0	TON	\$500.00	\$2,500.00	\$50.00	\$500.00	\$228.33
6	40600525	LEVELING BINDER (HAND METHOD), N50	5.0	TON	\$140.00	\$700.00	\$50.00	\$500.00	\$223.33
7	40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	1,599.0	TON	\$75.00	\$119,925.00	\$78.10	\$100.00	\$86.03
8	40600990	TEMPORARY RAMP	151.0	SQ YD	\$10.00	\$1,510.00	\$5.00	\$32.00	\$15.67
9	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	223.0	TON	\$70.00	\$15,610.00	\$5.00	\$107.00	\$60.45
10	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	3,158.0	TON	\$70.00	\$221,060.00	\$59.25	\$92.00	\$71.75
11	42001300	PROTECTIVE COAT	1,482.0	SQ YD	\$2.00	\$2,964.00	\$1.00	\$2.50	\$2.00
12	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	9,398.0	SQ FT	\$8.00	\$75,184.00	\$6.25	\$6.60	\$6.48
13	42400800	DETECTABLE WARNINGS	980.0	SQ FT	\$25.00	\$24,500.00	\$24.00	\$35.00	\$31.33
14	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	32,262.0	SQ YD	\$3.00	\$96,786.00	\$2.00	\$2.25	\$2.13

Return Bid Details

Project: Almond Road Resurfacing
Section: 17-00999-33-RS
Description: Resurfacing of Almond Road from Fairfield Lane to Washington Street
CPMS Pin: B-01389
Let Date: 3/20/2018

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
15	44000500	COMBINATION CURB AND GUTTER REMOVAL	2,191.0	FOOT	\$10.00	\$21,910.00	\$6.00	\$7.00	\$6.67
16	44000600	SIDEWALK REMOVAL	6,808.0	SQ FT	\$3.00	\$20,424.00	\$0.25	\$2.15	\$1.22
17	44004250	PAVED SHOULDER REMOVAL	224.0	SQ YD	\$15.00	\$3,360.00	\$1.90	\$45.00	\$16.30
18	44201725	CLASS D PATCHES, TYPE I, 7 INCH	60.0	SQ YD	\$50.00	\$3,000.00	\$10.00	\$20.00	\$16.67
19	44201729	CLASS D PATCHES, TYPE II, 7 INCH	90.0	SQ YD	\$50.00	\$4,500.00	\$10.00	\$20.00	\$16.67
20	44201733	CLASS D PATCHES, TYPE III, 7 INCH	269.0	SQ YD	\$50.00	\$13,450.00	\$10.00	\$20.00	\$16.67
21	44201735	CLASS D PATCHES, TYPE IV, 7 INCH	180.0	SQ YD	\$50.00	\$9,000.00	\$10.00	\$20.00	\$16.67
22	44201749	CLASS D PATCHES, TYPE I, 9 INCH	72.0	SQ YD	\$50.00	\$3,600.00	\$11.00	\$25.00	\$19.33
23	44201753	CLASS D PATCHES, TYPE II, 9 INCH	107.0	SQ YD	\$50.00	\$5,350.00	\$11.00	\$25.00	\$19.33
24	44201757	CLASS D PATCHES, TYPE III, 9 INCH	321.0	SQ YD	\$50.00	\$16,050.00	\$11.00	\$25.00	\$19.33
25	44201759	CLASS D PATCHES, TYPE IV, 9 INCH	214.0	SQ YD	\$50.00	\$10,700.00	\$11.00	\$25.00	\$19.33
26	44201859	CLASS D PATCHES, TYPE I, 18 INCH	23.0	SQ YD	\$50.00	\$1,150.00	\$12.00	\$50.00	\$30.67
27	44201863	CLASS D PATCHES, TYPE II, 18 INCH	34.0	SQ YD	\$50.00	\$1,700.00	\$12.00	\$50.00	\$30.67
28	44201867	CLASS D PATCHES, TYPE III, 18 INCH	102.0	SQ YD	\$50.00	\$5,100.00	\$12.00	\$50.00	\$30.67
29	44201869	CLASS D PATCHES, TYPE IV, 18 INCH	68.0	SQ YD	\$50.00	\$3,400.00	\$12.00	\$50.00	\$30.67
30	48101500	AGGREGATE SHOULDERS, TYPE B 6"	664.0	SQ YD	\$15.00	\$9,960.00	\$6.25	\$17.00	\$13.00
31	56109210	WATER VALVES TO BE ADJUSTED	2.0	EACH	\$1,000.00	\$2,000.00	\$180.00	\$595.00	\$375.00
32	60300105	FRAMES AND GRATES TO BE ADJUSTED	54.0	EACH	\$750.00	\$40,500.00	\$100.00	\$400.00	\$291.67
33	60300305	FRAMES AND LIDS TO BE ADJUSTED	9.0	EACH	\$750.00	\$6,750.00	\$100.00	\$800.00	\$400.00
34	60600605	CONCRETE CURB, TYPE B	4.0	FOOT	\$40.00	\$160.00	\$18.00	\$19.00	\$18.33

Return Bid Details

Project: Almond Road Resurfacing
Section: 17-00999-33-RS
Description: Resurfacing of Almond Road from Fairfield Lane to Washington Street
CPMS Pin: B-01389
Let Date: 3/20/2018

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
35	60603900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (ABUTTING EXISTING PAVEMENT)	470.0	FOOT	\$50.00	\$23,500.00	\$18.00	\$24.00	\$20.00
36	60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	912.0	FOOT	\$55.00	\$50,160.00	\$20.00	\$28.00	\$22.67
37	60609300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12 (ABUTTING EXISTING PAVEMENT)	823.0	FOOT	\$50.00	\$41,150.00	\$18.00	\$23.00	\$19.67
38	67100100	MOBILIZATION	1.0	L SUM	\$60,948.03	\$60,948.03	\$16,500.00	\$48,260.00	\$37,586.67
39	70300100	SHORT TERM PAVEMENT MARKING	33,561.0	FOOT	\$0.10	\$3,356.10	\$0.01	\$0.55	\$0.30
40	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	291.2	SQ FT	\$1.00	\$291.20	\$0.01	\$0.15	\$0.06
41	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	17,297.0	FOOT	\$0.25	\$4,324.25	\$0.01	\$0.15	\$0.06
42	70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	15,416.0	FOOT	\$0.25	\$3,854.00	\$0.01	\$0.15	\$0.06
43	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	1,951.0	FOOT	\$0.25	\$487.75	\$0.01	\$0.15	\$0.06
44	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	285.0	FOOT	\$0.50	\$142.50	\$0.01	\$0.15	\$0.06

Return Bid Details

Project: Almond Road Resurfacing
Section: 17-00999-33-RS
Description: Resurfacing of Almond Road from Fairfield Lane to Washington Street
CPMS Pin: B-01389
Let Date: 3/20/2018

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
45	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	2,364.0	FOOT	\$1.25	\$2,955.00	\$0.01	\$0.15	\$0.06
46	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	240.0	FOOT	\$2.50	\$600.00	\$0.01	\$0.15	\$0.06
47	70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	8,391.0	FOOT	\$1.20	\$10,069.20	\$0.01	\$1.15	\$0.65
48	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	38.0	FOOT	\$1.25	\$47.50	\$0.50	\$0.79	\$0.60
49	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	1,060.0	FOOT	\$1.50	\$1,590.00	\$0.60	\$0.97	\$0.72
50	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	234.0	FOOT	\$4.00	\$936.00	\$1.40	\$1.49	\$1.43
51	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	23.0	FOOT	\$8.00	\$184.00	\$3.89	\$4.00	\$3.96
52	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	50.0	FOOT	\$25.00	\$1,250.00	\$19.80	\$44.60	\$36.17
53	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	1.0	EACH	\$1,500.00	\$1,500.00	\$964.20	\$2,200.00	\$1,748.07
54	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	350.0	FOOT	\$1.00	\$350.00	\$1.20	\$1.30	\$1.23
55	87600200	PEDESTRIAN PUSH-BUTTON POST, TYPE II	2.0	EACH	\$2,000.00	\$4,000.00	\$911.40	\$1,900.00	\$1,560.13
56	87800100	CONCRETE FOUNDATION, TYPE A	4.0	FOOT	\$125.00	\$500.00	\$361.60	\$440.00	\$411.37

Return Bid Details

Project: Almond Road Resurfacing
Section: 17-00999-33-RS
Description: Resurfacing of Almond Road from Fairfield Lane to Washington Street
CPMS Pin: B-01389
Let Date: 3/20/2018

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
57	87900200	DRILL EXISTING HANDHOLE	2.0	EACH	\$300.00	\$600.00	\$328.20	\$545.00	\$470.07
58	88800100	PEDESTRIAN PUSH-BUTTON	4.0	EACH	\$400.00	\$1,600.00	\$559.00	\$741.80	\$621.93
59	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	1.0	EACH	\$1,000.00	\$1,000.00	\$89.00	\$1,060.00	\$729.67
60	LC200051	REJECTED LOAD TRANSPORTATION	5.0	LOAD	\$500.00	\$2,500.00	\$160.00	\$750.00	\$386.67
61	LC400202	SEAL COAT	7,266.0	SQ YD	\$2.00	\$14,532.00	\$1.35	\$2.00	\$1.62
62	LC600200	INSTALL SURVEY MONUMENTS	1.0	EACH	\$1,000.00	\$1,000.00	\$820.00	\$1,500.00	\$1,106.67
63	LC780020	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LETTERS AND SYMBOLS	291.2	SQ FT	\$7.00	\$2,038.40	\$5.50	\$5.59	\$5.53
64	LC780021	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LINE 4"	17,260.0	FOOT	\$1.25	\$21,575.00	\$0.75	\$0.89	\$0.80
65	LC780022	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LINE 5"	14,356.0	FOOT	\$1.50	\$21,534.00	\$0.85	\$1.09	\$0.93
66	LC780023	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LINE 6"	1,951.0	FOOT	\$2.00	\$3,902.00	\$0.95	\$1.39	\$1.10
67	LC780024	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LINE 8"	285.0	FOOT	\$3.00	\$855.00	\$1.50	\$2.40	\$1.80
68	LC780025	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LINE 12"	2,364.0	FOOT	\$4.00	\$9,456.00	\$2.00	\$2.79	\$2.26
69	LC780026	GROOVED THERMOPLASTIC PAVEMENT MARKINGS - LINE 24"	217.0	FOOT	\$8.00	\$1,736.00	\$5.00	\$5.59	\$5.20

Return Bid Details

Project: Almond Road Resurfacing
Section: 17-00999-33-RS
Description: Resurfacing of Almond Road from Fairfield Lane to Washington Street
CPMS Pin: B-01389
Let Date: 3/20/2018

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
70	X0325476	RADAR VEHICLE DETECTION SYSTEM	1.0	EACH	\$35,000.00	\$35,000.00	\$35,174.40	\$36,200.00	\$35,720.13
71	X0327036	BIKE PATH REMOVAL	1,377.0	SQ YD	\$15.00	\$20,655.00	\$5.03	\$10.00	\$7.68
72	X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	117.0	SQ FT	\$5.00	\$585.00	\$15.40	\$17.00	\$15.93
73	X1400102	OUTDOOR RATED NETWORK CABLE	163.0	FOOT	\$5.00	\$815.00	\$1.60	\$2.85	\$2.42
74	X1400215	REMOTE CONTROLLED VIDEO SYSTEM	1.0	EACH	\$8,000.00	\$8,000.00	\$4,766.00	\$5,045.70	\$4,877.23
75	X1400216	LAYER II (DATALINK) SWITCH	1.0	EACH	\$5,500.00	\$5,500.00	\$5,071.80	\$5,175.00	\$5,122.27
76	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	2,316.0	SQ YD	\$5.50	\$12,738.00	\$2.00	\$5.55	\$4.28
77	X4810200	AGGREGATE SHOULDER REMOVAL	148.0	CU YD	\$15.00	\$2,220.00	\$16.00	\$67.15	\$36.05
78	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	3.0	CAL MO	\$3,000.00	\$9,000.00	\$1,000.00	\$3,000.00	\$1,716.67
79	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	1.0	L SUM	\$36,568.82	\$36,568.82	\$7,000.00	\$65,000.00	\$28,700.00
80	X7810300	RECESSED REFLECTIVE PAVEMENT MARKER	107.0	EACH	\$30.00	\$3,210.00	\$30.00	\$42.00	\$38.00
81	X8570215	FULL-ACTUATED CONTROLLER IN EXISTING CABINET	1.0	EACH	\$4,000.00	\$4,000.00	\$3,819.90	\$5,560.00	\$4,960.30
82	XX003168	WORK ZONE PAVEMENT MARKING REMOVAL, SPECIAL	8,391.0	FOOT	\$1.00	\$8,391.00	\$0.01	\$0.35	\$0.20
83	XX006344	SODDING (COMPLETE)	1,685.0	SQ YD	\$35.00	\$58,975.00	\$10.00	\$14.75	\$12.75

Return Bid Details

Project: Almond Road Resurfacing

Section: 17-00999-33-RS

Description: Resurfacing of Almond Road from Fairfield Lane to
Washington Street

CPMS Pin: B-01389

Let Date: 3/20/2018

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
84	Z0010688	CAMERA MOUNTING ASSEMBLY	1.0	EACH	\$1,500.00	\$1,500.00	\$2,294.00	\$4,115.00	\$3,493.00
85	Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	1.0	EACH	\$3,500.00	\$3,500.00	\$1,395.00	\$1,476.60	\$1,427.20
86	Z0033700	LONGITUDINAL JOINT SEALANT	16,636.0	FOOT	\$2.00	\$33,272.00	\$0.85	\$2.05	\$1.58
Bid Total					\$1,316,477.36				