DRAFT

LAKE COUNTY HIGHWAY ACCESS AND USE ORDINANCE

TECHNICAL REFERENCE MANUAL



Effective July 9, 2019

Lake County Division of Transportation

Lake County, IL 600 W Winchester Road Libertyville, IL 60048 Phone: 847-377-7400

TABLE OF CONTENTS

| CHAPTER | R 1 Introduction | 3 |
|---------|--|----|
| CHAPTER | | |
| 2.1 | Administrative Requirements (for all permit types) | 4 |
| 2.2 | Pre-application Meeting | 5 |
| 2.3 | Digital Submittals | 5 |
| 2.4 | Permit Requirements | 5 |
| 2.4.1 | 1 Minimum Access Permit | 7 |
| 2.4.2 | 2 Minor Access Permit | 8 |
| 2.4.3 | 3 Major Access Permit | 9 |
| 2.4.4 | 4 Designated Freeway Access Permit | 11 |
| 2.4.5 | 5 Temporary Access Permit | 12 |
| 2.4.6 | 6 Special Events Permit | 13 |
| 2.4.7 | 7 Utility Permit or Facility Permit | 14 |
| 2.4.8 | 8 Single Service Connection Permit | 15 |
| 2.5 | Permit Forms and Checklists | 16 |
| CHAPTER | R 3 Highway Classification | 18 |
| CHAPTER | R 4 Right-of-Way Dedication | 22 |
| 4.1 | Minimum Right-of-Way Width | 22 |
| 4.2 | Plat Approval Requirements | 22 |
| CHAPTER | R 5 Design Standards | 24 |
| 5.1 | Sight Distance Requirements | 27 |
| 5.2 | Access Design Requirements | 27 |
| 5.2.1 | Access Placement, Grade, and Length | 27 |
| 5.2.2 | | |
| 5.2.3 | - | |
| 5.3 | Highway Improvement Design Requirements | 28 |
| 5.3.1 | | |
| 5.3.2 | <u> </u> | |
| 5.3.3 | , , | |
| 5.4 | Limits of Required Highway Improvements | |
| 5.5 | Pavement Design for Required Highway Improvements | |
| 5.6 | Drainage Design | |
| 5.7 | Signage and Pavement Markings | |
| 5.8 | Existing Survey Monuments | 33 |
| CHAPTER | | 34 |
| 6.1 | Traffic Impact Study Requirements | |
| 6.1.1 | | |
| 6.1.2 | , | |
| 6.2 | Traffic Signal Warrant Analysis | |
| 6.2.1 | · | |
| 6.2.2 | | |
| 6.2.3 | · · · · · · · · · · · · · · · · · · · | |
| 6.3 | Sight Distance Study Analysis | |
| 6.4 | Soil Surveys | |
| 6.5 | Environmental Assessment | |
| 6.6 | Drainage Study | |
| | U 1 | |

| CHAPTER | 7 Utility and Facility Permit Requirements | 41 |
|----------------|--|----|
| 7.1 | Revisions | 41 |
| 7.2 | Location of Utilities and Facilities | 41 |
| 7.3 | Drainage and Access | 41 |
| 7.4 | Excavations, Trenches and Bore Pits | 41 |
| 7.5 | Open Cut of Pavements | 42 |
| 7.6 | Crossings | 42 |
| 7.7 | Berms and Earth Filling | 43 |
| 7.8 | Detention/Retention Facilities/Earth Excavation | 43 |
| 7.9 | Traffic Control Devices | 43 |
| 7.10 | Field Locate | 43 |
| 7.11 | Sidewalk and Bicycle Path Installation | 44 |
| CHAPTER | 8 Access Permit Special Requirements | 45 |
| 8.1 | Emergency Access | |
| 8.2 | Use of Temporary Access | |
| 8.3 | Temporary Access Maintenance | 45 |
| CHAPTER | • • | |
| 9.1 | Engineering Plan and Specification Requirements | 46 |
| 9.2 | Estimate of Cost | 49 |
| 9.3 | Location Map or Drawing Requirements | 50 |
| 9.4 | As-Built Drawing Requirements | |
| CHAPTER | 10 Performance and Maintenance Guarantee, and Insurance Requirements | 51 |
| 10.1 | Additional Insured Endorsements | 51 |
| 10.2 | General Insurance Conditions for all Required Policies | 51 |
| 10.3 | Workman's Compensation Insurance | |
| 10.4 | Employer's Liability | |
| 10.5 | Commercial General Liability Insurance | |
| 10.6 | Automobile Liability | |
| 10.7 | Minimum Limits of Liability | 52 |
| 10.8 | Self-Insurance | |
| 10.9 | Sample Insurance, Bond and Guarantee Forms | |
| | | 55 |

CHAPTER 1 Introduction

This manual has been developed as a companion to the Lake County Highway Access and Use Regulation Ordinance (Ordinance) to provide permit applicants with a "user-friendly" understanding of the various technical and procedural requirements required by the Ordinance.

It is the intent of this manual to provide the necessary guidance, reference materials and forms for residents, developers, municipalities, townships, and engineering consultants to understand the permitting process and requirements, and to develop complete permit and engineering plan submittals that can easily be reviewed in a timely manner.

The manual will be reviewed annually and updated as necessary by the Lake County Division of Transportation (LCDOT).

Lake County Division of Transportation staff can be contacted at:

Lake County Division of Transportation 600 W. Winchester Road Libertyville, Illinois 60048 847-377-7400 FAX: 847-984-5888

hdpermits@lakecountyil.gov

Permitting forms and resources are available on the Lake County website at:

http://www.lakecountyil.gov/659/Permits

CHAPTER 2 Permit Process

Access to Lake County Highway right-of-way is regulated by the LCDOT Permit Department. The Permit Department issues several different types of permits based on the type of use or access needed. Permit types are defined in Table 2.1.

Table 2.1 LCDOT Permit Types

| Permit Type | Access or Use |
|--|--|
| Minimum Access | Single-family home driveways, field entrances and emergency access with no more than 20 trips per day. |
| Minor Access | Access road, driveway or entrance with no more than 50 trips per day |
| Major Access | Access road, driveway or entrance with more than 50 trips per day |
| Designated Freeway Access | Any access to a designated freeway, as defined in the Ordinance |
| Temporary Access | Access road, driveway or entrance needed for less than 12 months |
| Special Event (previously Temporary Highway Closure) | Use of a County Highway for a special event (i.e. parade, race, festival) which requires full or partial closure or impacts typical operation of the County Highway |
| Utility or Facility | Installation of a new utility or municipal facility (i.e. water, sewer, telephone or cable service) or maintenance on an existing utility or facility which requires work in the County Highway right-of-way |
| Single Service Connection | Single service utility or facility connection for single family residences |

2.1 Administrative Requirements (for all permit types)

All permit applications will be reviewed for completeness within 3 working days. If required material is missing from the application packet, the Applicant will be notified of the items needed and no further review will proceed until the required material is submitted. If all required material has been submitted, the application will be logged in the permit tracking system and review will be initiated. All submittals will be reviewed within the timeframes identified in Table 2.2, or as deemed a reasonable time period given manpower, workload and budgeting constraints.

The initial submittal shall include a cover letter explaining what documents are enclosed. All resubmittals shall include a cover letter with detailed disposition of comments, two sets of all documents, and previously reviewed red marked submittals, unless otherwise directed by LCDOT staff.

The Applicant for a Minimum, Minor, Major, Designated Freeway or Temporary Access permit must be the owner of the property seeking access. The only exception to this is for an emergency access facility as discussed in section 2.4. While the owner's engineer, consultant, or contractor may lead coordination with LCDOT regarding the permit review process and required studies, plans or other documentation, the permit shall be issued to the owner, and the owner shall be responsible for all provisions of the Ordinance which reference Applicant or Permittee.

2.2 Pre-application Meeting

A pre-application meeting is required for all Major Access and Designated Freeway Access Permits. A pre-application meeting for other permit types is available at the request of the Applicant. The pre-application meeting for Major Access and Designated Freeway Access Permits will include LCDOT staff and representatives from other County Departments or outside agencies which may be impacted by the permit work, and will determine:

- Scope and limits of the required Traffic Impact Study
- Anticipated required highway improvements
- Anticipated right-of-way requirements
- Anticipated engineering plans and studies submittal requirements

The submittal requirements, sequence of submittals, total fee, performance guarantees and insurance requirements will be discussed at the pre-application meeting. The Permit Department staff can be contacted at (847) 377-7400 to schedule a pre-application meeting.

2.3 Digital Submittals

Utility and Facility Permit applications may be submitted to the LCDOT General Utility Permit email address of https://ndex.org/hdpermits@lakecountyil.gov or as directed by staff, and shall include a completed application and plans. Photos may also be required if excavation activities are involved. Files are typically submitted in Adobe .pdf format.

2.4 Permit Requirements

Permit requirements vary by the type of permit being requested. Table 2.2 provides a summary overview of the general requirements by permit type. The following sections provide a step-by-step checklist for each permit type with additional notes and details.

Applicants should review both the summary table and detailed permit process prior to submitting an application for a permit.

Table 2.2 Permit Requirements Matrix

| | Minimum Access | Minor Access | Major Access | Designated Freeway | Temporary Access | Special Event | Utility/Facility | Single Service |
|---|--|--|---|--|---|--|---|---------------------------------------|
| | Permit | Permit | Permit | Permit | Permit | Permit | Permit ⁴ | Connection Permit |
| Review Time ¹ | 10 Working Days | 10 Working Days | 15 Working Days | 15 Working Days | 15 Working Days | 10 Working Days | 15 Working Days | 10 Working Days |
| Pre-Application Meeting | Optional | Optional | Required | Required | Optional | Optional | Optional | Optional |
| | | • | | · | | · | Optional (Minor/Aerial) Required | |
| Engineering Professional | Optional | Optional | Required | Required | Optional | Optional | (Major/Underground) | Optional |
| Approving Agency | LCDOT | LCDOT | LCDOT | County Board | LCDOT | LCDOT | LCDOT | LCDOT |
| , , , , , , , , , , , , , , , , , , , | | | | , | | Person/Business/ | Utility or facility | |
| | | | | | | Agency/Municipality | owner/contractor/ | |
| Allowable Applicant/Permittee | Property Owner | Property Owner | Property Owner | Property Owner | Property Owner | responsible for event | consultant | Property (service) Owner |
| Initial Submittal | | | | | | | | |
| Cover Letter | Х | Х | X | X | Х | X | Х | X |
| Application Form(s) | X | X | X | X | X | X | X | X |
| Application Fee ² | \$150 | \$450 | \$1,500 / \$4,500 | \$2,400 / \$5,400 | \$600 (Minor/Construction) \$1,050 (Major) | \$50 | \$850/per each utility or facility | \$100 |
| Site Plan or Plat | LCDOT Worksheet | Χ | X | X | Χ | | | X |
| Centerline Staked | X | X | | | | | | |
| Engineering Documents ³ | | | | | | | | |
| Photographs of existing ROW | | | Х | | | | Х | Х |
| Traffic Impact Study | | | Х | | | | | |
| Traffic Signal Warrant Analysis | | | Х | | | | | |
| Sight Distance Study | | | Х | | | | | |
| Geometric Plan | | | X | | | | | |
| Pavement Design | | | Х | Engineering requirements | Engineering requirements | | | |
| Drainage Study | | | X | will follow Major Access process once request for | will follow Major or Minor | | | |
| Water Quality Plan | | | if requested | access is approved by Lake | process based on type or | | | |
| Erosion Control Plan | | | Х | County Board | use of temporary access | | | |
| Engineering Plans (includes Detour/Traffic Control plans) | | Х | x | | | Route Plan, Detour Plan (if required) | х | Boring Location Plan (if required) |
| On-site Engineering Plan | | Х | X | | | | | · · · / |
| Plat of Subdivision/Dedication | | | X | | | | | |
| Cost Estimate | | | Х | | | | X (Facility only) | |
| ROW Dedication | Not required | Not required | Required | Required | Not required | Not required | Not required | Not required |
| \ | | Within 6 months of permit | Within 6 months of permit | Within 6 months of permit | · | · · · · · · · · · · · · · · · · · · · | Within 3/6 months of | Within 3 months of permit |
| Construction to Begin | issuance | issuance | issuance | issuance | Upon issuance | Not Applicable | permit issuance | issuance |
| Construction to be Complete | 18 months from permit issuance | 18 months from permit issuance | within 24 months of construction start | within 24 months of construction start | Within 12 months of permit issuance | Not Applicable | Within 18/12 months of permit issuance | Within 18 months of permit issuance |
| | | | | | | | Per maintenance | |
| ROW Access/Use Duration | Until change in use | Until change in use | Until change in use | Until change in use | 12 months max | As specified on permit | agreement | Until change in use |
| Required Inspections | Culvert Placement, Final Inspection | Culvert Placement, Final Inspection | Performance Inspection, Maintenance Inspection | Performance Inspection, Maintenance Inspection | Final Inspection | None | Final Inspection | Final Inspection |
| neganica inspections | порессион | spection | | | \$5000 or | 110110 | 110% of Estimate, | \$2,000 / \$20,000 |
| Performance Guarantee | \$2,000 | \$2,000 | 110% of Estimate | 110% of Estimate | 110% of Estimate | Not required | plus crossing fee | depending on location |
| Maintenance Guarantee | Not required | Not required | 15% of Performance Guarantee | 15% of Performance Guarantee | Not required | Not required | Not required | Not required |
| Proof of Insurance | Required | Required | Required | Required | Required | Required | Required | Required |
| As-Built Plans | Not required | Not required | Required | Required | Not required | Not required | Required | Not required |

^{1.} Review time may vary based on manpower, workload, and budgeting constraint. All submittals that require review by LCDOT Departments outside of the Permitting Department may require additional time.

^{2.} Additional fees apply. See Permit Schedule for details.

^{3.} Engineering Documents shall be signed and sealed by a licensed profressional engineer. These are to be submitted after pre-application meeting if one is required, or with initial submittal package if no pre-application meeting needed.

 $^{4. \,} Small \, Cell \, Wireless \, facilities \, are \, governed \, by \, the \, "Wireless \, Telecommunications \, Facilities \, Ordinance".$

2.4.1 Minimum Access Permit

The Permit Department will use the following steps in reviewing requests for Minimum Access.

| Ste | <u>p 1:</u> | App | licant | submits |
|-----|-------------|-----|--------|---------|
| | | | | |
| | | | | |

- Application for Access to a County Highway form completed and signed
- ☐ Application fee: check made payable to "Lake County Treasurer"
- ☐ Site plan or Minimum Access Worksheet indicating:
 - o Proposed access location, including distance from nearest side or cross street
 - Existing culvert locations and size within the County right-of-way
 - Well location (if applicable)
 - Septic field location (if applicable)
- ☐ Centerline of driveway location by placing a field stake at the centerline of the driveway at the County Highway right-of-way

Step 2: Lake County Division of Transportation performs

- ☐ Field inspection of access location to determine: sight distance, culvert location, mailbox turnout location, curb and gutter or gravel shoulder requirements.
- ☐ Review of submitted site plan for any additional permits that may be required, i.e. water main or sanitary sewer connections within the County Highway right-of-way.

If location of proposed access is unacceptable, or if additional permits are required, LCDOT will notify the Applicant of the required revisions. Applicant must revise and re-submit appropriate documents within 90 days or the permit application will be closed. If the location of the proposed access is acceptable, LCDOT will notify parcel owner and proceed to Step 3.

Step 3: Parcel owner submits

- □ Performance guarantee for a minimum of \$2,000.00. This may be in the form of a cashier's check made payable to "Lake County Treasurer", surety bond, or irrevocable letter of credit. A cashier's check will be deposited if it contains an expiration date.
- Proof of insurance and endorsement provided by you or your contractor.

Step 4: Permit issuance and construction

- ☐ Upon completion of the above, the LCDOT will issue the Minimum Access permit.
- ☐ The parcel owner shall begin construction within six (6) months of the date of issuance of the permit and be completed within eighteen (18) months.
- ☐ The parcel owner shall request inspections for culvert placement and at the completion of the restoration of the right-of-way.
- ☐ Upon a satisfactory final inspection by the LCDOT, the performance guarantee is returned to the parcel owner.

2.4.2 Minor Access Permit

The Permit Department will use the following steps in reviewing requests for Minor Access.

| | Step 1: A | p | <u>plicant submits</u> |
|--|-----------|---|------------------------|
|--|-----------|---|------------------------|

| Application for Access to a County Highway form completed and signed |
|--|
| Application fee: check made payable to "Lake County Treasurer" |
| Site plan indicating: |
| |

- Proposed access location, including distance from nearest side or cross street
- Existing culvert location and size within the County right-of-way
- Well location (if applicable)
- Septic field location (if applicable)
- Detour/traffic control plan (if applicable)
- ☐ Centerline of driveway location by placing a field stake at the centerline of the driveway at the County Highway right-of-way

Step 2: Lake County Division of Transportation performs

| | Field inspection of access location to determine: sight distance, culvert location, mailbox |
|---|---|
| | turnout location, curb and gutter or gravel shoulder requirements. |
| П | Review of submitted site plan for any additional permits that may be required i.e. water |

Review of submitted site plan for any additional permits that may be required i.e. water main or sanitary sewer connections within the County Highway right-of-way.

If location of proposed access is unacceptable, or if additional permits or engineering studies are required, LCDOT will notify the Applicant of the required documents. Applicant must submit appropriate documents within 90 days or the permit application will be closed. If the location of the proposed access is acceptable, LCDOT will notify parcel owner and proceed to Step 3.

Step 3: Parcel owner submits

| Performance guarantee for a minimum of \$2,000.00. This may be in the form of a |
|--|
| cashier's check made payable to "Lake County Treasurer", surety bond, or irrevocable |
| letter of credit. A cashier's check will be deposited if it contains an expiration date. |
| Proof of insurance and endorsement provided by you or your contractor |

Proof of insurance and endorsement provided by you or your contractor.

Step 4: Permit issuance and construction

| Upon completion of the above, the LCDOT will issue the Minor Access permit. |
|---|
| The parcel owner shall begin construction within six (6) months of the date of issuance |
| of the permit and be completed within eighteen (18) months. |
| The parcel owner shall request inspections for culvert placement and at the completion |
| of the restoration of the right-of-way. |
| Upon a satisfactory final inspection by the LCDOT, the performance guarantee is |
| returned to the parcel owner. |

2.4.3 Major Access Permit

The Permit Department will use the following steps in reviewing requests for Major Access.

Step 1: Applicant submits

| Application for Access to a County Highway form completed and signed |
|--|
| Site plan indicating location of proposed access |
| Request for right-of-way stationing and traffic data for pavement design indicating limits |
| Request for pre-application meeting with three proposed times and dates |

Step 2: Pre-application meeting

LCDOT staff will contact Applicant with final date and time of pre-application meeting, as well as any additional information which will be needed at the meeting. The expectation for the pre-application meeting is outlined in section 2.2 of this Technical Reference Manual.

Step 3: Applicant submits

Applicable engineering documents from the list below, as identified at the meeting:

| Photographs of the existing right-of-way at 100-foot intervals; all photographs must |
|---|
| be taken along, not perpendicular to, the right-of-way |
| Sight Distance Study (signed and sealed by a Licensed Professional Engineer in the |
| State of Illinois) |
| Traffic Impact Study (signed and sealed by a Licensed Professional Engineer in the |
| State of Illinois) |
| Traffic Signal Warrant Analysis (if requested) |
| Geometric Plan |
| Pavement Design (signed and sealed by a Licensed Professional Engineer in the State |
| of Illinois) |
| Drainage Study and Water Quality Plan (if requested) |
| Erosion Control Plan |
| Engineering plans signed and sealed by a Licensed Professional Engineer in the State |
| of Illinois. Engineering plans are likely to require revisions and resubmittals. |
| Cost estimate, signed and sealed, required prior to final plan approval |
| Copy of on-site plans |
| Plat of Subdivision and Dedication (prepared by a Licensed Professional Land Surveyor |
| in the State of Illinois) |

Step 4: Fee assessment

| LCDOT staff reviews engineering document submittal for completeness, requests |
|---|
| additional information as needed |
| LCDOT identifies permit fee and informs Applicant of initial and total anticipated fees |
| Applicant submits application fee as a check made payable to "Lake County Treasurer" |
| Fee must be received prior to technical review of engineering documents |

Step 5: Review and approval of engineering documents

LCDOT staff review and comment on the engineering documents, request additional information, or approve the engineering documents (comments, requests and approvals will be provided electronically). Applicant must submit revised or additional documents within 90 days or the permit application will be closed.

| | Step 6: | Applicant submits |
|-------|----------------|---|
| | | Two final sets of approved access plans Any additional fees due at this time Copy of on-site plans approved by Village or County Performance guarantee in the amount of 110% of the cost estimate Certificate of Insurance, naming the County and the Division of Transportation as additional insured, and evidence of worker's compensation insurance The name, professional license number, and telephone number of the Resident Engineer for this project. This person will be responsible for providing weekly construction reports in the IDOT MFT format. The Developer and Resident Engineer agreement Plat of Dedication, ready for recording, if not a subdivision of property A PDF of the approved offsite plans and onsite plans |
| | <u>Step 7:</u> | Permit issuance and construction |
| | | At this time the access permit and all utility permits will be issued. Construction must begin within 6 months and be completed within 24 months. Final Plat of subdivision will be signed by the County Engineer When ALL construction work is completed, the Resident Engineer shall notify the Division, in writing, to request a final inspection. The Resident Engineer will be notified about any work needed and any follow-up inspections and fees. Any outstanding costs due to the LCDOT for work done such as signing shall now be paid. After a satisfactory inspection, access work is accepted by the LCDOT. |
| | Step 8: | Post-construction, Parcel Owner submits |
| | | Electronic as-builts Maintenance guarantee in the amount of 15% of the original Performance Guarantee for a 2-year period Performance Guarantee shall be released after the above are received |
| | Step 9: | Maintenance inspection: |
| | | Conducted after maintenance period is complete If all work is acceptable and any remaining outstanding costs are paid, final acceptance of the improvement is made and the maintenance guarantee is released |
| NOTE: | | Applicant/Permittee shall be responsible for the total cost of the access, including the review information, access plan preparation, all engineering studies, plat or dedication preparation, Performance and Maintenance Guarantees, insurance, right-of-way dedication, inspection and construction supervision, improvement construction materials, and application, permit and inspection fees. |

2.4.4 Designated Freeway Access Permit

The Permit Department will use the following steps in reviewing requests for Designated Freeway

| Access. | |
|----------------|--|
| <u>Step 1:</u> | Applicant submits |
| | Application for Access to a County Highway form completed and signed Site plan indicating location of proposed access Request for right-of-way stationing and traffic data for pavement design indicating limits Request for pre-application meeting with three proposed times and dates |
| Step 2: | Pre-application Meeting |
| any add | staff will contact Applicant with final date and time of pre-application meeting, as well as ditional information which will be needed at the meeting. The expectation for the pretion meeting is outlined in section 2.2 of this Technical Reference Manual. |
| Step 3: | Parcel owner submits |
| | Description of Project – a written request to the County Engineer stating that access to a County Highway designated as a freeway is being requested. The written request shall include a detailed description of the proposed use for which access is being requested and shall state the reason for initiating the request. Traffic Impact Study (signed and sealed by a Licensed Professional Engineer in the State of Illinois) |
| | Any other documents requested at the pre-application meeting |
| <u>Step 4:</u> | Fee assessment |
| | LCDOT staff reviews submittal for completeness, requests additional information as needed LCDOT identifies permit fee and informs Applicant of initial and total anticipated fees Applicant submits application fee as a check made payable to Lake County Treasurer" Fee must be received prior to technical review of engineering documents |
| Step 5: | County Engineer and Board review and action |
| | Access Control Officer reviews the submitted documents and prepares a report with a formal recommendation to the County Engineer County Engineer presents the report on the request for access to the Public Works, |
| | Planning and Transportation Committee The Public Works, Planning and Transportation Committee prepare a recommendation |

Upon determination by the County Board, the County Engineer shall implement the decision of the County Board. If approved by the County Board, a Designated Freeway Access Permit shall be issued in compliance with the Major Access Permit process as outlined in section 2.4.3.

☐ The County board shall consider the recommendation of the Public Works, Planning and

in the form of a resolution to the County Board

Transportation Committee and take formal action

2.4.5 Temporary Access Permit

The Permit Department will use the following steps in reviewing requests for Temporary Access.

| Step 1: | Applicant submits |
|---------|---|
| | Application for Access to a County Highway form completed and signed Application fee: check made payable to "Lake County Treasurer" Site plan or location sketch indicating: O Proposed access location, including distance from nearest side or cross street Location of access on property and dimensions of access Specifications for culvert size (a minimum 15 inch culvert with flared end sections must be used) Specifications for surface type |
| Step 2: | Lake County Division of Transportation performs |
| | Review submitted documents to determine if proposed location and surface of Temporary Access is acceptable, perform a field investigation if necessary If the Temporary Access is associated with a Major Access permit application, verify all required information for the Major Access permit has been submitted (see below) Notify the Applicant of any required revisions and required performance guarantee form |
| Step 3: | Applicant submits |
| | Any revised or additional documents requested Performance guarantee Proof of Insurance |
| Step 4: | Permit issuance and construction |
| | Upon completion of the above, the LCDOT will issue the temporary permit. The permit is valid for a period of 12 months from the issuance date, at which time the permit shall expire, unless another timeframe is specified on the permit. The access must be removed prior to or upon expiration of the permit Any requests for renewal are made on an individual basis and must be made in advance of the expiration of the access permit |
| Step 5: | Final inspection: |
| | After the access has been removed and the right-of-way restored, a written request for |

Temporary Access permits for utility and initial site work on property that will be served by a Major Access permit will be issued only at such time as a Major Access permit has been applied for and the location and extent of improvements required for the Major Access have been agreed to by the Access Control Officer.

☐ Restoration work must be completed and accepted by LCDOT prior to the release of any

inspection must be made to the LCDOT.

monies held as a performance guarantee.

2.4.6 Special Events Permit

The Permit Department will use the following steps in reviewing requests for use of County Highway right-of-way for a special event of public interest or filming.

Step 1: Applicant submits

| | Application form for Special Event on a County Highway completed and signed. Must be |
|------|--|
| | submitted a minimum of 30 days prior to the planned event. |
| | Application fee: check made payable to "Lake County Treasurer" |
| | Location map or course route map for the event |
| | Proof of insurance |
| o 2: | Lake County Division of Transportation performs |
| | Field inspection or review of detaur route if required |

Step

| Ш | Field inspection or review of detour route if required |
|---|--|
| | Review submitted site plan for any additional permits that may be required |
| | Review of proof of insurance |

If the proposed closure is unacceptable, or if additional permits are required, LCDOT will notify the Applicant of the required revisions. Applicant must revise and re-submit appropriate documents within 90 days or the permit application will be closed.

Step 3: Permit issuance and event management

| Upon completion of the above, the LCDOT will issue the special event permit. |
|---|
| The permittee, not the LCDOT, shall be responsible for advance notification of |
| temporary closures, the detour route, traffic control, including signage and |
| police/Sheriff presence or assistance if required. The LCDOT has the authority to require |
| that the permittee have police or Sheriff's presence during the highway closure. |
| The permittee shall be responsible for cleaning and maintaining the right-of-way of the |
| County Highway, including removal of all trash and debris at the conclusion of the event. |
| Sewers, drains and pavement surface shall be kept free of debris, trash, and other |
| extraneous materials. The permittee may be billed for costs of debris or trash removal if |
| not completed at the conclusion of the event. |

NOTES:

Temporary closure of a Designated Freeway or County Highway with a High Mobility Access Classification may require additional conditions of approval including, but not limited to, significant coordination with local and regional emergency service agencies, preparation of a detour plan, notification of media outlets, placement of changeable message signs on the route prior to the closure, etc.

2.4.7 Utility Permit or Facility Permit

The Permit Department will use the following steps in reviewing requests for installation of or maintenance on a utility or municipal facility in the County Highway right-of-way. Small cell wireless telecommunications installations shall follow the "Wireless Telecommunications Facilities Ordinance".

Step 1: Applicant submits

| | Facility Permit - Application to Perform Work within a County Highway Right-of-Way |
|--------|---|
| | completed and signed, transmitted electronically to hdpermits@lakecountyil.gov Utility Permit - Application for Utility Placement within a County Highway Right-of-Way completed and signed, transmitted electronically to hdpermits@lakecountyil.gov |
| | Application fee; check made payable to "Lake County Treasurer" |
| | Photographs of the right-of-way within the improvement limits at 100-ft intervals. All photographs must be taken along, not perpendicular to, the County Highway right-of-way |
| | Application for Municipal Acceptance form for any facility that will be maintained by anyone other than LCDOT (i.e., sanitary, watermain, sidewalk, street lights, fiber optic cable, retaining walls). The owner of the facility must complete the acceptance form. |
| | Engineering Plans for the installation or maintenance work |
| Step 2 | : Lake County Division of Transportation performs |
| | Field inspection as needed |
| | Review of submitted engineering plans and studies |
| | Notification to Applicant of required revisions, request for additional information, or approval of the engineering plans and provides invoice |
| Step 3 | : Applicant submits |
| | Final set of approved engineering plans as .pdf file(s) Permit and Inspection Fees per County invoicing Performance guarantee (forms supplied) in the amount of 110% of the cost estimate o Each pavement crossing requires an additional \$20,000.00, added to the Performance Guarantee amount o Performance guarantees are held for a period of 18 months. There is no maintenance period. |
| | Proof of insurance |
| Sten 4 | : Permit issuance and construction |
| | Upon completion of the above, the LCDOT will issue the utility/facility permit. |
| | Facility work must begin construction within six (6) months of the date of issuance of |
| | the permit and shall be completed in one year, from the date of the permit issuance |
| | Utility work must begin within three (3) months of the date of issuance of the permit, |
| | and shall be completed in eighteen (18) months from the date of issuance of the permit After the project is constructed and the right-of-way and highway restoration has been completed, the Permittee must request in writing a final inspection. |
| | Upon a satisfactory final inspection by the LCDOT and receipt of the as-built plans, the performance guarantee is released. |

2.4.8 Single Service Connection Permit

The Permit Department will use the following steps in reviewing requests for installation of a single service connection to a utility or facility for a single family residence.

Step 1: Applicant submits

released.

| | Facility Permit - Application to Perform Work within a County Highway Right-of-Way |
|--------|---|
| | completed and signed, transmitted electronically to hdpermits@lakecountyil.gov Utility Permit - Application for Utility Placement Within a County Highway Right-Of-Way |
| | completed and signed, transmitted electronically to hdpermits@lakecountyil.gov |
| | Application fee; check made payable to "Lake County Treasurer" Photographs of the right-of-way within the improvement limits at 100' intervals; all |
| | photographs must be taken along, not perpendicular to, the County Highway right-of- way |
| | Application for Municipal Acceptance form for any facility that will be maintained by anyone other than LCDOT (i.e., sanitary, watermain, sidewalk, street lights, fiber optic |
| | cable, retaining walls). The owner of the facility must complete the acceptance form. Engineering or site plans, submitted electronically to hdpermits@lakecountyil.gov . |
| | If your proposed connection is located on the same side of the county highway as your residence, you may include the connection location on your site plan. If you need to bore under the county highway to perform the connection, an engineering plan of the county highway, signed and sealed by a licensed engineer in the State of Illinois, will be required. |
| Step 2 | : Lake County Division of Transportation performs |
| | Field inspection as needed |
| | Review of submitted engineering or site plans Notification to Applicant of required revisions, request for additional information, or approval of the engineering plans and provides invoice |
| Step 3 | : Applicant submits |
| | Final sets of approved engineering as .pdf file(s) |
| | Performance guarantee: |
| | If the connection crosses under the county highway the performance guarantee is \$20,000.00, in the form of a letter of credit or cashier's check. |
| | If the connection is on the same side of the county highway as your residence, the performance guarantee is \$2,000.00. |
| | Performance guarantees are held for a minimum period of 18 months. |
| | Proof of insurance |
| Step 4 | : Permit issuance and construction |
| | Upon completion of the above, the LCDOT will issue the single service permit. |
| | The permittee must begin construction within three (3) months of the date of issuance |
| | of the permit and shall be completed in eighteen months, from the date of the permit |
| П | issuance After the project is constructed and the right-of-way and highway restoration has been |
| | completed, the Permittee must request in writing a final inspection. |
| | Upon a satisfactory final inspection by the LCDOT, the performance guarantee is |

2.5 Permit Forms and Checklists

All applications and checklist forms can be found on the website and accessed through links below:

Application or Notification Forms

- Application for Access to a County Highway
- Change In Land-Use Notification Form
- Application to Perform Work within a County Highway Right-of-Way (Utility/Facility)
- Application for Utility Placement within a County Highway Right-of-Way
- Application for Special Event on a County Highway (Temporary Closure of a County Highway)
- Emergency Repair Notification Form
- Pavement Open Cut Request Form

Acceptance Forms

- Local Agency (Municipal) Utility-Facility Acceptance
- Property Owner Acceptance
- Public Utility Acceptance

Samples of the above forms are included in this manual for reference only. Applicants should use fillable forms from the website to ensure the most current version is submitted.

Checklists for Major Access Permits and Facility Permits and a Sample Resident Engineer Letter are provided as a reference to assist Applicants in preparation of submittal materials. Specific requirements for each permit should be discussed at a pre-application meeting.



600 W. Winchester Road Libertyville, IL. 60048 Telephone: 847 377 7400

APPLICATION FOR ACCESS TO A COUNTY HIGHWAY (Please print or type)

| | Telephone Number: | |
|-------|---|-----------------|
| In ac | ccordance with the provisions of the Lake County, IL Code of Ordinances, as amended, the above na | med applicant |
| | by makes application to the County Engineer of Lake County for access to a Highway that is part of the | |
| | way System of Lake County, Illinois. This access is described as follows: | • |
| | | |
| 1. | Name of County Highway: | |
| 2. | Property Identification Number (PIN) or Tax Parcel ID Number: | |
| 3. | Location of Proposed Access: Property Address: | |
| | Side of County Highway: North East South V | West |
| 4. | Use of Property to be Served By Proposed Access (explain use of land, such as single family do farming purposes, construction project, real estate office, shopping center, subdivision, etc.): | welling, |
| | | |
| 5. | Other Information | |
| 8 | a. Does the property to be served have frontage along another road or street? (If yes, explain): _ | |
| | Will an dage the property to be consed been athereses 2. (If year symbols) | |
| I. | b. Will or does the property to be served have other access? (If yes, explain): | |
| (| c. Will the proposed access be removed or no longer be needed in the near future? (If yes, explain | n): |
| | | , <u> </u> |
| C | d. Comments (if needed): | |
| | | |
| 6. | Additional Information (if applicable) | |
| a | a. Name, address and telephone number of agent for above property owner: | |
| t | b. Name, address and telephone number of Design Engineer or firm: | |
| , | c. Comments (if needed): | _ |
| | c. Comments (if needed): | |
| Am | ount of Enclosed Application Fee (non-refundable): | |
| | Minor Access | porary Access |
| | i milion recode i major recode i i recina y recode i i milimiani recode i i remp | 50.a.j / 100000 |

GENERAL CONDITIONS FOR APPLICATION FOR ACCESS TO A COUNTY HIGHWAY

- 1. In submitting this application, the Applicant agrees to comply with the Lake County, IL Code of Ordinances, as amended.
- 2. This application shall be used for only one access. Any additional access will require a separate application form and fee.
- 3. The submittal of this application does not obligate the County Engineer to issue an access permit if such access facility will not comply with the provisions of the Lake County Highway Access and Use Ordinance, as amended.
- 4. Lack of immediate response to a submitted application form or submitted preliminary information, engineering plans or other submittals shall not be construed as approval or acceptance of the submittal.
- 5. The Lake County Division of Transportation, its employees and its agents, and the County of Lake, its employees and its agents shall not be held responsible for costs or delays to the Applicant due to the processing time required by the Lake County Division of Transportation to review submittals by the Applicant or his authorized agents.
- 6. The Applicant is responsible for the total cost of the access. This includes engineering, construction and inspection costs as well as any costs the Lake County Division of Transportation may incur such as traffic control signage installations and emergency corrective actions.
- 7. Application and Permit fees are non-refundable once processed.

| (Signature of Property Owner or Developer) |
|--|
| |
| (Printed name of above signature) |
| |
| (Title) |



600 W. Winchester Road Libertyville, IL. 60048 Telephone: 847 377 7400

CHANGE IN USE NOTIFICATION (for existing access to a County Highway)

(Please print or type)

| | Telephone Number: |
|----------------------|---|
| by | ordance with the provisions of the Lake County, IL Code of Ordinances, as amended, the above named owner notifies the County Engineer of Lake County of change in land use or land use density for a property with to the Highway System of Lake County, Illinois. The owner requests continued use of the access as follows: |
| | Name of County Highway: |
| ı | Property Identification Number (PIN) or Tax Parcel ID Number: |
| | Location of Proposed Access: Property Address: |
| | Side of County Highway: North East South West |
| í | dwelling, farming purposes, real estate office, shopping center, subdivision, etc.): |
| ļ | Previous use of Property to be Served By Proposed Access (include date of permit if known) |
| | |
| a. | Previous use of Property to be Served By Proposed Access (include date of permit if known) Other Information |
| a. b. | Previous use of Property to be Served By Proposed Access (include date of permit if known) Other Information Does the property to be served have frontage along another road or street? (If yes, explain): |
| a. b. | Previous use of Property to be Served By Proposed Access (include date of permit if known) Other Information Does the property to be served have frontage along another road or street? (If yes, explain): Will or does the property to be served have other access? (If yes, explain): |
| a. b. c. | Previous use of Property to be Served By Proposed Access (include date of permit if known) Other Information Does the property to be served have frontage along another road or street? (If yes, explain): Will or does the property to be served have other access? (If yes, explain): Will any existing access be removed or no longer be needed in the near future? (If yes, explain): |
| a. b. c. d. | Previous use of Property to be Served By Proposed Access (include date of permit if known) Other Information Does the property to be served have frontage along another road or street? (If yes, explain): Will or does the property to be served have other access? (If yes, explain): Will any existing access be removed or no longer be needed in the near future? (If yes, explain): Comments (if needed): Additional Information (if applicable) |
| a. b. c. | Previous use of Property to be Served By Proposed Access (include date of permit if known) Other Information Does the property to be served have frontage along another road or street? (If yes, explain): Will or does the property to be served have other access? (If yes, explain): Will any existing access be removed or no longer be needed in the near future? (If yes, explain): Comments (if needed): Additional Information (if applicable) Name, address and telephone number of agent for above property owner: |

NOTE: This Application is subject to the General Conditions as printed on the reverse side of this form. The Application is only valid when an original signature is provided on page 2.

GENERAL CONDITIONS FOR APPLICATION FOR ACCESS TO A COUNTY HIGHWAY

- 1. In submitting this application, the Applicant agrees to comply with the Lake County, IL Code of Ordinances, as amended.
- 2. This form shall be used for only one access. Any additional access will require a separate notification form.
- 3. The submittal of this notification does not obligate the County Engineer to approve continued use of the existing access if such access facility will not comply with the provisions of the Lake County Highway Access and Use Ordinance, as amended. Written response from LCDOT must be obtained which authorizes continued use of the existing access. If the access does not comply with the provisions of the Ordinance, a new access permit will be required.
- 4. Lack of immediate response to a submitted notification form or submitted preliminary information, engineering plans or other submittals shall not be construed as approval or acceptance of the submittal.
- 5. The Lake County Division of Transportation, its employees and its agents, and the County of Lake, its employees and its agents shall not be held responsible for costs or delays to the Property Owner due to the processing time required by the Lake County Division of Transportation to review submittals by the Property Owner or his authorized agents.
- 6. The Property Owner is responsible for the total cost of the access. This includes engineering, construction and inspection costs as well as any costs the Lake County Division of Transportation may incur such as traffic control signage installations and emergency corrective actions.
- 7. Application and Permit fees are non-refundable once processed.

| (Signature of Property Owner or Developer) |
|--|
| |
| (Printed name of above signature) |
| |
| (Title) |



600 W. Winchester Road Libertyville, IL. 60048 Telephone: 847 377 7400

APPLICATION TO PERFORM WORK WITHIN A COUNTY HIGHWAY RIGHT-OF-WAY

(Please print or type)

| APPI | LICANT (Name and address): | | | | | |
|------|---|--|--|--|--|--|
| | Telephone Number: | | | | | |
| Coun | cordance with the Lake County, IL Code of Ordinances, as amended, the above Applicant hereby makes application to the ty Engineer of Lake County for permission to perform certain work herein described within the County Highway right-of-way. Droposed work is described as follows: | | | | | |
| 1. | Name of County Highway: | | | | | |
| 2. | Property Identification Number (PIN) or Tax Parcel ID Number: | | | | | |
| 3. | Location of Proposed Access Property Address: | | | | | |
| | Side of County Highway: North East South West | | | | | |
| 4. | Type of Proposed Work (check all that apply): | | | | | |
| | ☐ Storm sewer/culvert or sewer crossing ☐ Single service connection ☐ Street lighting | | | | | |
| | ☐ Sanitary sewer line ☐ Sidewalk ☐ Open Cut | | | | | |
| | ☐ Water main / water line ☐ Bike Path ☐ Other | | | | | |
| 5. | Reason for Proposed Work (describe why work is needed such as improve drainage, village requirement, etc.): | | | | | |
| 6. | Construction or Installation of Proposed Work shall be by: Applicant | | | | | |
| | Contractor (name, address, telephone): | | | | | |
| | Other (name, address, telephone): | | | | | |
| 7. | Name, address and telephone number of Agent for Applicant (if applicable): | | | | | |
| | | | | | | |
| 8. | Operational and Maintenance responsibilities for completed Proposed Work: | | | | | |
| 9. | Comments (if needed): | | | | | |
| J. | Comments (ii needed): | | | | | |
| 10. | Enclosed Application Fee (based on # of boxes checked above, non-refundable): | | | | | |

NOTE: This Application is subject to the General Conditions as printed on the reverse side of this form. The Application is only valid when an original signature is provided on page 2.

GENERAL CONDITIONS FOR APPLICATION TO PERFORM WORK WITHIN A COUNTY HIGHWAY RIGHT-OF-WAY

- 1. In submitting this Application, the Applicant agrees to comply with the various policies, conditions and requirements of the Lake County Division of Transportation, whether written or verbal, and to the Lake County, IL Code of Ordinances, as amended, to make such changes and revisions to the Proposed Work as may be necessary to comply or more closely conform to those various policies, conditions and requirements of the Lake County Division of Transportation, whether written or verbal, and to the Lake County, IL Code of Ordinances, as amended.
- 2. The Applicant shall supply, at his expense, such information or submittals as the Lake County Division of Transportation may require to complete the review of the Proposed Work.
- 3. Lack of an immediate response to this application form or any information submitted for review and/or comment shall not be construed as approval or acceptance of the application or submittal.
- 4. The Lake County Division of Transportation is not responsible for providing room within the County Highway right-of-way for the Proposed Work and lack of sufficient room may be cause for not permitting the Proposed Work to be located within the County Highway right-of-way.
- 5. The Proposed Work may not be permitted if it will create a hazard to the Public or interfere with the ability of the Lake County Division of Transportation to operate and maintain the County Highway right-of-way.
- 6. This Application does not relieve the Applicant from obtaining permission and authority from the Federal, State, County or Local Government or any political subdivision or administrative agency which may administer any statutes, regulations, ordinances or administrative orders that pertain to the Proposed Work.
- 7. The Applicant is cautioned that the County Highway rights-of-way have been obtained for Public Road Purposes and any other use of the right-of-way is subject to approval or permission from the legal property owner. The Applicant shall be responsible for contacting the property owner and obtaining any required approval or permission.
- 8. The Lake County Division of Transportation, its employees and its agents, and the County of Lake, its employees and its agents shall not be held responsible for costs or delays to the Applicant due to the processing time required by the Lake County Division of Transportation to review information or submittals by the Applicant or his authorized agents.
- 9. The submittal of this Application by the Applicant does not obligate the County Engineer to issue a permit.
- 10. If the Proposed Work is permitted the Applicant and his successors and assigns shall be generally responsible for the following:
 - a. Obtaining any other permission or authority needed for the Proposed Work.
 - b. Having the Proposed Work completed, including any required restoration work.
 - c. Supplying any required bonding and/or insurance.
 - d. Not making any changes to the approved Proposed Work without prior permission.
 - e. Providing maintenance for the completed Proposed Work.
 - f. Making or having made any adjustments or changes to the completed Proposed Work due to maintenance or construction work of the Highway Authority.
 - g. Assuming liability for the Proposed Work during construction and after completion.
 - h. Removal of the completed Proposed Work if required in the future.
 - i. The costs involved by the above responsibilities and any other costs related to the Proposed Work.
 - j. Other items as specified in the Lake County,, IL Code of Ordinances, as amended.

| (Signature of Applicant) |
|-----------------------------------|
| (Printed name of above signature) |
| |
| (Title) |



600 W. Winchester Road, Libertyville, Illinois 60048

 General Office
 847/377-7400

 Facsimile
 847/984-5944

 Maintenance
 847/377-7498

APPLICATION FOR UTILITY PLACEMENT WITHIN A COUNTY HIGHWAY RIGHT-OF-WAY

| | | | (Ple | ase print or t | ype) | | Utility Ref# |
|--|-----------------------------------|--------------|-----------------|-----------------|------------|---|---|
| APP | PLICANT: | | | | | | |
| Con | npany Name: | | | | | | |
| Mail | ing Address: | | | | | | |
| Tele | phone: | | F | ax: | | | |
| appl | | gineer of L | ake County | for permission | on to perf | orm certain work h | Applicant hereby makes erein described within the |
| 1. | Name of County High | way: | | | | | |
| | LCDOT Station: From | | | | То | | |
| 2. | Location: Quarter | Sectio | n of | | | Township | Town/City |
| | between the | intersection | ns of | | | and | |
| 3. | Project Information: | | | | | | |
| | Project Name: | | | | Develo | per (if applicable): | |
| | Nature of Project: | .t 🗆 D | ·imaaa | | | iviolog | |
| | LCDOT Improvemen | | siness | in | | ivision r (Describe): | |
| 4. | Single-Family Home Proposed Work: | ∐Ріа | ce of Worsh | ıh | □ Otner | (Describe). | |
| 7. | rioposeu work. | | | | | | |
| 5. | Proposed Starting Da | te: | | Propos | sed Numb | er of Working Days | s: |
| 6. | Check All That Apply: | | Company Cr | ews 🗌 Co | ntractor | Other: | |
| 7. | Is an Open Cut Requi | red? | ■ No | Yes | If yes, at | tach pavement ope | n cut request form |
| 8 | Is a Lane Closure Rec | quired? | ☐ No | Yes | | | |
| 9. | Contacts-Please prov | ide Name a | and Phone I | Number | | | |
| Concerning the Proposed Work: | | | | | | | |
| | During Construction Op | erations: | | | | | |
| Concerning Restoration Work: | | | | | | | |
| | 24 Hour Emergency Nu | ımber: | | | | | |
| In consideration of this application and the issuance of a Utility Permit, the Permittee agrees to comply with the Lake County, IL Code of Ordinan amended, and the terms of the issued permit including the Mandatory General Conditions for Utility Permits (on reverse side), Pavement Open Cut I Form, Environmental Special Condition, Special Condition sheet (when added) and Engineering Plan. No changes or revisions to the work approved issued Permit will be allowed without first notifying and receiving permission from the Permit Office of the Lake County Division of Transportation. | | | | | | e side), Pavement Open Cut Request evisions to the work approved by the | |
| | For the APPLICANT: | | | | | | |
| | | Signature | of Authorized I | Employee or Age | ent | Date | |
| | Title | | | | | | Rev 06/16 |

GENERAL CONDITIONS FOR APPLICATION FOR UTILITY PLACEMENT WITHIN A COUNTY HIGHWAY RIGHT-OF-WAY

- 1.In submitting this Application, the Applicant agrees to comply with the various policies, conditions and requirements of the Lake County Division of Transportation, whether written or verbal, and to the Lake County, IL Code of Ordinances, as amended, to make such changes and revisions to the Proposed Work as may be necessary to comply or more closely conform to those various policies, conditions and requirements of the Lake County Division of Transportation, whether written or verbal, and to the Lake County, IL Code of Ordinances, as amended.
- 2.The Applicant shall supply, at his expense, such information or submittals as the Lake County Division of Transportation may require to complete the review of the Proposed Work.
- 3.Lack of an immediate response to this application form or any information submitted for review and/or comment shall not be construed as approval or acceptance of the application or submittal.
- 4.The review of the Proposed Work by the Lake County Division of Transportation shall be based on the primary use of the County Highway right-of-way is to provide for the safe and efficient movement of vehicular traffic. All other uses of the right-of-way that do not support or provide for this primary use shall be subordinate.
- 5. The Lake County Division of Transportation is not responsible for providing room within the County Highway right-of-way for the Proposed Work and lack of sufficient room can be cause for not permitting the Proposed Work to be located within the County Highway right-of-way.
- 6.The Proposed Work may not be permitted if it will create a hazard to the Public or interfere with the ability of the Lake County Division of Transportation to operate and maintain the County Highway right-of-way.
- 7. This Application does not relieve the Applicant from obtaining permission and authority from the Federal, State, County or Local Government or any political subdivision or administrative agency which may administer any statutes, regulations, ordinances or administrative orders that pertain to the Proposed Work.
- 8. The Applicant is cautioned that the County Highway rights-of-way have been obtained for Public Road Purposes and any other use of the right-of-way is subject to approval or permission from the legal property owner. The Applicant shall be responsible for contacting the property owner and obtaining any required approval or permission.
- 9.The Lake County Division of Transportation, its employees and its agents, and the County of Lake, its employees and its agents shall not be held responsible for costs or delays to the Applicant due to the processing time required by the Lake County Division of Transportation to review information or submittals by the Applicant or his authorized agents.
- 10. The submittal of this Application by the Applicant does not obligate the County Engineer to issue a permit.
- 11.If the Proposed Work is permitted the Applicant and his successors and assigns shall be generally responsible for the following:
 - a. Obtaining any other permission or authority needed for the Proposed Work.
 - b. Having the Proposed Work completed, including any required restoration work.
 - c. Supplying any required bonding and/or insurance.
 - d.Not making any changes to the approved Proposed Work without prior permission.
 - e.Providing maintenance for the completed Proposed Work.
 - f.Making or having made any adjustments or changes to the completed Proposed Work due to maintenance or construction work of the Highway Authority.
 - g. Assuming liability for the Proposed Work during construction and after completion.
 - h.Removal of the completed Proposed Work if required in the future.
 - i.The costs involved by the above responsibilities and any other costs related to the Proposed Work.

| FOR LCDOT USE ONLY | |
|-----------------------|--|
| Application Number | |



10.

600 W. Winchester Road Libertyville, IL 60048 Telephone: (847) 377-7400 Fax: (847) 984-5944

Email: hdpermits@lakecountyil.gov

APPLICATION FOR A SPECIAL EVENT ON A COUNTY HIGHWAY TEMPORARY CLOSURE OF A COUNTY HIGHWAY

(This Form Must Be Submitted A Minimum Of 30 Days Prior To The Planned Event) (Please print or type) APPLICANT: Name/Company: Mailing Address: Fax Number: Telephone: E-mail Address: In accordance with the Lake County, IL Code of Ordinances, as amended, the above Applicant hereby makes application to the County Engineer of Lake County for permission to temporarily close a section of County Highway for a special event of public interest. This proposed closure is described as follows: 1. Name of County Highway: (If multiple County Highways are needed for the same event separate applications and fees are required for each County Highway) 2. **Limits of Closure:** (From street to street) 3. Type of Closure: Full Closure Partial Closure Description: 4. **Type of Special Event** (check all that apply): ☐ Parade Race (walking/running) Race (bicycling) Street Festival Filming (movie, television, etc.) Other ____ 5. Name of Event Date(s) of Event: Time Limit of Closure: 6. **Estimated Attendance:** Estimated Participants: 7. Agent for Applicant (if applicable): Name & Company Mailing Address: Fax Number: Telephone Number: E-mail Address: **Person in Charge** (contact person for the day of the event and 24-hour emergency contact): 8. Name & Company: Mailing Address: Mobile Number: Telephone Number: E-mail Address: Police Department (police department handling the traffic control and closure of the County Highway): 9. Name & Dept: Mailing Address: Fax Number: Telephone Number: E-mail Address:

NOTES: Attach Course Route Map Or Location Map For The Special Event With This Application.
This Application Is Subject To The General Conditions As Printed On Page 2.

THIS APPLICATION IS ONLY VALID WHEN AN ORIGINAL SIGNATURE IS PROVIDED ON PAGE 2.

Enclosed Application Fee (all fees non-refundable):

GENERAL CONDITIONS FOR APPLICATON TO REQUEST TEMPORARY CLOSURE OF A COUNTY HIGHWAY

- 1. In submitting this Application, the Applicant agrees to comply with the various policies, conditions and requirements of the Lake County Division of Transportation, whether written or verbal, and to the Lake County, IL Code of Ordinances, as amended, to make such changes and revisions to the Proposed Special Event as may be necessary to comply or more closely conform to those various policies, conditions and requirements of the Lake County Division of Transportation, whether written or verbal, and to the Lake County, IL Code of Ordinances, as amended.
- 2. The Applicant shall supply, at his expense, such information or submittals as the Lake County Division of Transportation may require to complete the review of the Proposed Temporary Highway Closure.
- Lack of an immediate response to this application form or any information submitted for review and/or comment shall not be construed as approval or acceptance of the application or submittal.
- 4. The Proposed Temporary Highway Closure may not be permitted if it will create a hazard to the Public or interfere with the ability of the Lake County Division of Transportation to operate and maintain the County Highway right-of-way.
- 5. This Application does not relieve the Applicant from obtaining permission and authority from the Federal, State, County or Local Government or any political subdivision or administrative agency which may administer any statutes, regulations, ordinances or administrative orders that pertain to the Proposed Special Event.
- 6. The Applicant is cautioned that the County Highway rights-of-way have been obtained for Public Road Purposes and any other use of the right-of-way is subject to approval or permission from the legal property owner. The Applicant shall be responsible for contacting the property owner and obtaining any required approval or permission.
- 7. The Lake County Division of Transportation, its employees and its agents, and the County of Lake, its employees and its agents shall not be held responsible for costs or delays to the Applicant due to the processing time required by the Lake County Division of Transportation to review information or submittals by the Applicant or his authorized agents.
- 8. The submittal of this Application by the Applicant does not obligate the County Engineer to issue a permit.
- 9. Application and Permit fees are non-refundable once processed.
- 10. If the Proposed Temporary Highway Closure is permitted the Applicant and his successors and assigns shall be generally responsible for the following:
 - a. Obtaining any other permission or authority needed for the Proposed Special Event.
 - Supplying acceptable proof of insurance.
 - c. Posting advance notification of the Proposed Temporary Highway Closure to the motoring public.
 - d. Providing the required traffic control including signage and police/Sheriff presence or assistance if required.
 - e. Allowing safe passage of emergency vehicles through the Proposed Temporary Highway Closure.
 - f. Cleaning and maintaining the County Highway right-of-way during and immediately after the Proposed Special Event. This includes keeping the pavement surface free of mud, gravel, debris, trash, and other extraneous materials.
 - g. Other items as specified in the Lake County Highway Access and Use Ordinance.

| SIGNATURE BLOCK | | | | |
|-----------------------------------|--|--|--|--|
| | | | | |
| (Signature of Applicant) | | | | |
| (Printed name of above signature) | | | | |
| | | | | |
| (Title) | | | | |

| FOR LCDOT USE ONLY | | | |
|--------------------------|--|--|--|
| Application Number | | | |
| Utility Reference Number | | | |

600 W. Winchester Road Libertyville, IL 60048 Telephone: 847 377 7400 Fax: 847 984 5944

Email: hdpermits@lakecountyil.gov

EMERGENCY REPAIR NOTIFICATION FORM

LakeCounty
Division of Transportation

Signature of authorized employee or agent for applicant

FOR WORK WITHIN A COUNTY HIGHWAY RIGHT-OF-WAY(SUBMIT WITHIN 24-HOURS OF EMERGENCY) (Please print or type) APPLICANT (Name and address): Telephone Number: _____ Fax Number: _____ E-mail Address: Hereby requests permission from the County Engineer of Lake County to excavate within the County Highway Right-of-Way in order to make repairs to an existing utility/facility. This repair work and existing utility/facility are described as follows: Name of County Highway: Type of Utility/Facility to be repaired:

FACILITY ☐ UTILITY 2. (Check one of the boxes) (water main, sanitary sewer) (electric, gas, telephone, cable) 3. Location and extent of Repair Work (distance and direction from cross street, which side of County Highway, distance from pavement edge, size and depth of excavation, start and completion dates, etc.): Pavement Opening: None required Required (Open Cut Permit and Charges Required) (explain type of opening such as traffic lane, turning lane, paved shoulder, driveway, side road): **Contact Person** (name, company, 24-hour telephone number): Excavation and Repair Work to be done by (name, address, telephone number): Comments: NOTE: SEE PAGE 2 OF THIS FORM FOR EMERGENCY REPAIR WORK GENERAL CONDITIONS. The above Applicant hereby agrees to complete the repair work as quickly as possible and to restore the damaged and/or disturbed portions of the County Highway Right-of-Way as required by the LCDOT. It is further understood that the LCDOT reserves the right to require the Utility/Facility Owner to obtain the appropriate permit(s) and pay associated application/permit fees under the Lake County, IL Code of Ordinances.

Note: This Emergency Repair Notification Form is subject to the General Conditions as printed on Page 2 of this form.

Printed Name

Date

GENERAL CONDITIONS FOR EMERGENCY REPAIR WORK

- In submitting this Emergency Repair Notification Form, the Utility/Facility Owner (as Applicant) agrees to comply with the Lake County. IL Code of Ordinances and the various policies, conditions and requirements of the Lake County Division of Transportation (LCDOT), whether written or verbal.
- 2. Emergency repair work may be performed on a utility or facility located within a right-of-way of a County Highway prior to obtaining a permit to perform the work necessary to remedy the emergency situation. LCDOT shall be notified immediately during business hours and the Lake County Sheriff's Office shall be notified outside of normal business hours.
- 3. This Emergency Repair Notification Form shall be submitted to the LCDOT within 24-hours of the discovery of the emergency. A permit application for the emergency work shall be received by the LCDOT no later than one week after the emergency had been identified. The County Engineer shall determine whether a permit is required for the work performed. A permit is required for all pavement open cuts.
- 4. The duration of the emergency repair work is 72 hours or less. Temporary pavement may be required as part of the emergency repair work. All permanent restoration to pavement, shoulders and right-of-way that was disturbed as the result of the emergency work shall be completed within one week of the completion of the emergency repair if weather conditions are suitable.
- 5. The Applicant shall indemnify, defend and hold harmless the County of Lake and the Lake County Division of Transportation including their elected and duly appointed officials, agents, employees and representatives from and against any and all claims, suits, actions, losses, expenses, damages, injuries, deaths, judgments, and demands arising from and relating to this repair work regardless of any limitations of insurance coverage.
- 6. The Applicant shall pay all damages, judgments, costs and expenses including attorney's fees and court costs in connection with or resulting from the emergency repair work regardless of any limitations of insurance coverage.
- 7. This Emergency Repair Notification Form does not release the Applicant from compliance with the provisions of any existing statutes, regulations, ordinances or administrative orders of the Federal, State, County or Local Government or any political subdivision or administrative agency thereof relating to the emergency repair work.
- 8. The Applicant shall not, at any time or in any circumstances, create any hazards to the General Public during the emergency repair work and/or restoration of the County Highway right-of-way, the Applicant shall meet the following requirements: a) Vehicle traffic using the County Highway (including vehicle traffic to and from adjacent properties) shall be maintained; b) All regulatory signing and warning devices shall at all times be kept in view of the motoring public; c) Construction equipment and materials shall be stored off the right-of-way and there shall be no parking or storage of vehicles, materials or equipment within the right-of-way at any time; d) Excavation shall be kept to a minimum and closed up or fenced off at the close of each working day; e) Roadway pavements shall not be damaged by construction equipment and shall be kept clean of debris at all times; f) Drainage shall be maintained; g) The LCDOT shall be notified about any tile lines found; h) The disturbed areas of the County Highway right-of-way shall be promptly restored to a condition equal or better than existed or as directed by the LCDOT.
- 9. The Applicant shall be responsible for the total cost of the repair work, traffic control, clean-up, and County Highway right-of-way restoration. The Owner shall be responsible for any costs incurred by the Lake County Division of Transportation to enforce the provisions of the Lake County, IL Code of Ordinances.
- 10. The Applicant shall be responsible for repairing or the cost of repairing damage to any highway appurtenances and/or any equipment of any other Utility/Facility Owner located within the County Highway right-of-way caused by the emergency repair work.
- 11. The applicable portions of the current "Manual of Uniform Traffic Control Devices for Streets and Highways," "Standard Specifications for Road and Bridge Construction," and the "Highway Standards" manual as published by the Illinois Department of Transportation shall apply to this repair work, traffic control, clean-up, and restoration.
- 12. The Snow and Ice Removal Operations of the LCDOT shall have precedence over all emergency repair work.
- 13. The Applicant shall be responsible for maintenance of the disturbed areas of the County Highway right-of-way, until such time as the restoration has been completed.

Page 2 of 2

| FOR LCDOT OR UTILITY COMPANY USE | E ONLY |
|----------------------------------|--------|
| LCDOT Application/Utility Ref # | |



600 W. Winchester Road Libertyville, IL 60048 Telephone: (847) 377-7400 Fax: (847) 984-5944 hdpermits@lakecountyil.gov

PAVEMENT OPEN CUT REQUEST FORM

THIS FORM MUST BE SUBMITTED WITH THE APPLICATION FOR LAKE COUNTY DOT UTILITY/FACILITY PERMIT

(Please print or type)

| Applicant: | |
|-----------------|--|
| County Highway: | |

Applicants working within LCDOT's rights-of-way shall take all steps necessary to avoid open cutting the pavement. No open cutting is allowed without prior permission of LCDOT.

If there is no alternative to open cutting, the Permittee must first submit this request form with the necessary payment before work can begin. Any open cut shall be kept to the minimum size necessary to complete the work.

- 1. The Permittee shall demonstrate that an open cut in a County Highway is the only option available to complete the desired work. Cost or convenience to the Permittee is not a justifiable reason to permit an open cut of a County Highway.
- 2. A dimensioned engineering plan, prepared at a 1"=20' scale, showing all existing pavement, right-of-way, sidewalks, bike paths, guardrail, trees, curb and gutter, traffic signals, traffic signal loops, storm sewer structures, existing lane configuration, location of the proposed open cut, and proposed traffic control, including taper rates and signing, for the open cut area.
- 3. To determine the open cut charge, complete the following open cut estimate:

| a. | Basic Charge | \$ 700 |
|----|--|-----------|
| b. | Sq Ft of pavement opened × \$25.00 per Sq Ft | \$ |
| c. | Inspection Fee | \$ 350 |
| d. | Total Open Cut Charge (Items A+B+C) | \$ |

- 4. After the requested permit has been issued, the Permittee shall be required to hold an onsite meeting with the Permittee's contractor or workforce and the LCDOT's Manager of Highway Operations to go over the proposed work, traffic control, and the timing of any needed lane closures.
- 5. Any pavement opened must be permanently patched the same day.
- 6. The patching requirements are as follows:
 - a. The open cut pavement shall be replaced with flowable fill within 12 inches of the finished grade. The remaining 12 inches shall be Hot Mix Asphalt Binder Course, IL 19.0 N70, 10 inches and Hot Mix Asphalt Surface, Mix D, N70, 2 inches. The flowable-fill must setup within 1 hour.
 - b. No open cuts shall be permitted between November 15th and April 15th.
 - c. Please contact the LCDOT Permits Department at (847) 377-7400 to schedule the open cut.



600 W. Winchester Road Libertyville, IL 60048 Telephone: 847 377 7400

LOCAL AGENCY UTILITY/FACILITY ACCEPTANCE ON A COUNTY HIGHWAY

(Please print or type)

| APP | LICANT (Name and address): |
|-----------------|--|
| | Telephone Number: |
| Engii limits | g a Local Agency in the State of Illinois, County of Lake, hereby requests permission from the County neer of Lake County to locate and maintain the below described Local Agency Utility/Facility within the right-of-way of a County Highway in accordance with the Lake County, IL Code of Ordinances, as amended. Local Agency Utility/Facility is described as follows: |
| 1. | Name of County Highway: |
| 2. | Location (distance from nearest intersection, which side of road, etc.): |
| | |
| 3. | Type of Local Agency Utility/Facility (watermain, sidewalk, etc.): |
| | |
| 4. | Utility/Facility to be constructed by: Local Agency Crews (contact person): |
| | Contractor (name, address, telephone): |
| | Developer (name, address, telephone): |
| | Other (name, address, telephone): |
| 5. | Comments (if needed): |

NOTE: This Acceptance is subject to the General Conditions as printed on the reverse side of this form. The Application is only valid when an original signature is provided on page 2.

GENERAL CONDITIONS FOR LOCAL AGENCY UTILITY/FACILITY ACCEPTANCE ON A COUNTY HIGHWAY

- 1. In submitting this Acceptance, the Local Agency agrees to comply with the various policies, conditions and requirements of the Lake County Division of Transportation, whether written or verbal and the Lake County, IL Code of Ordinances, as amended.
- 2. The Local Agency shall supply, at its expense, such information or submittals as may be required for review and to make such changes or revisions as required by the Lake County Division of Transportation.
- 3. Lack of an immediate response to this application form or any information or submittals supplied for review and/or comment shall not be construed as approval or acceptance by the County Engineer or the Lake County Division of Transportation, nor shall they be held responsible for any costs or delays due to the processing time required.
- 4. The review of the Local Agency Utility/Facility shall be based on the primary use of the County Highway right-of-way for the safe and efficient movement of vehicular traffic and the maintenance and improvements needed to support such primary use.
- 5. The Lake County Division of Transportation shall not be responsible for providing room within the County Highway right-of-way for the Local Agency Utility/Facility.
- 6. This Acceptance does not relieve the Local Agency from complying with any statutes, regulations, ordinances or administrative orders of the Federal, State or County Governments or any political subdivision or administrative agencies that may apply to the Local Agency Utility/Facility.
- 7. The Local Agency shall obtain permission from the legal property owner of the County Highway right-of-way where the Local Agency Utility/Facility will be located.
- 8. Unless otherwise stated in the issued Highway Permit, the Local Agency and its successors and assigns shall be responsible for the following:
 - a. The operation and maintenance of the Local Agency Facility within the County Highway right-of-way. Such operation and maintenance shall include keeping the Local Agency Facility in a safe condition for use by the Public, not creating any hazardous conditions, providing any special maintenance such as cleaning ice and snow from sidewalks or bike paths or additional mowing of adjacent turf areas, making changes or revisions to the Local Agency Facility needed because of the maintenance operations of the Lake County Division of Transportation or use of the County Highway right-of-way by the General Public and restoring portions of the County Highway right-of-way disturbed by repairs, maintenance, extensions, service connections, and/or other work done to the Local Agency Facility without a Highway Permit being issued.
 - b. Any additional costs to the County of Lake and/or its Division of Transportation for road improvements and/or maintenance work due to the location and/or use of the Local Agency Facility within the County Highway right-of-way. Such costs can include adjustments needed to the Local Agency Facility to accommodate said road improvements and/or maintenance work and/or damage to County Property and/or equipment.
 - c. For indemnifying, defending and holding harmless the County of Lake and the Lake County Division of Transportation including their elected and duly appointed officials, agents, employees and representatives from and against any and all claims, suits, actions, losses, expenses, damages, injuries, deaths, judgments and demands arising from and relating to the location and/or use of the Local Agency Facility within the County Highway right-of-way regardless of any limitations of insurance coverage.
 - d. Other items as specified in the Lake County Highway, IL Code of Ordinances, as amended.

| 9. | If a separate application is made by an App | licant other than the Local Agency to construct the Utility/Facility, then the Lo | cal |
|----|---|---|-----|
| | Agency, by submitting this Acceptance form, | hereby acknowledges that it will become the successor or assign of this Applic | ant |
| | for the said Utility/Facility. | | |
| | ATTEST: | FOR THE LOCAL AGENCY: | |

| | Ву: | |
|--------------------|-------|------------------------|
| Local Agency Clerk | | Local Agency President |
| | Date: | |



600 W. Winchester Road Libertyville, IL 60048 Telephone: 847 377 7400

PROPERTY OWNER UTILITY/FACILITY ACCEPTANCE ON A COUNTY HIGHWAY

(Please print or type)

| APPLICANT (Name and address): | | |
|-------------------------------|--|--|
| | Telephone Number: | |
| Engi imits | g a Property Owner in the State of Illinois, County of Lake, hereby requests permission from the County neer of Lake County to locate and maintain the below described private Utility/Facility within the right-of-way of a County Highway in accordance with the Lake County, IL Code of Ordinances, as amended. private Utility/Facility is described as follows: | |
| 1. | Name of County Highway: | |
| 2. | Location (distance from nearest intersection, which side of road, etc.): | |
| 3. | Type of Utility/Facility (water service, sanitary service, etc): | |
| 4. | Utility/Facility to be constructed by: | |
| | Contractor (name, address, telephone): | |
| | Developer (name, address, telephone): | |
| | Other (name, address, telephone): | |
| 5. | Comments (if needed): | |

NOTE: This Acceptance is subject to the General Conditions as printed on the reverse side of this form. The Application is only valid when an original signature is provided on page 2.

GENERAL CONDITIONS FOR PROPERTY OWNER UTILITY/FACILITY ACCEPTANCE ON A COUNTY HIGHWAY

- In submitting this Acceptance, the Property Owner agrees to comply with the various policies, conditions and requirements of the Lake County Division of Transportation, whether written or verbal and the Lake County, IL Code of Ordinances, as amended.
- 2. The Property Owner shall supply, at its expense, such information or submittals as may be required for review and to make such changes or revisions as required by the Lake County Division of Transportation.
- 3. Lack of an immediate response to this application form or any information or submittals supplied for review and/or comment shall not be construed as approval or acceptance by the County Engineer or the Lake County Division of Transportation, nor shall they be held responsible for any costs or delays due to the processing time required.
- 4. The review of the private Utility/Facility shall be based on the primary use of the County Highway right-of-way for the safe and efficient movement of vehicular traffic and the maintenance and improvements needed to support such primary use.
- The Lake County Division of Transportation shall not be responsible for providing room within the County Highway right-ofway for the private Utility/Facility.
- 6. This Acceptance does not relieve the Property Owner from complying with any statutes, regulations, ordinances or administrative orders of the Federal, State or County Governments or any political subdivision or administrative agencies that may apply to the private Utility/Facility.
- 7. The Property Owner shall obtain permission from the legal property owner of the County Highway right-of-way where the private Utility/Facility will be located.
- 8. Unless otherwise stated in the issued Highway Permit, the Property Owner and its successors and assigns shall be responsible for the following:
 - a. The operation and maintenance of the private Utility/Facility within the County Highway right-of-way. Such operation and maintenance shall include keeping the private Utility/Facility in a safe condition for use by the Public, not creating any hazardous conditions, providing any special maintenance such as cleaning ice and snow from sidewalks or bike paths or additional mowing of adjacent turf areas, making changes or revisions to the private Utility/Facility needed because of the maintenance operations of the Lake County Division of Transportation or use of the County Highway right-of-way by the General Public and restoring portions of the County Highway right-of-way disturbed by repairs, maintenance, extensions, service connections, and/or other work done to the private Utility/Facility without a Highway Permit being issued.
 - b. Any additional costs to the County of Lake and/or its Division of Transportation for road improvements and/or maintenance work due to the location and/or use of the private Utility/Facility within the County Highway right-of-way. Such costs can include adjustments needed to the private Utility/Facility to accommodate said road improvements and/or maintenance work and/or damage to County Property and/or equipment.
 - c. For indemnifying, defending and holding harmless the County of Lake and the Lake County Division of Transportation including their elected and duly appointed officials, agents, employees and representatives from and against any and all claims, suits, actions, losses, expenses, damages, injuries, deaths, judgments and demands arising from and relating to the location and/or use of the private Utility/Facility within the County Highway right-of-way regardless of any limitations of insurance coverage.
 - d. Other items as specified in the Lake County Highway, IL Code of Ordinances, as amended.

| 9. | If a separate application is made by an Applicant other than the Property Owner to construct the Utility/Facility, then the |
|----|---|
| | Property Owner, by submitting this Acceptance form, hereby acknowledges that it will become the successor or assign of this |
| | Applicant for the said Utility/Facility. |

| | (Signature of Applicant) |
|-------|-----------------------------------|
| | (Printed Name of Above Signature) |
| Date: | |



600 W. Winchester Road Libertyville, IL 60048 Telephone: 847 377 7400

PUBLIC UTILITY/FACILITY ACCEPTANCE ON A COUNTY HIGHWAY

(Please print or type) APPLICANT (Name and address): Telephone Number: being a public utility in the State of Illinois, County of Lake, hereby requests permission from the County Engineer of Lake County to locate and maintain the below described Public Utility/Facility within the right-of-way limits of a County Highway in accordance with the Lake County, IL Code of Ordinances, as amended. This Public Utility/Facility is described as follows: 1. Name of County Highway: 2. **Location** (distance from nearest intersection, which side of road, etc.): 3. Type of Public Utility/Facility (watermain, sidewalk, etc.): Utility/Facility to be constructed by:

Public Utility Crews (contact person): 4. Contractor (name, address, telephone): Developer (name, address, telephone): Other (name, address, telephone): 5. Comments (if needed):

NOTE: This Acceptance is subject to the General Conditions as printed on the reverse side of this form. The Application is only valid when an original signature is provided on page 2.

GENERAL CONDITIONS FOR PUBLIC UTILITY/FACILITY ACCEPTANCE ON A COUNTY HIGHWAY

- 1. In submitting this Acceptance, the Public Utility agrees to comply with the various policies, conditions and requirements of the Lake County Division of Transportation, whether written or verbal and the Lake County, IL Code of Ordinances, as amended.
- 2. The Public Utility shall supply, at its expense, such information or submittals as may be required for review and to make such changes or revisions as required by the Lake County Division of Transportation.
- 3. Lack of an immediate response to this application form or any information or submittals supplied for review and/or comment shall not be construed as approval or acceptance by the County Engineer or the Lake County Division of Transportation, nor shall they be held responsible for any costs or delays due to the processing time required.
- 4. The review of the Public Utility/Facility shall be based on the primary use of the County Highway right-of-way for the safe and efficient movement of vehicular traffic and the maintenance and improvements needed to support such primary use.
- 5. The Lake County Division of Transportation shall not be responsible for providing room within the County Highway right-of-way for the Public Utility/Facility.
- 6. This Acceptance does not relieve the Public Utility from complying with any statutes, regulations, ordinances or administrative orders of the Federal, State or County Governments or any political subdivision or administrative agencies that may apply to the Public Utility/Facility.
- 7. The Public Utility shall obtain permission from the legal property owner of the County Highway right-of-way where the Public Utility/Facility will be located.
- 8. Unless otherwise stated in the issued Highway Permit, the Public Utility and its successors and assigns shall be responsible for the following:
 - a. The operation and maintenance of the Public Facility within the County Highway right-of-way. Such operation and maintenance shall include keeping the Public Facility in a safe condition for use by the Public, not creating any hazardous conditions, providing any special maintenance such as cleaning ice and snow from sidewalks or bike paths or additional mowing of adjacent turf areas, making changes or revisions to the Public Facility needed because of the maintenance operations of the Lake County Division of Transportation or use of the County Highway right-of-way by the General Public and restoring portions of the County Highway right-of-way disturbed by repairs, maintenance, extensions, service connections, and/or other work done to the Public Facility without a Highway Permit being issued.
 - b. Any additional costs to the County of Lake and/or its Division of Transportation for road improvements and/or maintenance work due to the location and/or use of the Public Facility within the County Highway right-of-way. Such costs can include adjustments needed to the Public Facility to accommodate said road improvements and/or maintenance work and/or damage to County Property and/or equipment.
 - c. For indemnifying, defending and holding harmless the County of Lake and the Lake County Division of Transportation including their elected and duly appointed officials, agents, employees and representatives from and against any and all claims, suits, actions, losses, expenses, damages, injuries, deaths, judgments and demands arising from and relating to the location and/or use of the Public Facility within the County Highway right-of-way regardless of any limitations of insurance coverage.
 - d. Other items as specified in the Lake County, IL Code of Ordinances, as amended.

| 9. | If a separate application is made by an Applicant other than the Public Utility to construct the Utility/Facility, then the Public |
|----|--|
| | Utility, by submitting this Acceptance form, hereby acknowledges that it will become the successor or assign of this Applicant |
| | for the said Utility/Facility. |

| ATTEST: | FOR THE PUBLIC UTILITY: | |
|--------------|-------------------------|--------|
| | Ву: | |
| Public Clerk | Public Mayor/Pre | sident |
| | Date: | |

Major Access Permit Checklist

The following checked items must be provided to the LCDOT permit department for review and approval. Additional information may be requested during your permit process. The format for the preparation of these items may be found in Chapter 90 of the Lake County Code of Ordinances. http://www.amlegal.com/nxt/gateway.dll?f=templates&fn=default.htm&vid=amlegal:lakecounty_il

| Not Required | Submitted | Completed | Date Completed | |
|-----------------|-----------|-----------|-------------------|---|
| | | | | Pre-Application Meeting |
| | | | | Access Application |
| | | | | Variance Application & Fee |
| | | | | Facility Application & Fee |
| | | | | Municipal Acceptance Form |
| | | | | Photographs of the Right-of-Way |
| | | | | Sight Distance Study |
| | | | | Traffic Impact Study or Waiver Request |
| | | | | Traffic Signal Warrant Analysis |
| | | | | Traffic Signal Agreement with Public Entity |
| | | | | Geometric Plan |
| | | | | Major Access Fee |
| | | | | Pavement Design |
| | | | | Drainage Study/Water Quality Plan |
| | | | | Plat of Dedication |
| | | | | Plat of Subdivision |
| | | | | Engineering Plans |
| | | | | Cost Estimate |
| | | | | Performance Guarantee (Letter of Credit) |
| | | | | Certificate of Insurance & Endorsement |
| | | | | Permit & Inspection Fees |
| | | | | Developer/Resident Engineer Agreement Letter |
| | | | | Resident Engineer Letter |
| | | | | On-site Engineering Plan (approved by Village) |
| | | | | Electric Utility Application (N/A) |
| | | | | Telephone Utility Application (N/A) |
| | | | | Cable Utility Application (N/A) |
| | | | | Gas Utility Application (N/A) |
| | | | | As-built Plans |
| | | | | Performance Guarantee Inspection Request Letter |
| | | | | Maintenance Guarantee (Letter of Credit) |
| | | | | Maintenance Guarantee Inspection Request Letter |

Facility Permit Checklist

The following checked items must be provided to the LCDOT permit department for review and approval. Additional information may be requested during your permit process. The format for the preparation of these items may be found in the Lake County,, IL Code of Ordinances. The ordinance may be found online at: www.lakecountyil.gov/Transportation/Publications/Ordinances.htm

| Not | | | Date | |
|----------|-----------|-----------|-----------|---|
| Required | Submitted | Completed | Completed | |
| | | | | Pre-Application Meeting |
| | | | | Facility Application & Fee |
| | | | | Municipal Acceptance Form |
| | | | | Photographs of the Right-of-Way |
| | | | | Drainage Study |
| | | | | Water Quality Plan |
| | | | | Engineering Plans |
| | | | | Performance Guarantee (Letter of Credit) |
| | | | | Certificate of Insurance & Endorsement |
| | | | | Permit & Inspection Fees |
| | | | | Person in Charge Letter |
| | | | | Electric Utility Application (N/A) |
| | | | | Telephone Utility Application (N/A) |
| | | | | Cable Utility Application (N/A) |
| | | | | Gas Utility Application (N/A) |
| | | | | As-built Plans (Electronic and Hard Copy) |
| | | | | Performance Guarantee Inspection Request Letter |

SAMPLE RESIDENT ENGINEER LETTER

(COMPANY LETTERHEAD)

| (Date) |
|--|
| (Project Name) (County Highway Name) |
| The following information is offered in compliance with the Lake County Access and Use Ordinance requirements: |
| Company Name: Resident Engineer Name: State of Illinois P.E. Registration #: Address: Phone: Email Address: |
| will be the Resident Engineer for the above referenced project with regard to work on and within the County Highway and right-of-way. The Resident Engineer will make of cause to be made the necessary inspections to verify the work is being constructed according to plans and permit and will, upon completion of the work, certify in writing that the work was completed as specified in the approved plans and permit. The Resident Engineer will also make a written request to the Lake County Division of Transportation for an inspection of the completed work on and within the County Highway and right-of-way. |
| Please feel free to contact me ifyou have any questions regarding this notification. |
| Sincerely, |
| (Name) |
| (Title) |

SAMPLE DEVELOPER AND RESIDENT ENGINEER AGREEMENT

| Major Access Permit No. [County Highway Name] |
|---|
| I, [Name of Individual], on behalf of [Development Company], certify that I have secured a contract with [Resident Engineer Name] of [Engineering Company] to provide construction inspection services and to fulfill the Resident Engineer duties in accordance with Chapter 90 of the Lake County Code of Ordinances. |
| I agree to ensure that the contractors working on behalf of my development shall notify the Resident Engineer regarding the times that work will be taking place in the right-of-way of the County Highway so that the Resident Engineer may be present to fulfill his/her duties as Resident Engineer. |
| I further agree that failure on my part to fulfill this obligation may result in the assessment of fines against my organization in accordance with Section 30.333 - Violations and Penalties of the Lake County Code of Ordinances. |
| Dated this day of |
| By: |
| Printed Name |
| [Developer Name & Address] |

CHAPTER 3 Highway Classification

County Highway Access Classification identifies the intended level of mobility of each County Highway under LCDOT permitting authority. The assigned classification is based on current roadway function as well as County strategic and long range plans for the corridor.

Access Classification impacts permit requirements in the following ways:

- 1. Access to a roadway classified as a Designated Freeway requires approval of the County Board
- 2. Required right-of-way dedication width increases as intended level of mobility increases
- 3. Design standards vary based on road function and classification
- 4. LCDOT will take into account access classification when considering requests related to access policies (i.e. spacing, number of access points, etc.)

In addition to Access Classification, context or surrounding land use of a roadway impacts appropriate standards for right-of-way dedication (future expansion) and design of required highway improvements. In order to consider context of the roadway in permit requests, LCDOT will also use Functional Classifications as defined in the IDOT Bureau of Local Roads and Streets (BLRS) Manual Chapter 27-3 (Arterial, Collector, Local), Types of Development Areas surrounding the roadway, as defined in BLRS Manual Chapter 27-4 (Rural, Suburban, Urban Central Business District, Urban Fringe Area/Outlying Business District), and Central Business Districts identified in the Lake County Framework Plan when reviewing required highway improvements for Major Access permits.

Access Classifications are defined in Chapter 4 of the Ordinance. Access Classification for each County Highway are depicted on Figure 3.1 and summarized in Table 3.1 following this page. The LCDOT will review these classifications annually and will consider requests from local agencies during this review.




Table 3.1 Lake County Highway Access Classification Designations

| Danderer Name | A a a a a Classification | France | T-0 |
|-------------------------------|------------------------------------|------------------------------|--------------------------|
| Roadway Name 21st Street | Access Classification Low Mobility | From Delany Rd | IL Rte 173 |
| 33rd Street | Low Mobility | IL Rte 131 | North Shore Bicycle Path |
| 9th Street | Low Mobility | IL Rte 131 | IL Rte 137 |
| | Medium Mobility | Peterson Rd | IL Rte 120 |
| Alleghany Rd Almond Road | Low Mobility | Fairfield Ln | Washington St |
| Aptakisic Rd | High Mobility | IL Rte 83 | IL Rte 21/US Rte 45 |
| Arlington Heights Rd | High Mobility | Lake Cook Rd | IL Rte 83 |
| Big Hollow Rd | Medium Mobility | Lake/McHenry County Line | US Rte 12 |
| Bonner Rd | Medium Mobility | . , , | + |
| | | Darrell Rd | IL Rte 12 |
| Bonner Rd Buffalo Grove Rd | Low Mobility | IL Rte 12 | Fairfield |
| | Medium Mobility | US Rte 45 | IL Rte 22 |
| Buffalo Grove Rd | High Mobility | IL Rte 22 | Lake Cook Rd |
| Butterfield Rd | High Mobility | US Rte 45 | IL Rte 137 |
| Casey Rd | Low Mobility | IL Rte 137 | US Rte 45 |
| Casimer Pulaski Dr | Medium Mobility | IL Rte 43 | IL Rte 131 |
| 14th St | Permitted by Others | IL Rte 131 | IL Rte 137 |
| Cedar Lake Rd | Low Mobility | II Rte 132 | IL Rt 120 |
| Cedar Lake Rd | Medium Mobility | IL Rte 120 | IL Rte 60 |
| Center St | Medium Mobility | IL Rte 83 | US Rte 45 |
| Cuba Rd | Low Mobility | IL Rte 59 | US Rte 12 |
| Darrell Rd | Medium Mobility | IL Rte 120 | IL Rte 176 |
| Darrell Rd | Low Mobility | IL Rte 176 | Roberts Rd |
| Deep Lake Road | Medium Mobility | IL Rte 132 | IL-WI State Line |
| Deerfield Pkwy | High Mobility | IL Rte 83 | IL Rte 21/US Rte 45 |
| Deerfield Rd | High Mobility | IL Rte 21/US Rte 45 | Wilmot Rd |
| Deerfield Rd | Permitted by Others | IL Rte 41 | IL Rte 43 |
| Delany Rd | Medium Mobility | IL Rte 173 | Yorkhouse Rd |
| Delany Rd | High Mobility | Yorkhouse Rd | IL Rte 41 |
| Diamond Lake Rd | Low Mobility | Gilmer Rd | IL Rte 60/83 |
| Dilley's Rd | Medium Mobility | Grand Ave | Wadsworth Rd |
| Duffy Ln | Low Mobility | Riverwoods Rd | East of I-94 |
| Ela Rd | Medium Mobility | Lake Cook Rd | IL Rte 22 |
| Engle Dr | Low Mobility | IL Rte 83 | N Nathan Hale Dr |
| Everett Rd | Low Mobility | St. Mary's Rd | Estate Ln |
| Fairfield Rd | Medium Mobility | Petite Lake Road | Rollins Rd |
| Fairfield Rd | Low Mobility | Rollins Rd | IL Rte 120 |
| Fairfield Rd | Medium Mobility | IL Rte 120 | Old McHenry Rd |
| Fremont Center Rd | Medium Mobility | Gilmer Rd | IL Rte 60 |
| Gages Lake Rd | Medium Mobility | US Rte 45 | IL Rte 21 |
| Gelden Rd | Low Mobility | Deep Lake Rd | Grass Lake Rd |
| Genoa Ave | Low Mobility | N Nathan Hale Dr | Granada Blvd |
| Gilmer Rd | Medium Mobility | IL Rte 120 | IL Rte 83 |
| Granada Blvd | Low Mobility | Genoa Ave | IL Rte 132 |
| Grass Lake Rd | Medium Mobility | State Park Rd | US Rte 45 |
| Greenleaf St | Medium Mobility | IL Rte 120 (North Exit Ramp) | Washington Street |
| Hainesville Rd | Low Mobility | IL Rte 120 | Rollins Rd |
| Hart Rd | Low Mobility | Lake Cook Rd | US Rte 14 |
| Hawley St | Medium Mobility | IL Rte 176 | IL Rte 83/60 |
| Hawley St | Low Mobility | IL Rte 83/60 | Seymour Ave |
| Hunt Club Rd | High Mobility | IL Rte 120 | Stearns School Rd |
| Hunt Club Rd | Medium Mobility | Stearns School Rd | IL-WI State Line |
| Hutchins Rd | Low Mobility | IL Rte 132 | Stearns School Rd |

Table 3.1 Lake County Highway Access Classification Designations (Continued)

| Roadway Name | Access Classification | From | То |
|--------------------------|-----------------------|-------------------------|--------------------------|
| Kelsey Rd | Medium Mobility | IL Rte 14 | River Road |
| Kelsey Rd | Low Mobility | River Road | IL Rte 59 |
| Kenosha Rd | Medium Mobility | IL Rte 131 | Russell Rd |
| Kilbourne Rd | High Mobility | Wadsworth Rd | IL-WI State Line |
| Lake Ave | Low Mobility | IL Rte 173 | IL-WI State Line |
| Lewis Ave | Medium Mobility | Russel Rd | Sunset Ave |
| Lewis Ave | Permitted by Others | IL Rte 120/Belvidere | IL Rte 137 |
| Long Grove Rd | Low Mobility | Ela Rd | US Rte 12 |
| Martin Luther King Jr Dr | Medium Mobility | IL Rte 43 | IL Rte 131 |
| | Low Mobility | | Sheridan Rd |
| Martin Luther King Jr Dr | , | IL Rte 131 | |
| McGaw Rd | Medium Mobility | Dead End | IL Rte 43 |
| Midlothian Rd | Medium Mobility | IL Rte 176 | IL Rte 137 |
| Millburn Rd | Medium Mobility | US Rte 45 | Hunt Club Rd |
| Miller Rd | Low Mobility | Kelsey Rd | IL Rte 12 |
| Monaville Rd | Medium Mobility | IL Rte 59 | IL Rte 83 |
| Nathan Hale Dr | Low Mobility | Engle Dr | Genoa Ave |
| North Ave | Low Mobility | IL Rte 83 | Nelson Rd |
| North Ave | Medium Mobility | Nelson Rd | US Rte 45 |
| Old McHenry Rd | Medium Mobility | US Rte 12 | IL Rte 22 |
| Old McHenry Rd | Low Mobility | IL Rte 22 | IL Rte 53 |
| O'Plaine Rd | Low Mobility | Old Grand Ave | Washington Street |
| O'Plaine Rd | Medium Mobility | Washington Street | IL Rte 137 |
| Peterson Rd | Freeway | IL Rte 60 | US Rte 45 |
| Petite Lake Rd | Medium Mobility | IL Rte 59 | IL Rte 83 |
| Prairie Rd | Medium Mobility | Aptakisic Rd | IL Rte 22 |
| Quentin Rd | High Mobility | Lake Cook Rd | IL Rte 22 |
| Quentin Rd | Medium Mobility | IL Rte 22 | Old McHenry Rd |
| River Rd | Low Mobility | Kelsey Rd | Roberts Rd |
| Riverwoods Rd | Medium Mobility | Deerfield Rd | IL Rte 60 |
| Roberts Rd | Low Mobility | IL Rte 59 | McHenry-Lake County Line |
| Rollins Rd | Medium Mobility | Grand Ave | IL Rte 83 |
| Rollins Rd | High Mobility | IL Rte 83 | IL Rte 132 |
| Russell Rd | Medium Mobility | Des Plaines River Trail | IL Rte 137 |
| Saint Marys Rd | Medium Mobility | IL Rte 137 | IL Rte 60 |
| Saint Marys Rd | Low Mobility | IL Rte 60 | Everett Rd |
| Sand Lake Rd | Medium Mobility | IL Rte 132 | US Rte 45 |
| Saunders Rd | Medium Mobility | Lake Cook Rd | Deerfield Rd |
| State Park Rd | Medium Mobility | US Rte 12 | County Line |
| Sterns School Rd | Medium Mobility | US Rte 41 | US Rte 45 |
| Sunset Ave | Medium Mobility | Delany Rd | IL Rte 131 |
| Sunset Ave | Permitted by Others | IL Rte 131 | Sheridan Rd |
| Wadsworth Rd | Medium Mobility | Hunt Club Rd | Lewis Ave |
| Wadsworth Rd | Low Mobility | Lewis Ave | Sheridan Rd |
| Washington St | Medium Mobility | Cedar Lake Rd | Hainesville Rd |
| Washington St | High Mobility | Hainesville Rd | IL Rte 21 |
| Washington St | Freeway | IL Rte 21 | US Rte 41 |
| _ | High Mobility | US Rte 41 | IL Rte 131 |
| Washington St | | • | |
| Weiland Rd | Low Mobility | Lake Cook Rd | Aptakisic Rd |
| Wilson Rd | Medium Mobility | IL Rte 60 | IL Rte 134 |
| Wilson Rd | Low Mobility | IL Rte 134 | IL Rte 59 |
| Winchester Rd | Medium Mobility | IL Rte 83 | IL Rte 21 IL Rte 131 |
| York House Rd | Medium Mobility | Delany Rd | 111 U+A 1 J 1 |

CHAPTER 4 Right-of-Way Dedication

4.1 Minimum Right-of-Way Width

Minimum required right-of-way dedication widths for each access classification have been defined to reflect anticipated future needs of each roadway type. Additional right-of-way width may be required on a case by case basis, at the discretion of the County Engineer. In fully developed Urban areas where right-of-way is restricted or obtaining required right-of-way would cause significant hardship on the local economy, a variance may be requested below the minimum required right-of-way dedication widths.

Table 3.1 Required Right-of-Way by Access Classification

| Access Classification | Total Right-of-Way Width | Half Right-of-Way Width |
|-----------------------|-----------------------------|----------------------------|
| Low Mobility Road | 100 Feet | 50 Feet |
| Medium Mobility Road | 120 Feet | 60 Feet |
| High Mobility Road | 120 Feet | 60 Feet |
| Designated Freeway | 140 Feet | 70 Feet |

A minimum radius of 35 feet shall be provided at intersecting right-of-way lines. For major intersections, the minimum radius at the intersecting right-of-way lines shall be 50 feet.

4.2 Plat Approval Requirements

When right-of-way dedication is required, the Preliminary Plat should be submitted to the LCDOT as early as possible. Failure of a permit applicant to submit a Preliminary Plat prior to municipal approval does not constitute grounds for a variance under the Ordinance.

The Final Plat of Subdivision may not be approved and may not be signed by the County Engineer until all access permitting issues have been resolved and the plat of dedication has been signed and recorded.

To obtain written approval for access to a County Highway, the final plat of subdivision shall include the following signature certificate:

| STATE OF ILLINOIS) | |
|--|---|
|)SS | |
| COUNTY OF LAKE) | |
| County pursuant to 765 ILCS 205/2 et. seq. of the access to County Highway also known as from County Highway shall be restricted as sh County Highway Access Regulation Ordinance wh | , A.D., 20 by the County Engineer of Lake Illinois Compiled Statutes, as amended, as to roadway Direct access either to or nown on this plat and shall be subject to the Lake ich requires, in part, that application be made and an eer of Lake County prior to any access installation. |
| County Engineer | |

To obtain written approval for a subdivision with prohibited access to a County Highway, the final plat of subdivision shall include the following signature certificate:

| STATE OF ILLINOIS |) |
|--|---|
| |)SS |
| COUNTY OF LAKE |) |
| Engineer of Lake Coamended, as to road | pproved this day of, A.D., 20 by the County unty pursuant to 765 ILCS 205/2 et. seq. of the Illinois Compiled Statutes, as dway access to County Highway also known as Direct access either to or from County Highway is prohibited |
| as shown on this pla | it. |
| County Engineer | |
| · | oproval for access to a County Highway without a subdivision of land, the nall include the following signature certificate: |
| STATE OF ILLINOIS |) |
| |) SS |
| COUNTY OF LAKE |) |
| This dedication here | eby accepted for public road purposes this day of |
| , A.D. | , 20 |
| County Engineer | |

The plat of dedication is always used to dedicate right-of-way and shall be signed and recorded by the LCDOT prior to the signing and recording of a plat of subdivision in order to be able to provide the document number on the plat of subdivision.

CHAPTER 5 Design Standards

The design of access-related improvements shall comply with the standards and specifications set forth in the Ordinance and as defined by LCDOT. Any deviations from these specifications must be filed as a variation unless otherwise specified. In the absence of specific guidance in this Technical Reference Manual, the policies of the following various IDOT and AASHTO manuals, most recent editions of, and any supplements thereto or any successor document or documents, shall govern.

IDOT Publications

- 1. Standard Specifications for Road and Bridge Construction
- 2. Supplemental Specifications and Recurring Special Provisions
- 3. Illinois Manual on Uniform Traffic Control Devices for Streets and Highways (IMUTCD)
- 4. Bureau of Design and Environment Manual (Bureaus of Design and Programming)
- 5. Bureau of Local Roads and Streets Manual (Bureau of Local Roads and Streets)
- 6. Coded Pay Item Book (Bureau of Design and Environment)
- 7. Highway Standards Manual

AASHTO Publication

- A Policy on Geometric Design of Highways and Streets, current edition (AASHTO "Green Book")
- 2. Guide for the Development of Bicycle Facilities, current edition
- 3. Roadside Design Guide, current edition

ITE Publications

- 1. ITE Trip Generation, current edition: An ITE Informational Report
- 2. ITE Trip Generation Handbook, current edition: An ITE Recommended Practice

Lake County Publications

- 1. Lake County Highway Access and Use Ordinance
- 2. Lake County Unified Development Ordinance
- 3. Lake County Watershed Development Ordinance
- 4. Lake County Stormwater Management Commission Technical Reference Manual
- 5. Lake County Division of Transportation Plan Preparation Guidelines
- Lake County Recorder of Deeds Plat Guidelines
- 7. Design Guidance for LCDOT Traffic Plans
- 8. LCDOT Standard Details (available as dgn or pdf)
- 9. Lake County Wireless Telecommunications Ordinance
- 10. A Policy for Automated Red Light Running (RLR) Camera Traffic Enforcement Systems

General design standards for Minor Access permits and Major Access permits are summarized in Tables 5.1 and 5.2. Sections 5.1 through 5.8 provide additional detail or explanation on submittal requirements.

Table 5.1 Design Standards Matrix - Minor Access

| | Low Mobility | Medium Mobility | High Mobility | Designated Freeway | CBD/OBD |
|--|--|--|--|--|--|
| Design Speed | Posted | Posted + 5 mph | Posted + 5 mph | Posted + 5 mph | Posted |
| Sight Distance Requirements | Per AASHTO Green Book (see Section 9-5) |
| Access Design | See LC4100 |
| Angle, Grade & Length | See Section 5.2.1 |
| Throat Width | 10-24 feet |
| Maximum Flare Width (along highway pavement) | 36 feet |
| Minimum return radii | 2 feet |
| Culvert minimum diameter | 15 inches |
| Culvert extension from driveway | 4 feet |
| Mailbox turnout design | Per LC4120/LC4121 | Per LC4120/LC4121 | Not allowed | Not allowed | Per LC4120/LC4121 |
| Channelizing Islands/Medians | Per IDOT BLRS/BDE Manuals and Standards |
| Pavement Markings | Per LCDOT & IMUTCD Standards |
| Signage | Per LCDOT & IMUTCD Standards |
| Highway Improvement Design | N/A | N/A | N/A | N/A | N/A |
| Drainage Design | See Section 5.6 |
| Erosion Control and Water Quality | Per Lake County WDO |

^{*} Table presents typical minimum requirements for designer reference. Variances from these may be allowed based on site-specific conditions with appropriate written justification. See Technical Reference Manual for additional detailes and designer guidance.

CBD/OBD - Central Business District/Outlying Business District as defined in IDOT BLRS Manual 27.4 or the Lake County Framework Plan

Table 5.2 Design Standards Matrix - Major Access

| | Low Mobility | Medium Mobility | High Mobility | Designated Freeway | CBD/OBD |
|---|--|--|--|--|--|
| Design Speed | Posted | Posted + 5 mph | Posted + 5 mph | Posted + 5 mph | Posted |
| Sight Distance Requirements | Per AASHTO Green Book (see Section 9-5) |
| Access Design | See LC4101/LC4102 |
| Angle, Grade & Length | See Section 5.2.1 |
| Throat Width - Driveway | 12-35 feet | 12-35 feet | 12-35 feet | 12-35 feet | 10-35 feet |
| Throat Width - Side Road | 24-35 feet |
| Maximum Flare Width (along highway pavement) | 85 feet |
| Minimum return radii | 10 feet |
| Minimum Design Vehicle | SU | WB-50 | WB-65 | WB-65 | per expected access use |
| Channelizing Islands/Medians | Per IDOT BLRS/BDE Manuals and Standards |
| Pavement Markings | Per LCDOT & IMUTCD Standards |
| Signage | Per LCDOT & IMUTCD Standards |
| Highway Improvement Design | | | | | |
| Through Lane Widths | 11-12 feet | 11-12 feet | 11-12 feet | 12 feet | 11-12 feet |
| Right Turn Lanes | Case-by-Case evaluation | Per Table 4.3/4.4 | Per Table 4.3/4.4 | Required | Case-by-Case evaluation |
| Left Turn Lanes | Case-by-Case evaluation | Per Table 4.5/4.6/4.7 | Per Table 4.5/4.6/4.7 | Required | Case-by-Case evaluation |
| Turn Lane Storage | 125 feet (unsignalized) |
| Minimum Length | 150 feet (signalized) |
| Lane Drops | Per LCDOT & IMUTCD Standards |
| Pavement Markings | Per LCDOT & IMUTCD Standards |
| Signage | Per LCDOT & IMUTCD Standards |
| Crown (typical) | 1/4-in per foot |
| | Per LCDOT standards |
| Shoulders | (see 4000, 4001, 4010, 4011, 4020, 4021) |
| Maximum Earth Slope | 4:1 | 4:1 | 4:1 | 4:1 | 4:1 |
| Drainage Design | See Section 5.6 |
| Erosion Control and Water Quality | Per Lake County WDO |

^{*} Table presents typical minimum requirements for designer reference. Variances from these may be allowed based on site-specific conditions with appropriate written justification. See Technical Reference Manual for additional detailes and designer guidance.

CBD/OBD - Central Business District/Outlying Business District as defined in IDOT BLRS Manual 27.4 or in the Lake County Framework Plan

5.1 Sight Distance Requirements

An access point should be located at the point of maximum sight distance along a property frontage. Placement of an access in a horizontal curve along a highway or just below the high point of a crest vertical curve on a highway should be avoided.

The access must meet minimum safety requirements in accordance with the AASHTO Green Book (current edition) guidelines. Any movement for which sight distance is inadequate shall be prohibited by use of signs, pavement markings, and restrictive design features as required by the LCDOT.

Access to a property shall be denied when minimum safe sight distance cannot be attained. When access is denied, access may be allowed, at the owner's expense, in one of the following ways:

- 1. Negotiating with adjacent property owners to acquire access to the subject property through easements.
- 2. Constructing a frontage road serving the subject property and connecting with the highway where safe access can be provided.
- 3. Redesign or reconstruction of the existing highway to correct sight distance deficiency.
- 4. Additional roadway easement or right-of-way may be necessary and shall be dedicated or obtained by the owner to obtain adequate Intersection Sight Distance.

5.2 Access Design Requirements

Design of the access driveway or street intersection should follow LCDOT Design Standards, minimum requirements in Table 5.1 and 5.2, and the below specifications.

5.2.1 Access Placement, Grade, and Length

All accesses shall be constructed perpendicular to the existing roadway. The grade for any access shall slope down from the highway pavement to the ultimate right-of-way line at a rate of two percent (2%), except in a super-elevated section of highway where the grade shall match the super-elevation. No Major Access shall be located on horizontal curves where the super-elevation of the pavement exceeds three percent (3%).

The onsite storage bay for the proposed access shall be of sufficient length to store exiting or entering vehicles clear of the parking and on-site circulation area and off of the abutting highway.

5.2.2 Access Design Dimensions

The access driveway or roadway shall be designed as close as possible to the LCDOT Standard and meet minimum and maximum dimensions identified in Table 5.1 and 5.2. For large developments such as regional shopping centers, industrial complexes and large office developments, the Access Control Officer shall determine on a site-specific basis the maximum throat and flare widths for driveways.

5.2.3 Access Control

At high-volume access locations, it may be desirable to control particular maneuvers. This shall be achieved through regulatory signage and by installing channelizing islands and/or medians.

Instances where turning movements may be restricted include:

- Where numerous low-volume access points exist and the spacing between them
 does not permit adequate left-turn tapers and storage bays for inbound vehicles
 without blocking adjacent access points.
- At access points close to an intersection where inbound or outbound left turns would have to be made within areas where traffic is queued during any period of the day.
- 3. Where other conditions, such as sight distance, prevent left turns in or left turns out from being made safely.
- 4. Where a particular parcel is provided with more than one access point and volumes do not justify left-turn access into and/or from both access points, restrictions may be required at one or both access points.
- 5. When a parcel has access provided by both a signalized access point and an unsignalized access point, left turns in and left turns out may be prohibited at the unsignalized location.
- 6. When the median opening for left-turning vehicles would be too close to another median opening, left turns may be prohibited at one of the access points.

Channelizing islands and medians at access locations shall be designed to the same standards as islands and dividers installed at street intersections. These islands and medians shall not be within the County Highway right-of-way.

Signage at access locations shall be designed in accordance with MUTCD standards.

5.3 Highway Improvement Design Requirements

Where widening or improvement to the County Highway is required to mitigate impacts of the proposed access location, design of the improvements to the County Highway should follow LCDOT Design Standards, minimum requirements in Table 5.1 and 5.2, and the below specifications.

5.3.1 Through Lane Widths

The required lane width for the improvement will be based on the widths of the adjacent lanes and planned lane usage. At improvements of intersections with existing widths different from the required lane widths, the improvement will include adjusting the pavement width to accommodate the required lane widths.

5.3.2 Auxiliary Lane Requirements

The use of auxiliary lanes (both right and left turn lanes) can significantly improve safety and optimize traffic operations on County Highways. This is especially true on high volume and high speed roadways. Due to the high mobility characteristics of a Designated Freeway, right and left turn lanes shall be required for any proposed major access to a Designated Freeway.

For all other County Highways, Table 5.3 and 5.4 provide guidance for when a right turn lane will be required, and Table 5.5, 5.6 and 5.7 provide guidance for when a left turn lane will be required. Peak-Hour volumes to be used with these tables shall be projected to the date of the ultimate buildout of the development. In addition to the volume and speed characteristics, a right or left turn lane may be required in the following circumstances:

- At any intersection where a capacity analysis determines a right or left turn lane is necessary to meet level of service criteria.
- For uniformity of intersection design along the highway if other intersections have turn lanes.

At any intersection where the crash experiences, existing traffic operations, sight
distance restrictions or engineering judgement indicates a significant conflict related to
right or left turning vehicles.

For low mobility roadways (with low speed and/or low volume) and roadways in highly developed urban areas with restricted right of ways, auxiliary lanes may not be required if the benefit of the turn lane does not justify the cost. Each access request will be evaluated on a case by case basis considering the characteristics of the roadway (speed, volume, capacity, frequency of intersections, etc.) as well as the available right-of-way and service provided by the access to determine if a turn lane is warranted.

The Access Management Manual, 2nd ed., 2014 and Access Management Application Guidelines, 2016, published by the Transportation Research Board (TRB) provide frequently used recommendations and warrants for right and left turn lanes. Variations from Tables 5.3-5.7 will be considered provided the proposed design is supported by appropriate design guidelines, research, or cost-benefit analysis. Appropriate guidelines include IDOT, AASHTO, ITE and NCHRP publications. Documentation of the supporting guidelines, research, or analysis shall be submitted with the capacity analysis or traffic impact study.


Table 5.3 Right-Turn Lane Guidelines for Two-Lane Highways

| Approach | Minimum Right-turn Volume Warranting Exclusive Lane (vph) | | | | | | |
|----------------------|---|--------|--------|--------|--------|--|--|
| Lane Volume (vph) | By Posted Speed Limit | | | | | | |
| (0), | 35 mph | 40 mph | 45 mph | 50 mph | 55 mph | | |
| 200 | | | 75 | 35 | 20 | | |
| 300 | | 120 | 40 | 25 | 15 | | |
| 400 | 200 | 50 | 30 | 20 | 10 | | |
| 500 | 50 | 25 | 20 | 15 | 10 | | |
| 600 | 25 | 15 | 15 | 10 | 10 | | |
| 800 | 15 | 10 | 10 | 10 | 10 | | |
| 1200 | 10 | 10 | 10 | 10 | 10 | | |

Table 5.4 Right-Turn Lane Guidelines for Four-Lane Highways

| Approach Lane Volume | Minimum Right-turn Volume Warranting Exclusive Lane (vph) By Posted Speed Limit | | | | |
|-------------------------|--|--------|--------|--------|--------|
| (vph) | 35 mph | 40 mph | 45 mph | 50 mph | 55 mph |
| 300 | | | | 75 | 20 |
| 400 | | 40 | 40 | 40 | 15 |
| 500 | | 40 | 40 | 30 | 15 |
| 600 | 40 | 40 | 40 | 25 | 10 |
| 800 | 40 | 35 | 30 | 20 | 10 |
| 1200 | 25 | 30 | 20 | 15 | 10 |
| 1600 | 15 | 15 | 15 | 10 | 5 |
| 2000 | 10 | 10 | 10 | 10 | 5 |

Table 5.5 Left Turn Lane Guidelines for Rural Two-Lane Highways







Table 5.6 Left Turn Lane Guidelines for Rural Four-Lane Highways








Table 5.7 Left Turn Lane Guidelines for Urban and Suburban Arterials





Source: NCHRP Report 745: Left Turn Accommodations at Unsignalized Intersections, TRB 2013

5.3.3 Auxiliary Lane Storage Length

Storage length shall be determined by a capacity analysis, subject to a 125 foot minimum at an unsignalized intersection and 150 foot minimum at a signalized intersection.

5.4 Limits of Required Highway Improvements

If the limits of construction on a County Highway to provide a widening and improvement for an access falls within 250 feet of an existing widened section of County Highway, the widening and improvement required for the access shall be extended to connect with and meet the existing widened section of County Highway to maintain continuity and lane alignment.

The existing traffic operations on the County Highway shall not be negatively impacted as a result of the proposed access and related traffic. The Permittee shall be responsible for making any required improvements to existing adjacent intersections to ensure that the level of service letter grade does not decrease and that the volume to capacity ratio (v/c) does not significantly degrade as a result of a proposed development.

The following shall be analyzed for the proposed access facility and adjacent impacted intersections:

- 1. Intersection level of service (existing + site + background) shall remain the same as existing conditions.
- 2. Volume to capacity ratios for through lane groups and critical lane groups shall not exceed 0.85 (or 10% of the existing v/c ratio, not to exceed 1.0, whichever is greater).
- 3. If the existing through lane group and/or critical lane group is operating below level of service "D", allowable delays for those lane groups shall not increase more than 10%.

Limits of the improvement shall be discussed at the pre-application meeting, and shall be determined by the LCDOT.

5.5 Pavement Design for Required Highway Improvements

Pavement construction, rehabilitation or resurfacing for required highway improvements associated with an access permit shall be designed in accordance with current LCDOT standards. Guidance on typical crown, shoulder and earth slope standards is provided in Table 5.2.

When portions of existing highways are required to be widened the following requirements shall be met and indicated on the design plans:

- 1. The existing edge of pavement to be widened shall be sawcut full depth to obtain a clean vertical face. The existing paved shoulder, including the white edgeline, must be removed.
- 2. When the widening will alter through traffic travel paths, the existing pavement shall be resurfaced with a minimum thickness of 2.25 inches consisting of 0.75 inches polymerized leveling binder and 1.5 inches Hot-Mix Asphalt Surface Course of the mix design specified, to obliterate existing wheel paths and pavement markings.
- Strip Reflective Crack Control Treatment shall be installed over the joint of widened pavement.
- 4. When the highway to be improved is on the LCDOT Five-Year Highway Improvement Program as requiring an improvement, the treatment of the existing pavement shall be in accordance with the program recommendations.

For areas of pavement resurfacing, milled pavement shall be resurfaced within ten (10) calendar days.

5.6 Drainage Design

Access pavement shall drain away from the County Highway. The access shall be designed to prevent water from ponding on the access pavement, on the County Highway, or Highway right-of-way. Access-related improvements shall not impede or adversely alter area drainage.

Culvert pipes in excess of 100 feet in length shall be made of concrete storm sewer pipe. Those equal to or less than 100 feet may be of corrugated metal, subject to approval by the LCDOT. All storm sewer culvert pipe ends must include a flared end section. All flared end sections 24 inches or greater must be grated.

No private storm sewer systems shall be located within the right-of-way. Detention basins, berms, or detention outlet facilities shall not be allowed within the right-of-way of a County Highway. Proposed structure for public utilities or facilities must be identified on the plan and profile sheet by structure type, size, frame, grate or lid type, and all invert elevations. They must also include a station and offset from the centerline of survey. Proposed public utilities or facilities shall be located and designed in accordance with the Utility and Facility policies and requirements in the Ordinance and this Technical Reference Manual.

5.7 Signage and Pavement Markings

Pavement markings and raised pavement markers, in accordance with published IMUTCD and LCDOT standards shall be installed by the Permittee.

Standard signs and signage, as specified in the IMUTCD, shall be installed by the LCDOT for all access improvements/permitted work requiring signage. The type, size, and location of all traffic control signage shall be determined by the LCDOT. The Permittee shall be responsible for all costs associated with traffic control signage required for an access improvement. Upon receipt of an invoice billing from the LCDOT, the developer shall reimburse LCDOT for all costs incurred.

Any signage or pavement marking not approved by the LCDOT shall not be placed in the right-of-way of a County Highway.

5.8 Existing Survey Monuments

Existing right-of-way markers and survey monuments within the right-of-way of the County Highway that are affected by a permit project shall be replaced according to current LCDOT standards.

CHAPTER 6 Engineering Study Requirements

This chapter outlines the requirements for the Traffic Impact Study, traffic signal warrant analysis, sight distance study, soil surveys, environmental assessments and drainage study. All documents must be signed and sealed by a licensed Professional Engineer.

6.1 Traffic Impact Study Requirements

All applications for a Major Access permit shall include the submittal of a traffic impact study. In addition, any proposed variation from the provisions of the Ordinance or this Technical Reference Manual will require the submittal of a traffic impact study.

The owner shall be responsible for the costs of preparing a Traffic Impact Study and any revisions thereto. The Traffic Impact Study shall be prepared by a licensed Professional Engineer whose principal practice is traffic engineering. The Traffic Impact Study shall bear the name, signature and seal of the Professional Engineer who prepared the study. The LCDOT shall review the study, data sources, methods and findings. Revisions to the Traffic Impact Study may be required. All revisions shall be made prior to submitting a final report to the LCDOT. The LCDOT shall approve the final Traffic Impact Study prior to acceptance.

6.1.1 Traffic Impact Study Format

a. **Introduction**

The study shall include a brief description of the size of the property or development, the location, the political jurisdiction in which the development is located (including an area location map), the principal highways and roads in the site vicinity, the boundary or limits of the study area, and any other general information that would assist in the review of the development's traffic impact.

b. **Land-Uses**

Existing and proposed land-uses of the development shall be described. All land uses shall be defined. If several alternative land-uses are being proposed, the land-use that generates the most trips will govern.

c. Study Area

Traffic volumes (average daily traffic volumes and weekday AM/PM peak hour), road geometrics, intersection geometrics, and traffic control devices shall be shown or described in the site vicinity. The influence area shall be determined by the traffic generated from the site, the trip distribution of the traffic, and the trip assignment of the traffic generated by the development over the surrounding area road network. In general, the road network to be studied shall be to the next signalized intersection in each direction from the proposed access location. If no signalized intersections exist within 1 mile of the proposed access location, then the next adjacent intersections within 0.5 mile shall be analyzed. Variations to this standard study area should be discussed at the pre-application meeting and a larger study area may be required based on a site specific evaluation.

d. Peak-Hour Trip Generation Rates and Volumes

A summary table shall be prepared listing each type of proposed land-use, the size or area for each type of land-use, the average trip generation rates (both

average daily traffic volumes and weekday AM/PM peak hour of the adjacent street traffic) for each type of land-use, and total number of trips generated. The trip generation rates, both average daily traffic volumes and AM/PM peaks, shall be calculated from the latest data available contained in the Institute of Transportation Engineers' ITE <u>Trip Generation Manual</u>. Copies of pertinent equations or rates shall be included in an appendix to expedite review. The ITE Land Use Code must be included in the trip generation rates summary table.

The following are recommended guidelines on using the rates or equations provided in ITE Trip Generation based on ITE guidance:

Use regression equation when:

- Regression equation is provided
- Independent variable is within the range of data
- Data plot has at least 20 points
- $R^2 \ge 0.75$
- Equation falls within data cluster in plot
- Standard deviation > 110 percent of weighted average rate

Use weighted average rate when:

- At least 3 data points are available;
- Independent variable is within the range of data;
- Standard deviation ≤ 110 percent of weighted average rate;
- R² < 0.75 or no equation provided; and
- Weighted average rate falls within data cluster in plot.

In the event that suitable and accurate data for the proposed land use(s) is not available from the ITE Manual, other estimates may be provided, subject to approval by LCDOT. In general at least two trip generation studies shall be submitted for review. The entire study, including traffic counts, summaries, analysis and results must be submitted for review.

Mode Split: The ITE rates are based on numerous surveys taken at developments where there is no significant transit or pedestrian activity, and therefore represent 100 percent auto usage. This is an appropriate assumption for many of the developments that will be reviewed. There will be occasions, however, when some of the trips to and from the project would likely be made by another mode of transportation (e.g. transit, bicycle or walking). These trips would normally occur in populated areas where such services or facilities are available. Any assumptions regarding non-auto trips will be reviewed for reasonableness and must be well supported by documentation of the availability of transit service (board and alighting data for routes or stops), surveys of current travel behavior (census data) and/or similar relevant data.

Given the unique characteristics of certain land use types, the LCDOT may require average daily traffic volumes (24 hour traffic counts) and AM/PM peak hour traffic counts on other than a typical weekday. The existing trip generation of a proposed land use in operation out of county and out of state may be considered by the LCDOT if there are no comparable land uses within the County.

The Traffic Impact Study must be submitted within 6 months of the date the data was collected.

e. Trip Distribution

Both a figure and table shall be presented to show the directional distribution of site-generated traffic approaching and departing the site on the area road network. Different trip distribution allocations based on differing land use (residential vs. retail) may be applicable and should be used. An explanation of the rationale behind the trip distribution shall also be included.

f. Trip Assignment

The technical analysis, methods, and assumptions used in the assignment shall be clearly stated. The trip distribution and subsequent assignment shall represent the most logically traveled routes.

The trip assignment shall be developed based on the trip generation estimates and trip distribution estimate. Delay at intersections shall be taken into account in the trip assignment to ensure that the assignment represents an accurate estimate of intersection/driveway usage based on anticipated delays associated with accessing the County Highway and other heavily traveled routes (e.g. equilibrium assignment) A rationale of the assignment shall be provided to corroborate the assignment.

g. Existing and Projected Traffic Volumes

The following traffic volumes for access locations, intersections, and the area road network within the area of influence shall be provided in a graphic map format.

- 1. AM and PM weekday peak-hour existing traffic volumes within the site vicinity.
- 2. AM and PM weekday peak-hour of adjacent street traffic for the site generated traffic volumes.
- 3. AM and PM weekday peak-hour total traffic volumes.
- 4. Existing average daily traffic within the site vicinity.
- 5. Projected average daily traffic within the site vicinity.
- 6. Should the peak hour trip generation rate not occur on a weekday, a weekend peak hour must be provided, i.e. restaurant, shopping center, place of worship, and other land uses as determined by the LCDOT.

All maps of traffic volumes shall show both entering and exiting traffic at the proposed access points, as well as all turning movement volumes and through traffic at critical intersections. Total traffic refers to the background traffic plus site-generated traffic. Projected volumes are those expected at ultimate buildout of the development. Background growth shall be calculated as 3% per year, non-compounded. Pass-by trips may be considered in accordance with the ITE Trip Generation Handbook.

h. **Capacity Analyses**

Capacity analyses shall be conducted at proposed access points and impacted intersections within the traffic study area. These analyses shall follow the techniques described in the most recent edition of the <u>Highway Capacity Manual</u>.

Analyses of projected conditions shall include the effects of any committed developments other than the proposed development within the influence area. In designing an access or operation of impacted intersections, consideration must be paid to the existing and projected levels of service and the adequacy of storage for projected queue lengths. Summary tables of both Level-of-Service (LOS), queue lengths (95th percentile back of queue) shall be provided for both through movements, turning movements, and the intersection as a whole. Turn lane storage length should accommodate the 95th percentile back of que. Printed summaries of the analysis shall be included in the appendix. Any modification of default values in the analysis software must be identified and described. The rational in modifying default values must be provided.

i. Traffic Control Measures

The type and extent of existing and proposed traffic control measures shall be in conformance with the County standards. These may include, but are not limited to, signage, signalization, and pavement markings. If the County does not have a standard, current IDOT or IMUTCD standards will apply. Any proposed traffic signal control must follow the most current standards and must be compatible with existing traffic signals and ITS hardware and software.

j. Additional Highway Access

A request for additional accesses other than that allowed in the Ordinance will be considered on a case by case basis. Consideration in the analysis shall be paid to the standards set forth in this Technical Reference Manual the operation of the County Highway to which access is being requested; other forms of access including restricted access, indirect access and access to other streets or roads; signalized versus unsignalized access locations, and any other factors on which a determination can be made concerning the number of access points.

k. Required Highway Improvements

The need for additional turn lanes shall be analyzed and included in the TIS. The policy of LCDOT is that existing traffic operations shall not be negatively impacted as a result of the proposed access and related traffic. This shall be analyzed in the TIS as follows for proposed access facilities and adjacent impacted intersection:

- 1. Intersection Level-of-Service (existing + site + background) shall remain the same as existing conditions.
- 2. Volume-to-Capacity ratios for through lane groups and critical lane groups shall not exceed 0.85 (or the existing v/c for that lane group) whichever is greater.)
- 3. If the existing through lane group and/or critical lane group is operating below LOS "D", allowable delays for that lane group shall not increase more than 10%.

<u>Proposed Traffic Signals:</u> In addition to the above requirements for Required Highway Improvements:

- 1. Intersection LOS must be "D" or better (existing + site + background).
- If the signal is to be part of an interconnected or adaptive system, an appropriate traffic signal system analysis must be performed. Througharterial 90th percentile green-band (existing + site) must not decrease more than 15%. Both HCM-based and simulation-based capacity and queuing analysis shall be submitted.

<u>Proposed Modifications to Existing Traffic Signals:</u> In addition to the requirements above:

- 1. Intersection LOS must be "D" or better (existing + site + background).
- 2. Through movement lane group LOS shall not decrease.
- 3. If the signal is to be part of an interconnected or adaptive system, an appropriate traffic signal system analysis must be performed. Througharterial 90th percentile green-band (existing + site) must not decrease more than 15%. Both HCM-based and simulation-based capacity and queuing analysis shall be submitted.

k. Conclusions and Recommendations

A clear, concise description of the findings shall be presented. These findings shall include all improvements for the proposed access location, intersections, and the area road network as required per the Ordinance. The recommendations shall be limited to the improvements as required under the Ordinance or this Technical Reference Manual.

6.1.2 Improvements Based on Traffic Impact Study

All highway improvements recommended in the findings of the Traffic Impact Study that are a direct result of the proposed development shall be constructed or caused to be constructed by the owner. The total costs for these improvements shall be borne solely by the owner.

6.2 Traffic Signal Warrant Analysis

6.2.1 Warrants

Traffic signals shall only be installed if the warrants established by the IMUTCD are met. A Traffic Signal Warrant Analysis shall be prepared to determine if signalization warrants are met. In addition to the provisions required in Section 6.1.1, the Traffic Signal Warrant Analysis shall clearly demonstrate that the traffic signal will not impede coordinated traffic flow, result in undue delay, or impair traffic operations or safety.

A traffic signal may be installed, as part of the permitted access-related improvements, if the projected traffic generated by development would meet the warrants established by the IMUTCD. This must be documented as part of a Traffic Signal Warrant Analysis.

Satisfying traffic signal warrants does not guarantee that a traffic signal may be installed. The County Engineer shall make the final determination if traffic signals are to be installed.

A new traffic signal should not be located any closer to an existing traffic signal than one-quarter (1/4) mile.

6.2.2 Traffic Signal Costs

All costs associated with a traffic signal installation shall be the sole responsibility of the permittee. Prior to the issuance of an access permit with a traffic signal, the County shall prepare a formal joint agreement with the Local Agency. The joint agreement shall delineate the responsibilities of the County and the responsibilities of the Local Agency. The responsibilities of the Local Agency shall include, but not be limited to, paying, or causing to be paid, all perpetual costs for the energy and maintenance of a traffic signal; paying, or causing to be paid, all costs for any future upgrading, revisions, modifications, and/or modernizations; providing the County with indemnification; and meeting other provisions related to the traffic signal maintenance. The ownership of a traffic signal shall rest with the County. If a traffic signal is required to be a part of an interconnected traffic signal system, the permittee shall also be responsible for all costs associated with the interconnection as part of the traffic signal installation.

6.2.3 Intersection Design Study (IDS)

An IDS shall be required for any of the following: any new traffic signal, when auxiliary lanes are added to an existing signalized intersection, and for an existing signalized intersection when less than one-half (1/2) mile from a new traffic signal. An IDS shall be prepared as outlined in IDOT's Bureau of Design and Environment Manual.

An IDS shall also be required for any existing signalized intersection when a new signal is to be interconnected to the existing traffic signals.

6.3 Sight Distance Study Analysis

A Sight Distance Study is required for all Major Access locations and in those instances when the Access Control Officer determines any access location may not meet sight distance requirements. When a Sight Distance Study is required, the study shall include the following:

- 1. The study shall be prepared on a 22 inch by 34 inch sheet size
- 2. The stationing of the sight distance study shall be the same as the original construction plans for those highways the LCDOT originally constructed or as provided.
- 3. The study must be prepared on a plan and profile sheet at a horizontal scale of 1 inch = 50 feet.
- 4. The location of the driver's eye shall be 15 feet from the proposed pavement edge and shall be 3.5 feet above the pavement edge at the proposed access location.
- 5. Based upon the intersection sight distance, the location of the object height (approaching vehicle) must be shown on the plan view. The location of the object height (approaching vehicle) shall be 3.5 feet above the center of the traffic lane and must be shown on the profile view.
- 6. The intersection sight distance must be shown on both the plan and profile views.

The sight distance study shall show all appurtenances within the sight triangle such as, but not limited to trees, large signs and utility poles.

6.4 Soil Surveys

For a Major access, soil surveys shall be conducted in accordance with the IDOT Geotechnical Manual, prior to the completion of the final engineering plans and specifications to determine the existence of unsatisfactory subgrade materials or the need for remedial underground drainage. Soil surveys shall be

required when widening an existing pavement by six (6) feet or more. The results of the soil survey shall be submitted to the LCDOT for review.

6.5 Environmental Assessment

The owner shall provide any and all environmental subsurface investigation reports that were conducted for all properties adjacent to the County Highway right-of-way. In those instances where LCDOT has valid concerns that environmental conditions exist and remediation may be needed, the Access Control Officer may require that an environmental assessment be conducted. All environmental conditions shall be remediated prior to the dedication and acceptance of any right-of-way that is required by the Ordinance.

6.6 Drainage Study

Drainage for access-related, utility or facility improvements shall be designed in accordance with the requirements of the IDOT Bureau of Local Roads and Streets Design Manual and the Lake County Watershed Development Ordinance and the "Guide to the Hydraulic Design of Bridges and Culverts on Local Systems" and any amendments thereto or successor document or documents. A drainage study shall be submitted for LCDOT review and shall include, but not be limited to, the following:

- 1. U.S.G.S. Topographic Map delineating the site and the boundaries and area of all watershed and subwatershed areas affecting the site.
- 2. Drainage plan of the site delineating existing and proposed watershed and subwatershed areas; proposed drainage facilities; and design volumes and velocities of all structures, systems, and ditches.
- 3. Computations supporting the design of all proposed facilities, including, but not limited to, drainage areas, runoff coefficients, frequencies, volumes, velocities, methods of design, and others, as required.

The design of the on-site detention facilities shall include detention required for the highway widening impervious areas of any access -related improvements.

CHAPTER 7 Utility and Facility Permit Requirements

The construction, maintenance and restoration methods and procedures, materials used, construction and maintenance signing, and traffic control for all utility and facility work shall conform to and be in compliance with all Lake County Division of Transportation standards and requirements set forth in the most recent editions, successor documents to and any supplements or revisions to "The Illinois Manual on Uniform Traffic Control Devices for Streets and Highways," "Standard Specifications for Road and Bridge Construction," "Supplemental Specifications and Recurring Special Provisions," "the Bureau of Local Roads and Streets Manual," and the "Highway Standards" manual as published by or adopted by the Illinois Department of Transportation and any supplements thereto.

7.1 Revisions

The LCDOT may require revisions to the work permitted under this Ordinance due to unforeseen field conditions, errors or omissions in the plans, drawings, sketches and/or highway maintenance or safety problems which become apparent during construction, use or maintenance of the utility or facility, or by inspection made by the County Engineer or his authorized agents and representatives. These revisions must be made on the plan sheets and submitted and approved by the County Engineer prior to their implementation.

7.2 Location of Utilities and Facilities

The location, either above ground level, at ground level or below ground level, of a utility or facility shall be as determined by the LCDOT. The location of the utility or facility shall be no closer than thirty-six (36) feet from the centerline of the right-of-way and a minimum of four (4) feet deep except storm sewer unless the Applicant can demonstrate good and sufficient cause to locate closer than thirty-six (36) feet from the centerline of the right-of-way. Convenience and costs shall not be grounds for good and sufficient cause. Storm sewer systems shall be located outside the pavement and curbline.

No utility or facility may be located within five (5) feet of the back of any curb or within any clear zone as established in Figure 38-3.A of the IDOT Bureau of Design and Environment Manual unless approved by the County Engineer. Any new or relocated utility poles must be located within one foot of the right-ofway line. Any new or relocated fire hydrants must be located within two feet of the right-of-way line.

7.3 Drainage and Access

Disturbed drainage facilities and drainageways shall be re-established at the end of each workday and upon completion of the permitted work permitted. No drainage facility or drainageway shall be blocked or altered in any manner or form.

Convenient access shall be maintained for those abutting properties which take access to a County Highway. In the event the access is to be disrupted, the occupants of the abutting properties shall be given three (3) days advance written notice and access shall be maintained or re-established as soon as possible.

7.4 Excavations, Trenches and Bore Pits

Any excavated materials shall be piled on the near approach traffic side of the excavation, trench, or bore pit, but excavated material shall not be placed on the pavement or gravel shoulder. Open excavations, trenches or bore pits remaining after working hours shall not exceed fifty (50) feet in length and shall be properly protected and marked. No open pit shall be open longer than 48 hours. Should

the pit remain open after forty-eight (48) hours, it may be filled in by the LCDOT Maintenance Department at the permittee's expense.

Bore pits shall be located no closer than ten (10) feet to the highway pavement, back of curb or shoulder break, whichever is further. If casing pipes are used, voids in the casing pipe shall be filled and the ends sealed.

The areas disturbed by excavation work shall be kept to a minimum and proper erosion control measures and water quality measures shall be used per the approved engineering plans. Rough grading work shall begin after backfilling operations have been completed. This rough grading shall include reestablishing the highway shoulders, ditchlines and sideslopes so the drainage of the right-of-way is maintained. For larger projects, rough grading work shall be done as the areas of the project are backfilled. Settlement of rough graded areas shall immediately be filled in to prevent hazards or damage to the right-of-way.

7.5 Open Cut of Pavements

Open cuts of the roadway pavement, disturbance of or removal of any curb and gutter, or impacting any other roadway facility for the placement, location or construction of a utility or facility are prohibited except that open cuts may be permitted when existing utilities or facilities are underneath the existing pavement provided there is no other alternative to service or to maintain the utility or facility.

The County Engineer may authorize an open cut and the issued permit shall set forth the terms and conditions of the open cut which shall include, among other terms and conditions, payment of the open cut charge. No open cuts shall be permitted between November 15 and April 15 unless the Applicant can demonstrate good and sufficient cause. Convenience and cost shall not be grounds for good and sufficient cause. Unforeseen emergencies may constitute good and sufficient cause for an open cut of an existing payement between November 15 and April 15.

7.6 Crossings

All crossings of County Highways for any underground utility or facility shall be at right angles or as near thereto as practicable.

All pavement crossings should be enclosed in a casing pipe made of steel, HDPE, PVC or ductile iron, which will extend a minimum of ten (10) feet beyond the edge of pavement, back of curb, or shoulder break, whichever is further. Each crossing requires a specified amount added to the performance guarantee, to ensure the integrity of the highway pavement. Said amount shall be determined by the County Engineer.

The material selected for the crossing must allow for trenchless installation (i.e. boring, directional drilling) which minimizes impact to the pavement, both during installation and for future maintenance. The LCDOT may determine on a case by case basis whether the casing pipe can be omitted or a material other than those listed above can be used for a casing pipe provided good and sufficient reasons are presented to the County Engineer in writing by the owner of the utility or facility. However, cost savings shall not be the sole reason for a request to omit the casing pipe or use a material other than steel, HDPE, PVC or ductile iron for the casing pipe.

Casing pipe for a proposed utility or facility crossing may be installed by a party other than the utility or facility owner to be located inside the casing provided said utility or facility owner has signed the appropriate Acceptance Form acknowledging responsibility, ownership and maintenance of said casing pipe and that the appropriate permit has been issued.

Casing pipe or utilities installed with non-metallic materials such as PVC or HDPE shall be installed with an accompanying metallic tape to facilitate locating.

7.7 Berms and Earth Filling

No permanent berm or berming, in whole or in part, shall be allowed on or within the right-of-way of a County Highway.

No permanent earth filling of any type or nature shall be allowed on or within the right-of-way of a County Highway.

No berm or earth filling located outside the right-of-way of a County Highway shall alter or change in any manner or form any existing drainageways that will adversely affect the existing drainage of a County Highway.

The toe of any berm or earth filling shall not be located within ten (10) feet of the right-of-way line of a County Highway without receipt of a permit.

The toe of any berm or earth filling designed to detain water shall not be located nearer to the right-of-way of a County Highway than ten (10) feet plus one and one-half (1½) times the depth of the earth excavation, detention or retention basin as measured from the bottom of the basin to the top of berm without receipt of a permit.

7.8 Detention/Retention Facilities/Earth Excavation

No detention or retention basins shall be allowed on or within the right-of-way of a County Highway unless said detention or retention basins are constructed as a highway appurtenance to a County Highway.

No earth excavation, detention or retention basin shall be located at a distance closer than ten (10) feet plus one and one half (1 $\frac{1}{2}$) times the depth of the earth excavation, detention or retention basin from the right-of-way line of a County Highway without receipt of a permit.

7.9 Traffic Control Devices

Any existing traffic control device removed due to construction and restoration work shall be reset as that area is restored. Regulatory and warning devices shall at all times be kept in clear and unobstructed view of the public using the right-of-way. The permittee shall be responsible for the cost of any damaged or lost devices and for the cost of resetting any devices.

7.10 Field Locate

A field locate by field staking the location of the proposed utility or facility may be required prior to engineering plan approval.

7.11 Sidewalk and Bicycle Path Installation

Sidewalks shall be located within one (1) foot of the right-of-way line or in accordance with IDOT standards. Bicycle paths shall be located within two (2) feet of the right-of-way line or in accordance with IDOT standards. Bicycle paths shall also be in accordance with the AASHTO "Guide for the Development of Bicycle Facilities, latest edition" and applicable LCDOT standards. Accessible ramps in compliance with the Americans with Disabilities Act (ADA) shall be provided at all intersections per the IDOT standards. No County storm sewer appurtenances shall be located underneath the sidewalk or bicycle path. Any requests for allowing County storm sewer appurtenances to remain under the proposed sidewalk or bicycle path will be considered on a case by case basis. The County Highway stationing shall be used for all references to the sidewalk or bicycle path.

CHAPTER 8 Access Permit Special Requirements

8.1 Emergency Access

Requests for a gated access facility for the sole use of emergency response providers will be reviewed and approved under the Minimum Access process. Due to the unique nature of this type of access, special conditions and additional information may be required at the request of LCDOT.

The Applicant for an emergency access must be a municipality, township or fire district. Emergency access driveways shall be gated with a locking mechanism and shall be designed to discourage use by unauthorized vehicles. The gates and other related appurtenances shall be located outside of the County Highway right-of-way. This access shall be removed at the request of the County Engineer, at no cost to the County, if its intended use is violated or deemed no longer necessary.

8.2 Use of Temporary Access

The Temporary Access shall not be used to access, construct or occupy any home(s) or building(s) within a development unless specifically authorized in writing by the Access Control Officer. The Temporary Access shall not be used to access and occupy any home or building within a development in lieu of the internal access being constructed.

8.3 Temporary Access Maintenance

The permittee is responsible for installation and continued maintenance of a temporary access. Failure to maintain the Temporary Access to the satisfaction of the LCDOT may result in revocation of the permit and removal of the access. Maintenance of the Temporary Access includes keeping the County Highway pavements free of mud, dirt, dust or debris may result in revocation of the permit and removal of the access.

All Temporary Access locations shall be removed by the expiration date indicated on the permit and all disturbed areas of the highway right-of-way restored to a pre-construction condition or better, unless the Temporary Access is replaced with a Major Access. In the event the LCDOT determines that the permittee is using the Temporary Access for purposes, or for a period of time, not in conformance with the Ordinance or conditions that were part of the permit, the LCDOT may require removal of the Temporary Access. Failure by the permittee to remove a permitted Temporary Access after the expiration date of the permit, or upon notice by the LCDOT that the access is not in conformance with the permit, is a violation of the Ordinance and may result in assessment of fines.

CHAPTER 9 Engineering Plans, Specification, and Cost Estimates

9.1 Engineering Plan and Specification Requirements

Engineering plans and specifications for both access-related and utility or facility permits shall include the following:

1. The engineering plans shall be prepared on a 22 inch by 34 inch sheet size.

2. Cover Sheet:

- a. The following information should be displayed on the cover sheet: index of sheets; a location map; the stationing and length of the improvement; the name, address, and telephone number of the engineer who prepared the plans; the seal of the preparing engineer with the engineer's signature affixed over the seal; the name of the development or project; the name and address of the owner; the date of plans and subsequent revision dates; legend; general notes and specifications; summary of quantities (work items shall conform to the pay items established by the IDOT and used by the LCDOT as contained in the Standard Specifications and Coded Pay Item books); and any other general information required.
- b. The following note shall be placed on the cover sheet of the final plans: "The review and approval of these final engineering plans and specifications by the Lake County Division of Transportation does not constitute a release from or grant of variation from the standards and specifications required in the Lake County Highway Access and Use Ordinance, latest edition. The permittee, the permittee's designated representatives, and/or all successors and assigns shall be solely responsible for all work and improvements within the limits of the County Highway right-of-way. Unless otherwise specified, approved in writing by the Lake County County Engineer, and on file with the Lake County Division of Transportation, all work and materials necessary to perform work within the limits of the County Highway right-of-way shall be in conformance with the provisions and requirements of the Lake County Highway Access and Use Ordinance, latest edition."
- 3. The following General Notes shall be added to the coversheet or typical section sheet of the engineering plans:
 - The construction, including materials used, of this improvement shall be in accordance with the applicable portions of the most recent editions of the "Standard Specifications for Road and Bridge Construction," "Supplemental Specifications and Recurring Special Provisions," and the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways," including all amendments and successor documents to the aforementioned documents as published or adopted by the Illinois Department of Transportation and/or LCDOT unless otherwise stated in these engineering plans.
 - The construction of the improvements shall also be in accordance with the "Lake County Highway Access and Use Ordinance," latest edition.
 - The Lake County Division of Transportation shall not be held liable for any errors or omissions in these engineering plans or for any additional work, which may be needed due to errors or omissions in these engineering plans.

- The permittee shall be responsible for any additional work, and all costs thereof, required because of errors or omissions in these engineering plans and for the correction of any construction, maintenance, or safety problems, which become apparent during construction or by inspections made by the Resident Engineer or the Lake County Division of Transportation.
- Pavement Smoothness for Bituminous Pavements:
 - 1. The following smoothness requirements shall apply to the surface course:
 - For mainline traffic lanes the pavement surface shall not vary more than ¼ inch in a 10-foot distance as measured along the wheel path.
 - For turning lanes, including by-pass lanes, the pavement surface shall not vary more than ¼ inch in a 10-foot distance as measured along the wheel path.
 - 2. In order to satisfy the above smoothness requirements for a pavement overlay, the existing pavement may need leveling binder or cold milling in order to provide a proper base for the bituminous binder course. The Resident Engineer shall determine if leveling binder or cold milling will be necessary.
 - 3. The Lake County Division of Transportation shall require, at its discretion, the testing of the pavement for smoothness. For any such testing, the bituminous contractor shall provide construction signing and two flaggers. A representative of the bituminous contractor and the Resident Engineer (or representative) shall be present during testing. Any pavement areas that do not pass the above smoothness requirements shall be removed by the grinding method to a 2 inch minimum depth and resurfaced with Hot-Mix Asphalt Surface Course of the mix design specified.

FOR ACCESS PERMITS ONLY

- The Resident Engineer shall be responsible for establishing the proper lines and grades
 for all construction work including earthwork, paving, curbing and drainage. The
 Resident Engineer shall also be responsible for all other engineering work including
 inspections and any testing required by the Lake County Division of Transportation. An
 inspector, as provided or approved by the Resident Engineer, shall be present during
 critical phases of the construction work.
- The Resident Engineer shall note any changes from these engineering plans and shall notify the Permit Department of the Lake County Division of Transportation about any changes that deviate from the intent of the engineering plans such as changes in drainage, geometric plan, or grading work.
- The Lake County Division of Transportation "Special Conditions for Construction within a County Highway Right-of-Way" shall be included in the engineering plans.

FOR UTILITY OR FACILITY PERMITS ONLY

- The person in charge shall note any changes from these engineering plans and shall notify the Permit Department of the Lake County Division of Transportation about any changes that deviate from the intent of the engineering plans.
- 4. Complete detailed construction plans shall be prepared on plan and profile sheets at a horizontal scale of 1 inch equals 20 feet and a vertical scale of 1 inch equals 5 feet. The stationing of the engineering plans shall be the same as the original construction plans for those highways the LCDOT originally constructed or as provided. The following items must be shown on the plan and profile sheets:

- pavement widths and lane use (existing and proposed)
- drainage (existing and proposed)
- right-of-way and property lines (existing and proposed)
- survey monuments
- utilities and facilities (existing and proposed)
- adjustment to utilities and facilities
- topography i.e. driveways, intersections, shoulders, trees, bush lines, fences, berms, detention ponds adjacent to the right-of-way line
- elevations and grades, drainage systems, culverts and inverts (existing and proposed)
- ditch flow lines

The plan and profile sheets shall show all existing trees within the right-of-way along with their diameter. Trees within the right-of-way to remain shall be protected. Trees to be removed as a result of work in the right-of-way for the access improvements shall be labeled for removal and replacement trees may be planted on the development site in accordance with the tree requirements of the municipality in which the project develops for all trees 6" (six inches) in diameter or greater. The municipality must submit a Municipal Acceptance Form for any trees planted within the County Highway right-of-way as per the Ordinance.

- 5. Cross section sheets are required for all engineering plans. The cross sections shall be taken at 50-foot intervals and additional cross sections taken at the centerline of the proposed access, all existing cross road culverts, intersecting streets, and all single family driveways. The cross sections shall be shown at a scale of 1 inch equals 5 feet vertically and 1 inch equals 5 feet or 1 inch equals 10 feet horizontally. Half cross sections are required from the centerline to the right-of-way on the side in which work is being done, for work impacting only one side. The following items must be shown on the cross sections:
 - existing County Highway pavement
 - existing shoulder, ditches, ditch slopes and drainage
 - existing topography, utility poles, trees, fences
 - proposed pavement widening and shoulders, ditches and drainage
 - existing and proposed right-of-way lines
 - utilities and facilities (existing and proposed)
 - inverts of storm sewers, culverts and ditch lines
 - slope rates for proposed slopes
- 6. The pavement marking sheet is required when the intersection improvement requires changes to the existing pavement markings. Existing pavement markings shall be shown 300 feet beyond the end of the proposed pavement markings. The pavement marking detail shall be at a scale of 1 inch equals 50 feet. The sheet shall also include the pavement marking specifications for thermoplastic for HMA pavements, Modified Urethane for PCC pavements and the summary of quantities. If existing pavement markings are grooved, proposed pavement markings shall be grooved.
- For access permits, a site plan of the entire development drawn at a scale of 1 inch equals 100 feet showing the layout of the site, the drainage of the site, the grading of the site and utilities on the site is required.

- 8. A detailed traffic control plan (if applicable) to be implemented during construction, including but not limited to road closure, temporary runaround and detouring traffic.
- 9. A detour plan prepared in accordance with LCDOT Detour Procedures and Guidelines (if applicable) which includes the detour route with the location of all appropriate signs, a "typical intersection at point of detour" detail, and a schedule of quantities for all signs. If the proposed detour requires use of IDOT or other agency roadways, approval from the IDOT Detour Committee or appropriate jurisdictional agency is required.
- 10. A detour information signs sheet (if applicable) which includes the LCDOT Detour General Notes, details of pre-detour information signs used for advance notification, installation locations by intersections, and general layout at intersections for the pre-detour information signs.
- 11. Traffic Signal Plan sheets should be included when traffic signal equipment will be impacted by the work, including cable plan and sequence, interconnect plan and schematic, fiber splicing schematic and cabinet detail sheets.
- 12. A traffic control details sheet with the following items should be included: copies of the current Illinois Department of Transportation construction signing standards from the Highway Standards Manual and/or Part VI of the Manual of Uniform Traffic Control Devices and/or Lake County Traffic Control Devices that apply to the project's construction.
- 13. Traffic signal sheets shall be in accordance with the LCDOT Traffic Signal Design Guidelines.
- 14. A detail sheet or multiple detail sheets including the LCDOT and IDOT Highway Standards should be included. Details shall be provided for all applicable items including, but not limited to, drainage structures and curb and gutter. Details should be placed on sheets such that they can be read at 11x17 print size.
- 15. An erosion control plan as per the Watershed Development Ordinance requirements.

Any revisions to engineering plans required by the LCDOT shall be made prior to acceptance of final engineering plans and specifications. Upon completion of all revisions, the County Engineer shall approve the final engineering plans, specifications, and estimate of cost.

9.2 Estimate of Cost

A detailed estimate of cost, if required, shall be prepared by a licensed Professional Engineer. The estimate of cost shall be based on unit prices for individual work items. The minimum amount for unit prices for individual work items shall be the average amount for the unit prices for individual work items as paid for by the LCDOT for the previous twelve (12) month period for County Highway improvements. Work items shall conform to the pay items established by IDOT and as used by the LCDOT as contained in the Standard Specifications and Coded Pay Item books. For utility or facility work, each crossing under the County Highway requires a specified amount added to the cost estimate, to ensure the integrity of the highway pavement; said amount shall be determined by the County Engineer. All changes and revisions shall be made as required by the LCDOT prior to acceptance and approval by the LCDOT. Design and Construction Engineering Supervision shall be seventeen percent (17%) of the total estimate of cost. Traffic Control shall be 5% of the total estimate of cost or a minimum amount as set by the County Engineer.

9.3 Location Map or Drawing Requirements

Aerial utility work shall require a map or drawing that contains County Highway stationing. The drawing shall show, but not be limited to, the right-of-way, location and station of existing utility poles, proposed alignment of the installation, and it shall identify the beginning and ending station of the project.

Single service connection or disconnection work shall require a drawing that contains County Highway stationing. The drawing shall show, but not be limited to, the right-of-way, County highway pavement and shoulders, proposed alignment of the installation or removal, and distance to the nearest cross street.

9.4 As-Built Drawing Requirements

The following items shall be noted and/or included on all as-built plans and must be certified by the engineer of record as being correct and complete prior to final field inspection for approval of performance guarantee release.

Utility or Underground Improvements

- All manholes, vaults, pedestals, utility poles or other similar facilities on main lines must be numbered and their locations tied to two above ground permanent structures. As-built elevations must be provided.
- All ducts, pipes, cables or other raceways must be identified by diameter, material type, and color
 and any bends or tees must be tied to two permanent above ground structures. The actual asbuilt elevations at key locations (bends, crossings, etc.) shall be shown as well as any points where
 the elevations change.
- All service lines must be identified by diameter, material type and color, and location of connection to the main and exit from right of way from two building corners or other permanent above-ground structures.

All Other Improvements

- Property corners are not acceptable as permanent structures for improvement location measurements.
- Extension of building lines are not acceptable for location measurements.
- All recorded easements shall be shown and copies of all recorded easements shall be submitted.
- Any changes to the permitted lines and elevations of all facilities must be shown on the as-built drawings. This includes driveways, pavement, sidewalks, drainage structure locations, light poles, traffic signals, or any other permanent structure.
- Drawings may be submitted as legible, professionally scanned copies of full size project plans that
 have all changes, additions, and deletions tagged by clouds or similar easy to see markings in red
 ink. As an alternate electronic CAD files may also be submitted with and changes, additions, and
 deletions tagged by clouds or similar easy to see markings.

CHAPTER 10 Performance and Maintenance Guarantee, and Insurance Requirements

The Lake County Highway Access and Use Ordinance outlines the requirements for performance and maintenance guarantees and the requirement of the Lake County Division of Transportation to obtain a Certificate of Insurance prior to the issuance of a permit for work within the County Highway right-ofway.

Along with the submittal of the Performance Guarantee is a letter designating the Professional Engineer who will serve as the Resident Engineer if required. Prior to the release of any guarantee, certification by the Resident Engineer or the Person in Charge of the project's completion is required. The recommended format for both the project initiation and project completion letters are included in this section.

10.1 Additional Insured Endorsements

The Lake County Division of Transportation, and its officers, agents and employees, shall be designated as an additional insured in the Commercial General Liability Policies. The Additional Insured endorsement must be approved by the County Engineer, or a person designated by the County Engineer. The endorsement must demonstrate that the endorsement has been bound by the insurance company. Examples of Additional Insured endorsements are provided at the end of this chapter.

10.2 General Insurance Conditions for all Required Policies

The permittee and its contractors shall purchase all forms of insurance from a company licensed in the State of Illinois, with an A.M. Best's Rating of at least A-Class VIII. The insurance will protect the permittee from claims which may result from the permittee's operations under the permit and for which the permittee may be legally liable, whether by the permittee, contractor, subcontractor, anyone directly or indirectly employed by, or for anyone for whose acts any of them may be liable.

Any deductible and/or self-insured retention shall be the responsibility of the permittee.

10.3 Workman's Compensation Insurance

The Certificate of Insurance shall include Workman's Compensation, or satisfactory evidence that this liability is otherwise in accordance with Section 4. (a) of the "Workman's Compensation Act of the State of Illinois". This coverage shall be maintained until all work under the terms of the permit has been completed and accepted. Maintenance of the insurance or other protection is part of the permit until final acceptance by the LCDOT. Failure to maintain such insurance which results in lack of protection under the "Workman's Compensation Act" will result in the revocation of the permit.

10.4 Employer's Liability

The Certificate of Insurance shall include "Employer's Liability Insurance" to respond to claims because of bodily injury, occupational sickness or disease or death of the permittee's employees. This coverage shall be maintained until all work under the terms of the permit has been completed and accepted.

10.5 Commercial General Liability Insurance

The permittee shall maintain commercial general liability (C.G.L.) insurance on an occurrence basis. The Lake County Risk Management Department may determine what forms are acceptable. No restrictive endorsements pertaining to premises/operations insurance, contractual liability insurance, products and

completed operations insurance or independent contractor's coverage may apply. The policy should respond to claims for damages because of "Bodily Injury" including death, "Property Damage," "Ongoing Operations," "Completed Operations" "Personal Injury" and "Advertising Injury."

This coverage shall be maintained until all work under the terms of the permit has been completed and accepted. In addition, the permittee shall continue to carry "Complete Operations" liability insurance for at least twenty-four (24) months after the construction is complete. The permittee shall furnish the LCDOT evidence of such insurance at completion of construction and again one year after its acceptance by the LCDOT.

The Lake County Division of Transportation and its officers, agents and employees; Lake County and its officers, agents and employees shall be named as additional insureds. This insurance shall be written on an occurrence basis. The permittee's insurance shall be primary and non-contributory. The policy shall contain the standard Separation of Insureds condition and shall be endorsed to allow the General Aggregate Limit under LIMITS OF INSURANCE of the policy to apply separately to each project and each location.

10.6 Automobile Liability

The permittee shall maintain business auto liability insurance. The policy should respond to claims for damages because of bodily injury, death of a person or property damage arising out of the ownership, maintenance, or use of a motor vehicle. The policy shall contain the standard Severability of Interests provisions. This policy shall be written to cover any auto whether owned, leased, hired, or borrowed. This coverage shall be maintained until all work under the terms of the permit has been completed and accepted.

10.7 Minimum Limits of Liability

The Permittee's general liability insurance automobile liability insurance and employer's liability insurance shall have the minimum limits of insurance:

General Liability Insurance:

Access Permits:

Minimum Access Proof of insurance
 Minor Access Proof of insurance

3. Major Access Projects which exceed \$50,000 in construction cost: \$500,000

Projects which exceed \$1M in construction cost: \$2,000,000

4. Designated Freeway Projects which exceed \$50,000 in construction cost: \$500,000

Projects which exceed \$1M in construction cost: \$2,000,000

5. Temporary access Proof of insurance

Right-of-way Use Permits:

1. Special Event Proof of insurance

2. Utility \$2,000,000

3. Facility Projects which exceed \$50,000 in construction cost: \$500,000

Projects which exceed \$1M in construction cost: \$2,000,000

4. Single service connection Proof of insurance

Employer's Liability Insurance:

| Bodily Injury by Accident (Each Accident) | \$1,000,000 |
|---|-------------|
| Bodily Injury by Disease (Each Employee) | \$1,000,000 |
| Bodily Injury by Disease (Policy Limit) | \$1,000,000 |

Automobile Liability Insurance:

Bodily Injury, Property Damage and
Covered Pollution Cost or Expense (Each Occurrence Limit) \$1,000,000

10.8 Self-Insurance

Any self-insured organization seeking a permit under the Ordinance must meet or exceed the requirements of the Illinois Department of Insurance and the Illinois statute(s) for self-insurers. Qualified legal counsel must provide a provision to be inserted within any self-insured documents and/or trust, which provides that the protection afforded the Lake County Division of Transportation, its officers, agents and employees and Lake County, its officers, agents and employees will be the equivalent of the insurance protection required of those organizations which do purchase the required insurance coverages.

LCDOT is not obligated to accept self-insurance by an organization in lieu of any or all of the insurance policies or coverages delineated above. The decision to accept or reject an organization's self-insurance shall be made solely and exclusively by the County Engineer at the County Engineer's discretion.

10.9 Sample Insurance, Bond and Guarantee Forms

The following sample forms have been provided for reference:

- Insurance Certificate
- Access Permit Performance Bond
- Access Permit Maintenance Guarantee (Letter of Credit)
- Access Permit Performance Guarantee (Letter of Credit)
- Utility/Facility Performance Bond
- Utility/Facility Performance Guarantee (Letter of Credit)

| AC | ORD, CERTIFIC | ATE OF LIAE | BILITY INS | URANCE | | DATE (MM/DD/YYYY) | | |
|---------------------------|---|---|--|---|---|---------------------------------------|--|--|
| PRODUCE | R | | ONLY ANI HOLDER. | D CONFERS N | UED AS A MATTER (O RIGHTS UPON T ATE DOES NOT AME AFFORDED BY THE P | HE CERTIFICATE | | |
| | | | INSURERS A | FFORDING COV | ERAGE | NAIC# | | |
| INSURED | | | INSURER A: | | | | | |
| | | | INSURER B: | | · | | | |
| • | | | INSURER C: | | | | | |
| | | | INSURER D: | | | · · · · · · · · · · · · · · · · · · · | | |
| | | | INSURER E: | | | | | |
| COVER | | | | | | | | |
| ANY R MAY PI POLICI | DLICIES OF INSURANCE LISTED BELC EQUIREMENT, TERM OR CONDITION ERTAIN, THE INSURANCE AFFORDED ES. AGGREGATE LIMITS SHOWN MAY | OF ANY CONTRACT OR OT BY THE POLICIES DESCRIB | HER DOCUMENT WITH ED HEREIN IS SUBJECT AID CLAIMS. | H RESPECT TO WH T TO ALL THE TERI | HICH THIS CERTIFICATE | MAY BE ISSUED OR | | |
| INSR ADD'L LTR INSRE | | POLICY NUMBER | POLICY EFFECTIVE DATE (MM/DD/YY) | POLICY EXPIRATION DATE (MM/DD/YY) | LIMI | TS | | |
| | GENERAL LIABILITY | | | | EACH OCCURRENCE | \$ | | |
| | COMMERCIAL GENERAL LIABILITY | | | | DAMAGE TO RENTED PREMISES (Ea occurence) | \$ | | |
| | CLAIMS MADE OCCUR | | | | MED EXP (Any one person) | \$ | | |
| | | | | | RSONAL & ADV INJURY | \$ | | |
| | | | | | GENERAL AGGREGATE | \$ | | |
| | GEN'L AGGREGATE LIMIT APPLIES PER: | | M | | CODUCTS - COMP/OP AGG | \$ | | |
| | POLICY . PRO- JECT LOC | | | | | | | |
| | AUTOMOBILE LIABILITY ANY AUTO | | - | | COMBINED SINGLE LIMIT (Ea accident) | \$ | | |
| | ALL OWNED AUTOS SCHEDULED AUTOS | * | · | <u>:</u> | BODILY INJURY (Per person) | \$ | | |
| | HIRED AUTOS NON-OWNED AUTOS | | 1 | | BODILY INJURY (Per accident) | \$ | | |
| | | | | · | PROPERTY DAMAGE (Per accident) | \$ | | |
| | GARAGE LIABILITY | | | | AUTO ONLY - EA ACCIDENT | \$ | | |
| | ANY AUTO | | | | OTHER THAN EA ACC | \$ | | |
| | | | | | AUTO ONLY: AGG | \$ | | |
| | EXCESS/UMBRELLA LIABILITY | | | | EACH OCCURRENCE | \$ | | |
| | OCCUR CLAIMS MADE | | | | AGGREGATE | \$ | | |
| | | | | ! | | \$ | | |
| | DEDUCTIBLE | • | | | | \$ | | |
| | RETENTION \$ | | | | | \$ | | |
| | KERS COMPENSATION AND | | | | WC STATU- OTH- TORY LIMITS ER | | | |
| | LOYERS' LIABILITY PROPRIETOR/PARTNER/EXECUTIVE | | | | E.L. EACH ACCIDENT | \$ | | |
| OFFI | CER/MEMBER EXCLUDED? | | | | E.L. DISEASE - EA EMPLOYEE | \$ | | |
| SPE | CIAL PROVISIONS below | | | | . DISEASE - POLICY LIMIT | \$ | | |
| ОТН | ER | Jai | | ノして | | | | |
| DESCRIPTI | ON OF OPERATIONS / LOCATIONS / VEHICLES | S / EYC! IISIONS ADDED BY ENDOD | SEMENT/SPECIAL DENAME | ONS | | | | |
| DESCRIPTI | ON OF OPERATIONS / LOCATIONS / VEHICLES | STEXCEUSIONS ADDED BY ENDOR | SEMENT/SPECIAL PEDVISI | ONS | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | • . | | | | |
| | | | | | | | | |
| CERTIF | ICATE HOLDER | | CANCELLAT | ION | | | | |
| CERTIF | ICATE HOLDER | 7 | CANCELLAT | | | | | |
| | | | SHOULD ANY OF | THE ABOVE DESCRIB | ED POLICIES BE CANCELLED | 30 | | |
| | | | | | ER WILL ENDEAVOR TO MAIL | | | |
| | | • | I | | NAMED TO THE LEFT, BUT F | | | |
| | | | I | IMPOSE NO OBLIGATION OR LIABILITY OF ANY KIND UPON THE INSURER, ITS AGENTS OR | | | | |
| | | | REPRESENTATIV | | | | | |
| | , | | - Section in the last of the l | | | | | |

IMPORTANT

If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must be endorsed. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

DISCLAIMER

The Certificate of Insurance on the reverse side of this form does not constitute a contract between the issuing insurer(s), authorized representative or producer, and the certificate holder, nor does it affirmatively or negatively amend, extend or alter the coverage afforded by the policies listed thereon.

Highway Access Performance Bond # (SURETY COMPANY LETTERHEAD)

| Attention: | Lake County Division of Transportation County Engineer |
|------------------|--|
| | 600 Winchester Road |
| | Libertyville, IL 60048 |
| | Elberty vine, 12 00040 |
| Beneficiary: | Lake County Treasurer |
| Re: [Project | Namel |
| . , | ess Permit No. |
| | |
| Amount: | |
| Maturity Date | ə: |
| · | |
| | |
| KNOW BY | ALL MEN BY THE PRE EN S, what we [full name and address] as |
| Principal and | f [full name and addiد عن الله عن الله الله الله الله الله الله الله الل |
| | y of Lake ("t' County") in the punal sum of |
| Dollars (|) for he rymen of which sum, well and truly to be made, we bind |
| ourselves, ou | ur heirs, exectors actinistrators and successors, jointly and severally, firmly |
| by these pres | se is, aid an unt to include payment of actual costs and damages and for |
| | , architectura fees, design fees, engineering fees, accounting fees, testing |
| fees, consult | l. 😘 🗻, at nir strative costs, court costs, interest and any other fees and |
| expenses re | esulting from or incurred by reason of Principal's failure to promptly and |
| | form complete the work more fully described below, and to include |
| | es, court costs and administrative and other expenses necessarily paid or |
| incurred in su | uccessfully enforcing performance of the obligation of Surety under this bond. |
| | |
| | THE PRINCIPAL hereby does covenant and agree to insure the completion of |
| | provements and other related work (the "Improvements") as required by and in |
| | e with the Lake County Highway Access Regulation Ordinance, Chapter 90 of |
| | unty Code of Ordinances, the approved engineering plans and specifications |
| for that proje | ect, and Highway Access Permit No |
| NOW THE O | CONDITION OF THE ADOVE OR LOATION IS SHOULD AT A STATE OF THE PRINCIPAL |
| | CONDITION OF THE ABOVE OBLIGATION IS SUCH that if said PRINCIPAL, |
| | entatives or assigns shall truly and promptly complete the Improvements in |
| | with the Lake County Highway Access Regulation Ordinance, Chapter 90 of |
| the Lake Col | unty Code of Ordinances, the approved engineering plans and specifications |
| | project, and Highway Access Permit No, on or |
| | (two years from the date hereof) and shall indemnify |
| | armless the County against all claims for damages on account of the |
| | of said Improvements, and also against all costs and expenses which may be |
| • | he County of account of such claims, then the above obligation is to be null |
| | of the deing of and of the having performed and/or causing to be performed |
| | of the doing of and of the having performed and/or causing to be performed and things herein before set forth. |
| נווס ווומנוטוס מ | 3110 UHINGS HELEHI DEIDIE SEUIDIUI. |

| In the event the PRINCIPAL fails to construct the manner specified in the Lake County Highw 90 of the Lake County Code of Ordinances specifications, or Highway Access Permit No. Principal that the Improvements are unaccept corrective measures within seven (7) calendar of Improvements are unacceptable and complicational time, not to exceed fifteen (15) calendar corrective measures within such seven (7) corrective measures within such seven (7) corrective measures within such fifteen (15 responsible for commencement and completion reasonable time, not to exceed thirty (30) calendar seven the Surety of PRINICPAL's failure to commence within thirty (30) calendar days from the draw commence corrective measures, in which commence within thirty (30) calendar days from the draw commence corrective measures, in which commence by County in undertaking corrective measures billing. Moreover, notwithstanding anything to the County determines in its semiglication at welfare of the public or other energy necession corrective work notifying the PRIN CIPAL as so does not remit paymen to be County for such (15) calendar days of the data obtaining, Surety seven (7) command days at the date of notification corrective work has been completed. | ay Access Regulation Ordinance, Chapter s, the approved engineering plans and, the County shall notify the table. The PRINCIPAL shall commence days after notification by the County that the ete such corrective measures within a endar days from the time County notifies ptable. If PRINICIPAL fails to commence calendar day period, or complete such calendar day period. Surety shall be on of such conjective measures within a dar days from the one the County notifies the or to complete such corrective measures of notice, County shall have the right to Survey shall be contrary in this paragraph, in the event at imminent threat to the health, safety, or the County may immediately commence on thereafter as practical. If PRINCIPAL emergency corrective work within fifteen a shall remit payment to the County within |
|---|--|
| Signed, sealed and do.ed this day | y of, 20 |
| ATTEST: | PRINCIPAL: |
| BY: | BY: |
| TITLE: | TITLE: |
| ATTEST: | SURETY: |
| BY: | BY: |
| TITLE: | TITLE: |

FORM DOT HIGHWAY ACCESS MAINTENANCE LETTER OF CREDIT

(FINANCIAL HOUSE LETTERHEAD)

| , |
|---|
| Irrevocable Letter of Credit No |
| Re: [Project Name] |
| LCDOT Access Permit No |
| Amount: |
| Expiration Date: |
| |
| Treasurer, County of Lake |
| Attention: Lake County Division of Transportation |
| County Engineer |
| 600 Winchester Road |
| Libertyville, IL 60048 |
| |
| Gentlemen: |
| |
| We hereby establish our irrevocable creating the amount of (specify amount |
| |
| (\$) in favor of the it asult: County of Lake, Illinois, on behalf of |
| (applicant name) d/b (nan 3) . We understand that (applican |
| name) d/b/a (name) has completed the access improvement work |
| within the right-of-way of County lighw #, locally known as, and that |
| this irrevocable credit so be used to insure that all access improvements and other |
| related work completed per prisway Access Permit No are maintained in |
| a satisfactory condition setermined by the Lake County Division of Transportation. |
| |
| This irrevo tible crassistished by us shall be in force until and shall be inforce until |
| remain in example without regard to any default in payment of sums owed by the owner |
| and/or applicant and vahout regard to other claims which we may have against the owner |
| and/or applicant. |
| TI : |
| This irrevocable credit shall in no event expire until 60 days after written notification of |

This irrevocable credit shall in no event expire until 60 days after written notification of such expiration has been given by the issuing bank to the County Engineer by way of certified mail.

This Letter of Credit may be drawn upon by the Lake County Engineer at any time in the event that the above-described improvements are not being satisfactorily maintained in accordance with the Lake County Highway Access Regulation Ordinance, Chapter 90 of the Lake County Code of Ordinances, and the highway access permit. A written statement, signed by the County Engineer, in substantially the same form as that attached hereto as Exhibit "A", stating that the access improvements and other related work are not being satisfactorily maintained shall be deemed a sufficient request to draw on this Letter of Credit.

| All drafts hereunder | must be marked | d, "Drawn on | (name c | of financial house) |
|-----------------------|------------------|--------------|------------------|---------------------|
| Letter of Credit No | | and shall be | substantially in | the form attached |
| hereto as Exhibit "B" | . All drafts mus | t be drawn o | n or before the | expiration date of |
| | | | | |

EXCEPT AS EXPRESSLY PROVIDED OTHERWISE IN THIS LETTER OF CREDIT, THIS LETTER OF CREDIT IS SUBJECT TO THE "UNIFORM CUSTOMS AND PRACTICE FOR DOCUMENTARY CREDITS 2007 REVISION, INTERNATIONAL CHAMBER OF COMMERCE BROCHURE NO. 600" (THE "UNIFORM RULES") IN THE EVENT OF A CONFLICT BETWEEN THIS LETTER OF CREDIT AND THE UNIFORM RULES, THIS LETTER OF CREDIT SHALL CONTROL.

We hereby agree that drafts drawn under and in compliance with the terms of this Letter of Credit shall be honored no later than the close of the seventh bruking day following presentment. If, within seven banking days after the drawn under this Letter of Credit is presented to us in conformance with the trans on his butter of Credit, we fail to honor same, we agree to pay all reasonable attentions of his butter of Credit, we fail to honor same, we agree to pay all reasonable attentions of his butter of Credit, we fail to honor same, we agree to pay all reasonable attentions of his butter of Credit, we fail to honor same, we agree to pay all reasonable attentions of his butter of Credit, we fail to honor same, we agree to pay all reasonable attentions of his butter of Credit, we fail to honor same, we agree to pay all reasonable attentions of his butter of Credit, we fail to honor same, we agree to pay all reasonable attentions of his butter of Credit, we fail to honor same, we agree to pay all reasonable attentions of his butter of Credit, we fail to honor same, we agree to pay all reasonable attentions of his butter of Credit, we fail to honor same, we agree to pay all reasonable attentions of his butter of Credit, we fail to honor same, we agree to pay all reasonable attentions of his butter of Credit, we fail to honor same, we agree to pay all reasonable attentions of his butter of Credit has been determined by the County of Lake in enforcing the honor has been determined by the County of Lake in enforcing the honor has been determined by the County of Lake in enforcing the honor has been determined by the County of Lake in enforcing the honor has been determined by the County of Lake in enforcing the honor has been determined by the County of Lake in enforcing the honor has been determined by the County of Lake in enforcing the honor has been determined by the county of Lake in enforcing the honor has been determined by the county of Lake in enforcement has been determined by the county of Lake in enforcem

| /e. truly ours, |
|------------------------------|
| Signature of Bank Officer |
| Printed Name of Bank Officer |
| Officer's Title |

EXHIBIT "A"FORM DEMAND LETTER

(DOT Letterhead) (Date)

| To: [Financial Institution Name and Address] |
|--|
| Attention: [Financial Institution Officer] |
| Re: (Financial Institution Name) Irrevocable Letter of Credit No Expiration Date: (Project name) LCDOT Access Permit No |
| "Drawn on (Financial Lystitution Nan. |
| Letter of Credit No" |
| Dear Sir or Madam: |
| This is a demand for payment, dragon <u>ancial institution name</u>) Letter of Credit No of \$ United to as Do are. |
| This demand is made in co. So. noce with the conditions specified in the credit, to wit: |
| We understand the |
| * * * |
| [The] Letter of Credit may be drawn upon by the Lake County Engineer at any time in the event that the above-described improvements are not being satisfactorily maintained in accordance with the Lake County Highway Access Regulation Ordinance, Chapter 90 of the Lake County Code of Ordinances, and the highway access permit. |

The aforementioned access improvements and other related work are not being satisfactorily maintained.

Pursuant to the terms of the Letter of Credit, this demand for payment shall be honored no later than the close of the seventh banking day following receipt of this demand for payment.

The draft shall be payable to "Treasurer, County of Like" and delivered to the County Engineer, Lake County Division of Transportation, 600 (inches er Road, Libertyville, Illinois, 60048.

Since. ly,

County Engineer County of Lake Lake County Vision of Transportation

EXHIBIT "B"

FORM SIGHT DRAFT

[NAME OF FINANCIAL HOUSE]
IRREVOCABLE LETTER OF CREDIT NO.

| IRREVOCABLE I | LETTER OF CREDIT NO |
|--|--|
| • | SIGHT DRAFT |
| DRAWN ON [NAME OF FINANCIAL H | OUSE] LETTER OF CP 2DIT NO |
| \$ | [<u>DRA.</u> ' <u>D</u> A- <u>'</u> _] |
| AT SIGHT PAY TO THE ORDER OF T [DOLLAR AMOUNT OF DRAW] AND (US\$). | T LASU ER, OLVITY OF LAKE, ILLINOIS /100 JNITEL STATES DOLLARS |
| | COUNTY ENGINEER, COUNTY OF LAKE LAKE COUNTY DIVISION OF TRANSPORTATION |
| TO: [FINANCIAL HOUSE NAME AN | [print name of County Engineer] D ADDRESS1 |

Rev 12/1/15

FORM DOT HIGHWAY ACCESS LETTER OF CREDIT

(FINANCIAL HOUSE LETTERHEAD)

| | Irrevocable Letter of Credit No |
|-----------------|---|
| | Re: [Project Name] |
| | LCDOT Access Permit No |
| | Amount: |
| | Expiration Date: |
| Transurar C | County of Lake |
| | Lake County Division of Transportation |
| Attention. | County Engineer |
| | 600 Winchester Road |
| | Libertyville, IL 60048 |
| | |
| Gentlemen: | |
| | |
| We hereby e | establish our irrevocable and it is the amount or(specify amount) |
| | |
| (\$ |) in faver f the Tree sure. County of Lake, Illinois, on behalf of |
| (applicant na | <u>ame)</u> . We understand that this irrevocable |
| credit is to be | e used to incre that II ac ss improvements and other related work proposed |
| | half of (a plice nan) for (location) , |
| Transportetion | name en in ering plans as approved by the Lake County Division of |
| project | on and with the terms of the highway access permit throughout the term of the completion of all access improvements and other related work as |
| | the Late County Highway Access Regulation Ordinance, Chapter 90 of the |
| | ue of Ordinances, the approved engineering plans and specifications for |
| | and Highway Access Permit No |
| p. 0,000, | |
| This irrevoca | able credit established by us shall be in force until and shall |
| | fect without regard to any default in payment of sums owed by the owner |
| and/or applic | cant and without regard to other claims which we may have against the owner |
| and/or applic | cant. |
| | |
| This irrevoca | able credit shall in no event expire until 60 days after written notification of such |

This irrevocable credit shall in no event expire until 60 days after written notification of such expiration has been given by the issuing bank to the County Engineer by way of certified mail.

This Letter of Credit may be drawn upon by the Lake County Engineer at any time in the event that the above-described improvements are not being satisfactorily implemented in accordance with the Lake County Highway Access Regulation Ordinance, Chapter 90 of the Lake County Code of Ordinances, and the highway access permit. This Letter of Credit may also be drawn upon in the event that the above-described improvements have not been completed within the times set out in the time schedule provided in Section 90.226, of the Lake County Highway Access Regulation Ordinance, Chapter 90 of the Lake County Code of Ordinances, and the highway access permit. A written statement, signed by the County Engineer, in substantially the same form as that attached hereto as Exhibit "A",

stating that the proposed access improvements and other related work are not being satisfactorily implemented and/or have not been completed within the time set out in said time schedule as approved by the Lake County Division of Transportation shall be deemed a sufficient request to draw on this Letter of Credit.

| All drafts her | eunder | must b | e mark | ed, " | Drawn o | on | <u>(na</u> | me of fir | <u>iancia</u> | <u>al house) </u> | Le | etter |
|----------------|--------|--------|--------|-------|-----------|------|------------|------------|---------------|--|--------|-------|
| of Credit No. | | | " a | nd s | hall be s | ubst | tanti | ally in th | e forr | m attached | hereto | as |
| Exhibit "B". | All | drafts | must | be | drawn | on | or | before | the | expiration | date | of |
| | | _ | | | | | | | | | | |

EXCEPT AS EXPRESSLY PROVIDED OTHERWISE IN THIS LETTER OF CREDIT, THIS LETTER OF CREDIT IS SUBJECT TO THE "UNIFORM CUS". MS AND PRACTICE FOR DOCUMENTARY CREDITS 2007 REVISION, INTERNAL ON/2 CHAMBER OF COMMERCE BROCHURE NO. 600" (THE "UNIFORM RULES"). IN THE EVENT OF A CONFLICT BETWEEN THIS LETTER OF CONTROL

We hereby agree that drafts drawn upder and it compliance with the terms of this Letter of Credit shall be honored no later that the case of the seventh banking day following presentment. If, within seven banking day after any draft drawn under this Letter of Credit is presented to us in conformation with the terms of this Letter of Credit, we fail to honor same, we agree to pay all reactions a torneys' fees, court costs and other expenses incurred by the Country of Lake in informing the terms hereof.

| Very truly yours, |
|------------------------------|
| Signature of Bank Officer |
| Printed Name of Bank Officer |
| Officer's Title |

EXHIBIT "A" FORM DEMAND LETTER

(DOT Letterhead) (Date)

| To: [Financial Institution Name and Address] Attention: [Financial Institution Officer] |
|---|
| Re: (Financial Institution Name) Irrevocable Letter of Credit No Expiration Date: (Project name) LCDOT Access Permit No |
| "Drawn on <u>(Financial Institution Name,</u> Letter of Credit No" |
| Dear Sir or Madam: |
| This is a demand for payment, drawn on (the provided institution name) Letter of Credit No of \$ United State Done's. |
| This demand is made in com, see wit the conditions specified in the credit, to wit: |
| [T]his irremocable credit is to be used to insure that all access improvem into and other related work proposed by, or on behalf of appliance name), for (location), comply with the expering cans as approved by the Lake County Division of a ransportation and with the terms of the highway access perfecting but the term of the project, and to insure the completion of all access improvements and other related work as required by the Lake County Highway Access Regulation Ordinance, Chapter 90 of the Lake County Code of Ordinances, the approved engineering plans and specifications for that project, and Highway Access Permit No. |
| * * * |

[The] Letter of Credit may be drawn upon by the Lake County Engineer at any time in the event that the above-described improvements are not being satisfactorily implemented in accordance with the Lake County Highway Access Regulation Ordinance and the highway access permit. This Letter of Credit may also be drawn upon in the event that the above-described improvements have not been completed within the times set out in the time schedule provided in Section 90.226 of the Lake County Highway Access Regulation Ordinance, Chapter 90 of the Lake County Code of Ordinances, and the highway access permit.

The aforementioned access improvements and other related work are not being satisfactorily implemented and/or have not been completed within the time set out in the aforementioned time schedule.

Pursuant to the terms of the Letter of Credit, this demand for payment shall be honored no later than the close of the seventh banking day following receipt of this demand for payment.

The draft shall be payable to "Treasurer, County of Lake" and delivered to the County Engineer, Lake County Division of Transportation, 600 Witchester Road, Libertyville, Illinois, 60048.

Sincerely,

Cour / Diving of Transportation

EXHIBIT "B"

FORM SIGHT DRAFT

[NAME OF FINANCIAL HOUSE]
IRREVOCABLE LETTER OF CREDIT NO.

| TAKE VOONBEE EE | THER OF GREEN NO. |
|---|--|
| SIG | SHT DRAFT |
| DRAWN ON [NAME OF FINANCIAL HO | DUSE] LETTER OF CAEDIT NO |
| \$ | [DK_W_P(E) |
| AT SIGHT PAY TO THE ORDER OF TE [DOLLAR AMOUNT OF DRAW] AND (US\$). | REASURE: COUNTY O. LAKE, ILLINOIS /16 |
| | COUNTY ENGINEER, COUNTY OF LAKE LAKE COUNTY DIVISION OF TRANSPORTATION |
| | [print name of County Engineer] |
| TO: [FINANCIA LA ISL NAME AND | O ADDRESS] |

Rev 12/01/15

DOT Highway Right-of-Way Performance Bond # (SURETY COMPANY LETTERHEAD)

| Attention: | Lake County Division of Transportation County Engineer 600 Winchester Road Libertyville, IL 60048 |
|---|---|
| Beneficiary: | Lake County Treasurer |
| Re: [Project LCDOT High | Name] way Permit No |
| Amount: | |
| Maturity Date | e: |
| Principal and of the County Dollars (ourselves, or by these presattorneys' fee fees, consult expenses refaithfully per attorneys' feincurred in su WHEREAS, said work an Highway rightake County Chapter 91 of the county of the | ALL MEN BY THESE PRESENT what we [full name and address] as [full name and address] as Surjety are field and fully bound unto the People of Lake ("the County") in the field such and truly to be made, we bind in heirs, executors, admin to tors and successors, jointly and severally, firmly sents, said amount to include, however, a design fees engineering fees, accounting fees, testing ing fees, administrative lost, court costs, interest and any other fees and sulting from or incurved by reason of Principal's failure to promptly and form and complete the work more fully described below, and to include est, court costs and an inistrative and other expenses necessarily paid or accounting performance of the obligation of Surety under this bond. THE KINCIPAL hereby does covenant and agree to insure the completion of decomplete restoration of any damaged or disturbed portions of the County at-of to the "Improvements") as required by and in conformance with the Highway Temporary Closure and Utility and Facility Placement Ordinance, for that project, and Highway Permit No |
| heirs, repres accordance Placement O engineering | ONDITION OF THE ABOVE OBLIGATION IS SUCH that if said PRINCIPAL, entatives or assigns shall truly and promptly complete the Improvements in with the Lake County Highway Temporary Closure and Utility and Facility rdinance, Chapter 91 of the Lake County Code of Ordinances, the approved plans and specifications for that project, and Highway Permit No, on or before (eighteen (18) months from the and shall indemnify and save harmless the County against all claims for |
| damages on and expense | and shall indemnify and save harmless the County against all claims for account of the prosecution of said Improvements, and also against all costs s which may be incurred by the County of account of such claims, then the tion is to be null and void and of no further force and effect, otherwise to |

remain in full force and effect for the purpose of the doing of and of the having performed and/or causing to be performed the matters and things herein before set forth.

In the event the PRINCIPAL fails to construct the Improvements in accordance with, or in the manner specified in the Lake County Highway Temporary Closure and Utility and Facility Placement Ordinance, Chapter 91 of the Lake County Code of Ordinances, the approved engineering plans and specifications, or Highway Permit No. County shall notify the Principal that the Improvements are unacceptable. The PRINCIPAL shall commence corrective measures within seven (7) calendar hays after notification by the County that the Improvements are unacceptable and Implete such corrective measures within a reasonable time, not to exceed fifteen (15 calendar days from the time County notifies PRINCIPAL that the Improvements are unaccentante. If PRINICIPAL fails to commence corrective measures within such seven (7) calend 1 day paid, or complete such corrective measures within such fifteen (15) alendar day and, Surety shall be responsible for commencement and completion of sch corrective measures within a reasonable time, not to exceed thirty (30) calculated lays, rom the time the County notifies the Surety of PRINICPAL's failure to complence coto coursete such work, as the case may be. In the event Surety fails to commence and complete such corrective measures within thirty (30) calendar days from dat of notice, County shall have the right to commence corrective measures, in which ase a rety shall pay County all costs incurred by County in undertaking corrective measure, within seven (7) calendar days of the date of billing. Moreover, notwithstand, an other contrary in this paragraph, in the event the County determines in its sole coren that an imminent threat to the health, safety, or welfare of the public or the emergency exists, the County may immediately commence corrective work notifying he F NCIPAL as soon thereafter as practical. If PRINCIPAL does not remit payment to the County for such emergency corrective work within fifteen (15) calendar lays of the late of billing, Surety shall remit payment to the County within seven (7) caendar of he date of notification by the County that such emergency corrective work as been completed.

| Signed, sealed and Lated this | _ day of, 20 |
|-------------------------------|--------------|
| ATTEST: | PRINCIPAL: |
| BY: | BY: |
| TITLE: | TITLE: |
| ATTEST: | SURETY: |
| BY: | BY: |
| TITLE: | TITLE: |

FORM DOT HIGHWAY RIGHT-OF-WAY LETTER OF CREDIT

(FINANCIAL HOUSE LETTERHEAD)

| | Irrevocable Letter of Credit No |
|-----------------|--|
| | Re: [Project Name] |
| | LCDOT Highway Permit No |
| | Amount: |
| | Expiration Date: |
| Treasurer, Co | ounty of Lake |
| Attention: | · |
| | County Engineer |
| | 600 Winchester Road |
| | Libertyville, IL 60048 |
| | |
| Gentlemen: | |
| | |
| We hereby e | stablish our irrevocable credit in the stablish our irrev |
| Š | |
| (\$ |) in favor of the Tre surer County of Lake, Illinois, on behalf of |
| (applicant na | me) d/b/a (na). We understand that this irrevocable |
| credit is to be | me) <u>d/b/a (na s)</u> . We understand that this irrevocable used to insure that all v b. prop sed by, or on behalf of <u>(applicant name)</u> |
| | for (location), is performed in compliance with the plans as approved to the Late County Division of Transportation and with the highway permit to oug out the term of the project, and to insure the |
| engineering p | plans as approved to the Latte County Division of Transportation and with the |
| terms of the | the term of the project, and to insure the |
| completion of | f said work and complete restoration of any damaged or disturbed portions of |
| | nighway rig t-or as equired by the Lake County Highway Temporary |
| | Utility and Facility Placement Ordinance, Chapter 91 of the Lake County Code |
| | es and approod engineering plans and specifications for that project, and |
| Highway Per | nit No |
| | |
| | ble credit e .ablished by us shall be in force until and shall |
| | fect regard to any default in payment of sums owed by the owner |
| | ant and without regard to other claims which we may have against the owner |
| and/or applic | ant. |
| | |

This irrevocable credit shall in no event expire until 60 days after written notification of such expiration has been given by the issuing bank to the County Engineer by way of certified mail.

This Letter of Credit may be drawn upon by the Lake County Engineer at any time in the event that the above-described work or restoration is not being satisfactorily implemented in accordance with the Lake County Highway Temporary Closure and Utility and Facility Placement Ordinance, Chapter 91 of the Lake County Code of Ordinances, and the highway permit. This Letter of Credit may also be drawn upon in the event that the above-described work or restoration has not been completed within the times set out in the time schedule provided in Chapter 91, Section 91.095 to 91.108, of the Lake County Highway Temporary Closure and Utility and Facility Placement Ordinance, Chapter 91 of the Lake County Code of Ordinances, and the highway permit. A written statement, signed by the

County Engineer, in substantially the same form as that attached hereto as Exhibit "A", stating that the proposed work or restoration is not being satisfactorily implemented and/or has not been completed within the time set out in said time schedule as approved by the Lake County Division of Transportation shall be deemed a sufficient request to draw on this Letter of Credit.

| | d, "Drawn on <u>(na é of fir ncial house)</u> Letter |
|-------------------------------------|--|
| | d shall be substantially in the form attached hereto as |
| Exhibit "B". All drafts must be | be drawn on or before the expiration date of |
| · | |
| | |
| | EDOT IEN VISE NITH 3 LETTER OF CREDIT, THIS |
| | TO THE "UN FORM DISTOMS AND PRACTICE FOR |
| | 7 NOTERNATIONAL CHAMBER OF |
| | (THL UNIFORM RULES"). IN THE EVENT OF A |
| | TO FOR EDIT AND THE UNIFORM RULES, THIS |
| LETTER OF CREDIT SHALL CONT | |
| Me benefit and that drafts of the | Use and in second longer with the terms of this Letter of |
| | and in compliance with the terms of this Letter of |
| | han the close of the seventh banking day following |
| | g days after any draft drawn under this Letter of Credit with the terms of this Letter of Credit, we fail to honor |
| | able attorneys' fees, court costs and other expenses |
| incurred by the County of Lake in e | |
| incurred by the extension of | moroling the terms hereen |
| | Very truly yours, |
| | - , , , , , , , , , , , , , , , , , , , |
| | |
| | Signature of Bank Officer |
| | |
| | |
| | Printed Name of Bank Officer |
| | |
| | Officer's Title |
| | |

EXHIBIT A" FORM DEMAND LETTER

(DOT Letterhead) (Date)

| To: [Financial Institution Name and Address] |
|--|
| Attention: [Financial Institution Officer] |
| Re: (Financial Institution Name) Irrevocable Letter of Crost No. |
| Expiration Date: |
| (Project name) |
| LCDOT Highway Permit No |
| "Drawn on (Financia mst. tion lame" |
| Letter of C dit No" |
| |
| Dear Sir or Madam: |
| This is a demand for paymentwn on <u>fine cial institution name)</u> Letter of Credit No |
| of \$ Unit 15 tes Pollars. |
| σι ψ στιπ. το τος youars. |
| This demand is made in the conditions specified in the credit, to wit: |
| [Tlb: irrevolute creat is to be used to insure that all work |
| oposed by, on behalf of (applicant name), for (location), is |
| performance with the engineering plans as |
| approved by the Lake County Division of Transportation and |
| the terms of the highway permit throughout the term of the |
| project, and to insure the completion of said work and |
| complete restoration of any damaged or disturbed portions of |
| the County highway right-of-way as required by the Lake |
| County Highway Temporary Closure and Utility and Facility |
| Placement Ordinance, Chapter 91 of the Lake County Code of |
| Ordinances, the approved engineering plans and specifications |
| for that project, and Highway Permit No |

[The] Letter of Credit may be drawn upon by the Lake County Engineer at any time in the event that the above-described work or restoration is not being satisfactorily implemented in accordance with the Lake County Highway Temporary Closure and Utility and Facility Placement Ordinance, Chapter 91 of the Lake County Code of Ordinances, and the highway permit. This Letter of Credit may also be drawn upon in the event that the above-described work or restoration has not been completed within the times set out in the time schedule provided in Chapter 91 of the Lake County Highway Temporary Closure and Utility and Facility Placement

Ordinance, Chapter 91 of the Lake County Code of Ordinances, and the highway permit.

The aforementioned work or restoration is not being satisfactorily implemented and/or has not been completed within the time set out in the aforementioned time schedule.

Pursuant to the terms of the Letter of Credit, this demand for payment shall be honored no later than the close of the seventh banking day following receipt of this demand for payment.

The draft shall be payable to "Treasurer, County of Lake and elivered to the County Engineer, Lake County Division of Transportation, 600 Wing ester Fluad, Libertyville, Illinois 60048.

Since

Sunty Figineer, County of Lake
Lai County Division of Transportation

EXHIBIT "B"

FORM SIGHT DRAFT

[NAME OF FINANCIAL HOUSE]
IRREVOCABLE LETTER OF CREDIT NO. ____

| SIC | SHT DRAFT |
|--------------------------------------|--|
| DRAWN ON <u>[NAME OF FINANCIAL H</u> | DUSE] LETTER OF CK 'DIT N' |
| \$ | 'DRAW DATÉ] |
| DOLLAR AMOUNT OF DRAW] AND | READUPLA, COUNTY OF LAKE, ILLINOIS /10. INITED STATES DOLLARS |
| (US\$). | |
| | COUNTY ENGINEER, COUNTY OF LAKE LAKE COUNTY DIVISION OF TRANSPORTATION |
| | [print name of County Engineer] |

TO: [FINANCIAL HOUSE NAME AND ADDRESS]

CHAPTER 11 Fee Schedule

ACCESS PERMIT FEES

Revised November 10, 2015 Effective December 1, 2015

MINOR AND MINIMUM ACCESS PERMITS

The following fees shall be required for each Minor Access and shall be submitted along with the access application:

- Application Fee for a private driveway to one (1) single family residence or one (1) field entrance: \$150.00
- Application Fee for all other Minor Access Permits\$450.00

All fees are non-refundable.

MAJOR ACCESS PERMIT

The following fees shall be required for each Major Access and are payable upon submittal of the first engineering plan for review:

- Application Fee (no highway improvement required)\$1,500.00
- Application Fee (highway improvement required)\$4,500.00
- Traffic Signal Fee:\$1,500.00

The Traffic Signal fee is applicable to a new traffic signal installation or other access related modification to an existing traffic signal and shall be in addition to the Major Access Permit Application Fee.

All fees are non-refundable.

DESIGNATED FREEWAY ACCESS PERMIT

The following fees shall be required for each Designated Freeway Access:

- Application Fee (no highway improvement required)\$2,400.00
- Application Fee (highway improvement required)\$5,400.00

All fees are non-refundable.

TEMPORARY ACCESS PERMIT

A Temporary Access can be either a Minor Access or a Major Access.

The following fees shall be required for each Temporary Access:

| • | Application Fee for a private driveway to one (1) single family residence or |
|---|--|
| | one (1) field entrance:\$600.00 |

• Application Fee for other access types:\$1,050.00

All fees are non-refundable.

VARIATION

The following fees shall be required for each Variation:

| • | Each Variation in relation to a Minor Access: | \$150.00 |
|---|---|----------|
|---|---|----------|

• Each Variation in relation to a Major Access:\$1,500.00

All fees are non-refundable.

FINAL INSPECTION

The following fees shall be required for a Final Inspection:

| • | First Final Inspection for the release of the | |
|---|---|--------|
| | Performance Guarantee:\$! | 525.00 |

- Each subsequent Final Inspection for the release of the Performance Guarantee:.....\$300.00
- First Final Inspection for the release of the Maintenance Guarantee: \$300.00
- Each subsequent Final Inspection for the release of the Maintenance Guarantee:\$225.00

All fees are non-refundable. Fees for each first inspection (Performance and Maintenance) are paid prior to permit issuance.

UTILITY, FACILITY AND SPECIAL EVENT FEES

Revised November 10, 2015 Effective December 1, 2015

APPLICATION FEES

The following fees shall be required for each new installation or maintenance:*:

| | <u>Item</u> | Application Fee |
|---|--|-----------------------|
| • | Utility (and related equipment) including, but not limited to: Coaxial Cable Fiber Optic Cable Electric Cable Telecommunication Cable Wireless Communications Equipment Gas Line | \$850.00 per Utility |
| • | Facility (and related equipment) including, but not limited to: Sidewalk Bike path RRFB/ Crosswalk Sanitary or Storm Sewer Line Water Main/ Water Line Street Lighting Trees Public Transportation Shelter | \$850.00 per Facility |
| • | Traffic Signal Modifications | \$500.00 |
| • | Single Service Tap-On(for single family house) | \$100.00 |
| • | Municipal Signs | . No Fee |
| • | Special Event | . \$50.00 |

- - * Fees may be waived for Minor Maintenance (see Lake County, IL Code of Ordinances Chapter 91, Section 91.075 Maintenance of Utility and Facilities).

CHARGES

Open Cut Charge

- \$700.00
- +\$25/ft² of opened pavement
- An inspection charge of \$350.00 will be assessed for each open cut charge.
- Open cut charge does not apply for Major Maintenance, Minor Maintenance, and Emergency Repair Work performed by a Municipality, Special District or other unit of local government.
- Open cut charge for an individual permit shall not exceed \$10,000.

FINAL INSPECTIONS

The following fees shall be required for a Final Inspection:

- First Final Inspection for the release of the Performance Guarantee......\$350.00
- Each subsequent Final Inspection for the release of the Performance Guarantee\$200.00

Additional Notes:

- Typically, a Permit will be required for sidewalks, street lighting, bike paths, watermains/water lines, sanitary sewer lines, storm sewer lines, culvert crossings, and any other municipally-owned utility or facility.
- No fee will be charged if the work is performed on a municipally-owned facility and the work is performed with municipal employees.
- All fees are non-refundable.